STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

METRIC

STATION OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS	NEW AND SALVAGED SIGNS				EXIST. POST		NEW SIGN POSTS															REMARKS	SIGN DETAIL ON SHEET NUMBER	DETAIL STD. SHEET NUMBER
									FLANGED CHANNEL KG/M				TUBULAR ALUMINUM		FOUND-ATION	SQUARE STEEL (mm)			ANZIOR	SLEEVE	W SHAPED STEEL					
																44	50	63								
																kg/m										
																3.4	3.9	5.0			POST SIZE	WEIGHT	FTG. SIZE 600	FTG. SIZE 750	SIGN FRAME	
			''A''	''B''	SALV. SIGN	SALV. T.I.S.	RET.	SALV.	NO. OF POSTS	I.7	3.0	4.5	75 0	100 0												
VT ROUTE 15 ESSEX 9+460.0, LT. MM 0589	STOP 0150 0406 0589	750 X 750 150 X 120	0.56		~~2~~ 1				1			4.0 X						X							NEW ~~SALVAGED~~ SIGNS TO BE MOUNTED BACK TO BACK ON NEW POST. NEW MILE MARKER PAID AS SALVAGE	- -	- -
9+492.0, LT.	LEGAL LOAD LIMIT 24,000 POUNDS	600 X 750	0.45		~~1~~				1			4.0 X						X							SALVAGED SIGN TO BE MOUNTED ON NEW POST.	-	-
9+585.0, RT.	ONE WAY	900 X 300	0.27						1			4.3 X						X							"ONE WAY" SIGNS TO BE INSTALLED AS DETAILED ON VAOT STANDARD E-120.		E-142
	ONE WAY	900 X 300	0.27		1																					E-142
	LEGAL LOAD LIMIT 24,000 POUNDS	600 X 750	0.45																							E-141
9+605.0, RT.	ONE WAY	900 X 300	0.27						1			3.7 X						X							"ONE WAY" SIGNS TO BE INSTALLED AS DETAILED ON VAOT STANDARD E-120.		E-142
	ONE WAY	900 X 300	0.27																							E-142
MM 0597	0150 0406 0597	150 X 120			1																				NEW MILE MARKER PAID AS SALVAGE	-	-
10+303.0, RT.	LEGAL LOAD LIMIT 24,000 POUNDS	600 X 750	0.45						1			4.0 X						X								E-141
10+340.0, RT. MM 0642	STOP 0150 0406 0642	750 X 750 150 X 120	0.56		1				1			4.0 X						X							NEW ~~SALVAGED~~ SIGN TO BE MOUNTED BACK TO BACK WITH NEW SIGN ON NEW POST. NEW MILE MARKER PAID AS SALVAGE	-	E-143 -
10+447.0, RT.	ONLY	750 X 750	0.56						1			4.3 X						X								E-145A
10+500.0, RT. MM 0653	STOP 0150 0406 0653	750 X 750 150 X 120	0.56		1				1			4.3 X						X							NEW ~~SALVAGED~~ SIGN TO BE MOUNTED BACK TO BACK WITH NEW SIGN ON NEW POST. NEW MILE MARKER PAID AS SALVAGE	-	E-143 -
10+500.0, RT.			0.45		1				1			4.3 X						X							SALVAGED SIGN TO BE MOUNTED ON NEW POST.	-	-
11+695.0, RT.	LEGAL LOAD LIMIT 24,000 POUNDS	600 X 750	0.45						1			4.3 X						X								E-141
11+722.0, RT.	STOP 0150 0406 0730	750 X 750	0.56		1				1			4.3 X						X							SALVAGED SIGN TO BE MOUNTED BACK TO BACK WITH NEW SIGN ON NEW POST.	-	E-143 -
11+913.0, LT. MM 0741	STOP 0150 0406 0744	750 X 750 150 X 120	0.56		1				1			4.0 X						X							SALVAGED SIGN TO BE MOUNTED BACK TO BACK WITH NEW SIGN ON NEW POST. NEW MILE MARKER PAID AS SALVAGE	-	E-143 -
10+513.0 RT. MM 0653	STOP	750 X 750	0.56						1			4.3 X													NEW SIGN TO BE MOUNTED ON RIGHT SIDE OF SLIP RAMP		
11+303.0 LT. MM 0704	0150 0406 0704	150 X120	0.03																						NEW SIGN TO BE MOUNTED BACK TO BACK WITH EXISTING SIGN		
10+303.0 RT.	DEAD END				1							4.3 X													SIGN NEEDED TO BE RELOCATED TO INSTALL NEW LLL		
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."		SHEET TOTALS	m^2 6.83 ~~5.23~~	m^2	EA. 8 ~~9~~	m^2			m 58.1 ~~55.2~~	m	m ~~55.2~~	KG	KG	EA.	m 55.2	m	m ~~55.2~~	EA	KG	EA.	EA.			NOTE: ALL DIMENSIONS IN MILLIMETERS EXCEPT WHERE OTHERWISE INDICATED		

ARCHIVED IN DPR

TRAFFIC SIGN SUMMARY #1

SURVEYED BY N/A DATE N/A
DESIGN BY JLL/GAE DATE 11/96
DRAWN BY W-M DATE 11/96
DESIGN FILE NO. /pave/92b22l/pb22l.dgn
IPARM FILE pb22ltsl.1 DATE PLOTTED 28-SEP-2009 09
PROJ. NAME ESSEX-UNDERHILL
PROJ. NO. STP 9469(1)S
SHEET 29 OF 40 SHEETS