STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

Pilot Metric

STATION OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS	NEW AND SALVAGED SIGNS				EXIST. POST		NEW SIGN POSTS															REMARKS	SIGN DETAIL ON SHEET NUMBER	DETAIL STD. SHEET NUMBER
									FLANGED CHANNEL KG/M				TUBULAR ALUMINUM		FOUND-ATION	SQUARE STEEL (mm)			ANZIOR	SLEEVE	W SHAPED STEEL					
																44	50	63					FTG. SIZE		SIGN FRAME	
			"A"	"B"	SALV. SIGN	SALV. T.I.S.	RET.	SALV.	NO. OF POSTS	I.7	3.0	4.5	75 0	I00 0		kg/m 3.4	3.9	5.0			POST SIZE	WEIGHT	600	750			
VT ROUTE 15 ESSEX 11+933.0, LT.	LEGAL LOAD LIMIT 24,000 POUNDS				1				1			4.3 X						X							SALVAGED SIGN TO BE MOUNTED ON NEW POST.	-	-
12+742.6, LT. MM 0792	STOP 0150 0406 0792	150 X 120			2				1			4.0 X						X							SALVAGED SIGNS TO BE MOUNTED BACK TO BACK ON NEW POST NEW MILE MARKER PAID AS SALVAGE	- -	- -
12+744.0, LT.	LEGAL LOAD LIMIT 24,000 POUNDS / NO THRU TRUCKS	600 X 750 600 X 750	0.45 0.45						1			5.0 X						X							INSTALL NEW LEGAL LOAD LIMIT OVER NEW NO THRU TRUCKS.	35	
JERICHO 0+146.9, LT. MM 0009	STOP 0150 0409 0009	750 X 750 150 X 120	0.56		1 1				1			4.3 X						X							~~SALVAGED~~ NEW SIGN TO BE MOUNTED BACK TO BACK WITH NEW SIGN ON NEW POST NEW MILE MARKER PAID AS SALVAGE	-	E-143 -
0+154.9, LT.	LEGAL LOAD LIMIT 24,000 POUNDS	600 X 750	0.45						1			4.3 X						X									E-141
0+442.5, LT.	STOP 0150 0409 0026	750 X 750	0.56		1				1			4.3 X						X							SALVAGED SIGN TO BE MOUNTED BACK TO BACK WITH NEW SIGN ON NEW POST	-	E-143 -
0+450.5, LT.	LEGAL LOAD LIMIT 24,000 POUNDS	600 X 750	0.45						1			4.0 X						X									E-141
0+710.0, RT.	LEGAL LOAD LIMIT 24,000 POUNDS	600 X 750	0.45						1			4.3 X						X									E-141
0+716.0, RT. MM 0047	STOP 0150 0409 0047	750 X 750 150 X 120	0.56		~~1~~ 2				1			4.3 X						X							~~SALVAGED~~ NEW SIGNS TO BE MOUNTED BACK TO BACK ON NEW POST. NEW MILE MARKER PAID AS SALVAGE	- -	- -
0+721.0, RT.	JERICHO CENTER → / ← JERICHO CENTER	1350 X 200 1350 X 200	0.27 0.27						2 Ø3.7 ~~2~~ 2 Ø3.7			7.4 X 7.4						X							ORIENT FOR EASTBOUND AND WESTBOUND NEW SIGNS TO BE MOUNTED BACK TO BACK ON NEW POST. OR MAY HAVE TO BE SEPERATED FOR BETTER ORIENTATION		E-123 E-123
0+721.0, RT.	STOP	750 X 750	0.56						1			4.3 X						X									E-143
	3-WAY				1																				SALVAGED SIGN TO BE MOUNTED BELOW NEW SIGN ON NEW POST.	-	-
0+727.0, RT.	LEGAL LOAD LIMIT 24,000 POUNDS / YIELD	600 X 750 900 X 900	~~0.45~~ 0.45 0.81						1			4.3 X						X							MOUNT "YIELD" SIGN BACK TO BACK WITH NEW LEGAL LOAD SIGN		E-141
0+734.0, RT.	YIELD	900 X 900	0.81						1			4.3 X						X									E-146
0+867.0, LT.	STOP 0150 0409 0055	750 X 750 150 X 200	0.56 0.03						1			5.0 X						X									E-143
0+878.0, LT.	LEGAL LOAD LIMIT 24,000 POUNDS	600 X 750	0.45		~~1~~				1			4.3 X						X							SALVAGED SIGN TO BE MOUNTED ON NEW POST.	-	-
12+740 +/- LT.	REDUCED SPEED AHEAD				1				1			3.7 X													INSTALL SALVAGED SIGN A MINIMUM OF 33M FROM LLL		
0+442.5 LT.	LAWRENCE HGTS				1				1			3.7 X													REMOVE AND SALVAGE STREET SIGN ONTO NEW POST AS PER STD.		
11+933.0 LT.	NAYLOR RD.				1							3.7 X															
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."		SHEET TOTALS	m^2 8.14 ~~5.84~~	m^2	EA. 10 ~~9~~	m^2			m	m	m ~~69~~	KG	KG	EA.	m	m	m ~~69~~		EA	KG	EA.	EA.					
										86.9 ~~69~~						~~69~~										

ARCHIVED IN DPR

NOTE: ALL DIMENSIONS IN MILLIMETERS EXCEPT WHERE OTHERWISE INDICATED

TRAFFIC SIGN SUMMARY #2

SURVEYED BY N/A DATE N/A
DESIGN BY JLL/GAE DATE 11/96
DRAWN BY W-M DATE 11/96
DESIGN FILE NO. /pave/92b22l/pb22l.dgn
IPARM FILE pb22lts2.i DATE PLOTTED 28-SEP-2009 09
PROJ. NAME ESSEX-UNDERHILL
PROJ. NO. STP 9469(1)S
SHEET 30 OF 40 SHEETS