STATE OF VERMONT AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	FOUND-ATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL SIGN ID CODE	STD. SHEET NUMBER
												OPTION ITEMS																								
1+016 LT ~~1+008.0 LT~~	ONLY		900	750	0.68		*				1			3.98 *																				NEW LOCATION STA 1+016 LT WESTON DID NOT REMOVE SIGN. NEW SIGN INSTALLED.	VR-922	E145AM
1+080.1RT	SALVAGED MILE MARKER 0150 0406 0400		750	750	0.56		1				1			4.32 *																				WESTON REMOVED & SALVAGED EXSTING MILE MARKER	W1-2R	E-151M
1+040.0 LT	JCT VERMONT 289						* 1 * 1				1			4.17 *																				REMOVE BY WESTON SALVAGE BY WESTON		
1+090.4 LT			900	900	0.81						1			4.61 *																					W6-1	E-151M
1+029.8 RT ~~1+111.1 RT~~	Essex Country Club S; Alliance Church S; New Horizons Horse Farm N						* 1 * 1 * 1				2			4.32 * 4.34																				REMOVAL BY VTRANS SALVAGE BY WESTON		
1+145.8 RT			900	900	0.81						2			4.03 * 4.07																					W3-3	E-152M
1+180.0 LT	SPEED LIMIT 40		600	750	0.45						1			4.14 *																					R2-1	E-142M
1+212.3 RT	ONLY		900	750	0.68						1			3.81 *																					VR-922	E-145AM
1+285.0 LT	LEFT TURN YIELD ON GREEN		600	750																														SIGN SHALL BE MOUNTED ON MAST ARM #1 PAYMENT SUBSIDIARY TO 678.15 MOD. (OLD STAGE ROAD)	R10-12	E-140M
1+307.5 LT	LEFT TURN YIELD ON GREEN		600	750																														SIGN SHALL BE MOUNTED ON MAST ARM #4 PAYMENT SUBSIDIARY TO 678.15 MOD. (OLD STAGE ROAD)	R10-12	E-140M
1+345.8 RT	SPEED LIMIT 40		600	750	0.45						1			3.84 *																					R2-1	E-142M
1+352.4 LT	ONLY		900	750	0.68						1			3.90 *																					VR-922	E-145AM
1+410 RT ~~1+379.3 RT~~	Butler's Restaurant & Tavern at the Inn S; J. Summerville Dentist S; Alan Ashe Insurance Agent S						* 1 * 1 * 1				2			4.42 *																				REMOVAL BY VTRANS SALVAGE BY WESTON		
															m	m	m		EA	kg	kg	kg		kg	kg	kg	kg									
TOTALS					m² ~~4.44~~ 5.12	m²	EA. 9	m²				m ~~45.9~~ 58.72			m					kg			EA.	kg				EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: ESSEX
PROJECT NUMBER: STP 030-1(17)S

PLOT FILE NAME: zstp030-1(17)sfrm.dgn
L&D PROJECT NUMBER: 00-074
DESIGNED BY: LAMOUREUX & DICKINSON CONSULTING ENGINEERS, INC.
DRAWN BY: PLC
CHECKED BY: RJD
SHEET 25