

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							112				112		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				* N.A.B.I. - NOT A BID ITEM
							200				200		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
							400				400		HR	FLAGGERS	630.15				
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
							1				1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
							1100				1100		LF	DURABLE 4 INCH WHITE LINE, POLYUREA	646.404				
							1100				1100		LF	DURABLE 4 INCH YELLOW LINE, POLYUREA	646.414				
							50				50		LF	DURABLE 24 INCH STOP BAR	646.480				
							8				8		EACH	DURABLE LETTER OR SYMBOL	646.490				
							130				130		SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85				
								810			810		SY	GEOTEXTILE UNDER STONE FILL	649.31				
								66			66		SY	GEOTEXTILE FOR SILT FENCE	649.51				
								95			95		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
								20			20		LB	SEED	651.15				
								10			10		LB	SEED, WINTER RYE	651.17				
								100			100		LB	FERTILIZER	651.18				
								0.5			0.5		TON	AGRICULTURAL LIMESTONE	651.20				
								0.5			0.5		TON	HAY MULCH	651.25				
								130			130		CY	TOPSOIL	651.35				
								380			380		SY	GRUBBING MATERIAL	651.40				
								1			1		LS	EPSC PLAN	652.10				
								50			50		HR	MONITORING EPSC PLAN	652.20				
								1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
								400			400		SY	TEMPORARY EROSION MATTING	653.20				
								50			50		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25				
								30			30		CY	VEHICLE TRACKING PAD	653.35				
								2			2		EACH	INLET PROTECTION DEVICE, TYPE I	653.40				
								100			100		LF	BARRIER FENCE	653.50				
								700			700		LF	PROJECT DEMARCATION FENCE	653.55				
							6.08				6.08		SF	TRAFFIC SIGNS, TYPE A	675.20				
								35			35		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
								14			14		EACH	REMOVING SIGNS	675.50				
								7			7		EACH	ERECTING SALVAGED SIGNS	675.60				
								9			9		EACH	SETTING SALVAGED POSTS	675.61				
								1			1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50				
								10			10		EACH	SPECIAL PROVISION (CPM SCHEDULE)	900.620				
								1			1		LS	SPECIAL PROVISION (TRAFFIC CONTROL, ALL-INCLUSIVE)	900.645				

PROJECT NAME: WARDBORO
 PROJECT NUMBER: BRF 013-1(15)
 FILE NAME: s92b283qs.dgn PLOT DATE: 21-JUL-2015
 PROJECT LEADER: C. CARLSON DRAWN BY: D. KARABEGOVIC
 DESIGNED BY: D. PETERSON CHECKED BY: D. PETERSON
 QUANTITY SHEET 2 SHEET 7 OF 51