

# QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
								ROADWAY	BRIDGE	FULL C&E	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
									1		1		LS	SHORING SUPERSTRUCTURE	502.10				
									1		1		LS	CONTAINMENT & ENVIRONMENTAL PROTECTION, FIELD	513.36				
									1		1		LS	SURFACE PREPARATION, FIELD (1 TON)	513.41				
									1		1		LS	MAINTENANCE OF STRUCTURES AND APPROACHES	527.10				
								1			1		EACH	REMOVAL OF STRUCTURE (2100 SF - EST.)	529.15				
									1		1		EACH	PARTIAL REMOVAL OF STRUCTURE	529.20				
									1		1		CY	CONCRETE, CLASS LW	541.40				
									3		3		SY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS I	580.10				
								40			40		LF	TEMPORARY TRAFFIC BARRIER	621.90				
								260			260		LF	REMOVE AND RESET TEMPORARY TRAFFIC BARRIER	621.95				
								400			400		HR	FLAGGERS	630.15				
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
										1	1		LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25				
								1			1		LS	MOBILIZATION/DEMobilIZATION	635.11				
								1			1		LS	TRAFFIC CONTROL	641.10				
									23470		23470		LB	SPECIAL PROVISION (INSTALLATION OF STRUCTURAL STEEL)(FPQ)	900.635				
									260		260		LF	SPECIAL PROVISION (MAINTENANCE AND REMOVAL OF TEMPORARY TRAFFIC BARRIE	900.640				
									2290		2290		SF	SPECIAL PROVISION (INSTALLATION OF GRID DECK)(FPQ)	900.670				