QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

APPROXIMATE SUMMARY OF QUANTITIES

SHEFFIELD-GLOVER STP 9419(11)S	BROWNINGTON-CHARLESTON STP 9426(11)S	GLOVER STP 9435(11)S	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
1			1	CY	TRENCH EXCAVATION OF EARTH (NOT A BID ITEM)	204.20	-
2200	1800	1000	5000	SY	COLD PLANING-BIT. PAVEMENT	210.10	-
		775	775	TON	SUBBASE OF CRUSHED GRAVEL (FINE GRADED)	301.28	-
114500	104000		218500	SY	RECLAIMED STABILIZED BASE	310.20	-
115	105		220	MGL	WATER FOR STABILIZATION	310.23	-
4900	4500		9400	TON	CRUSHED AGGREGATE FOR STABILIZATION	310.24	-
2700	1775	700	5175	TON	AGGREGATE SHOULDERS	402.12	-
150	135	65	350	CWT	EMULSIFIED ASPHALT	404.65	-
22400	26200	3100	51700	TON	MEDIUM DUTY BIT. CONCRETE PAVEMENT	406.27	-
1			1	LS	PRICE ADJUSTMENT - ASPHALT CEMENT (NOT A BID ITEM)	406.50	-
450		205	655	LF	REMOVAL OF EXISTING RAILING	525.10	-
125			125	LF	BRIDGE RAIL - HEAVY DUTY STEEL BEAM FASCIA MOUNTED (MOD 1)	525.41	-
		100	100	LF	BRIDGE RAIL - HEAVY DUTY STEEL BEAM FASCIA MOUNTED (MOD.3)	525.41	
40		40	80	LF	15" CSP .064 (2-2⅔ X ½)	601.0010	
190	175	50	415	HR	POWER GRADER RENTAL	608.15	EST.
190	175	50	415	HR	ALL PURP. EXCAVATOR RENTAL, TYPE I	608.25	EST.
120	110	30	260	HR	POWER BROOM RENTAL	608.30	EST.
190	175	50	415	HR	TRUCK RENTAL	608.37	EST.
190	175	50	415	HR	LOADER RENTAL TYPE I	608.40	EST.
	50		50	TON	BITUMINOUS CONCRETE GUTTERS & TRAFFIC ISLANDS	616.47	
12	8	15	35	EA	YIELDING MARKER POST	619.17	EST.
5600	1000	850	7450	LF	STEEL BEAM GUARD RAIL	621.20	-
150	100	100	350	LF	STEEL BEAM GUARD RAIL W/ 8' STEEL POSTS (MOD)	621.20	-
300		130	430	LF	HEAVY DUTY STEEL BEAM GUARD RAIL	621.21	-
40	8	11	59	EA	BREAKAWAY CABLE TERMINAL	621.50	-
14		3	17	EA	ANCHOR FOR STEEL BEAM GUARD RAIL	621.60	-
5150	925	160	6235	LF	REMOVAL AND DISPOSAL OF GUARD RAIL	621.80	-
20		20	40	EA	REMOVAL AND DISPOSAL OF GUIDE POSTS	621.81	-
300	300	100	700	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
1130	1040	300	2470	HR	FLAGGERS	630.15	EST.
1			1	LS	FIELD OFFICE - ENGINEERS	631.0	
0.50	0.40	0.10	1	LS	TESTING EQUIPMENT - CONCRETE	631.16	-
0.50	0.40	0.10	1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	-
1			1	LS	FIELD OFFICE TELEPHONE (NOT A BID ITEM)	631.25	
520	520	520	1560	HR	EMPLOYEE TRAINEESHIP	634.10	EST.
0.50	0.40	0.10	1	LS	MOBILIZATION	635.10	-
450	400	100	950	HR	TRAFFIC OFFICER W/ FLASHING LIGHT	641.35	EST.
78500	72100	17800	168400	LF	DURABLE 4'' WHITE LINE	646.40	-
73100	63300	16800	153200	LF	DURABLE 4'' YELLOW LINE	646.41	-
	125		125	LF	DURABLE 8'' WHITE LINE	646.42	-
60	75	15	150	LF	DURABLE 24'' STOP BAR	646.46	-
29	25	4	58	EA	DURABLE LETTER OR SYMBOL	646.50	-
26			26	LF	DUR. CROSSWALK MKG. W/DIAG. LINES	646.51	-
78500	72100	17800	168400	LF	TEMPORARY 4'' WHITE LINE	646.60	EST.
73100	63300	16800	153200	LF	TEMPORARY 4'' YELLOW LINE	646.61	EST.
	125		125	LF	TEMPORARY 8'' WHITE LINE	646.62	-
60	75	15	150	LF	TEMPORARY 24'' STOP BAR	646.66	EST.
1000	1000	250	2250	EA	LINE STRIPING TARGETS	646.73	EST.
40	40	40	120	LB	SEED	651.15	EST.
250	250	250	750	LB	FERTILIZER	651.18	EST.
1	1	1	3	TON	AGRICULTURAL LIMESTONE	651.20	EST.
1	1	1	3	TON	HAY MULCH	651.25	EST.
25	25	25	75	CY	TOPSOIL	651.35	EST.
46			46	SF	TRAFFIC SIGNS, TYPE A	675.20	-
228			228	LB	FLANGED CHANNEL SIGN POST	675.30	-
5			5	EA	REMOVING SIGNS	675.50	-
1			1	EA	ERECTING SALVAGED SIGNS	675.60	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

STATIONS FROM	STATIONS TO	PAVEMENT WIDTHS			EQUATIONS +	EQUATIONS -	FEET	MILES	REMARKS
TOTALS									

9-OCT-1995
/pave/92c176/pc76.dgn

PROJECT NAME SHEFFIELD-GLOVER, BROWNINGTON-CHARLESTON & GLOVER
PROJECT NUMBER STP 9419(11)S, STP 9426(11)S & STP 9437(11)S