QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

APPROXIMATE SUMMARY OF QUANTITIES

EMPLOYEE TRAINEESHIP	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
		1	1	CY	TRENCH EXCAVATION OF EARTH (NOT A BID ITEM)	204.20	-
		2200	2200	SY	COLD PLANING-BIT. PAVEMENT	210.10	27
		114500	114500	SY	RECLAIMED STABILIZED BASE	310.20	314
		115	115	MGL	WATER FOR STABILIZATION	310.23	-
		4900	4900	TON	CRUSHED AGGREGATE FOR STABILIZATION	310.24	-
		2700	2700	TON	AGGREGATE SHOULDERS	402.12	19
		150	150	CWT	EMULSIFIED ASPHALT	404.65	3
		22400	22400	TON	MEDIUM DUTY BIT. CONCRETE PAVEMENT	406.27	5
		1	1	LS	PRICE ADJUSTMENT - ASPHALT CEMENT (NOT A BID ITEM)	406.50	-
	450		450	LF	REMOVAL OF EXISTING RAILING	525.10	10
	125		125	LF	BRIDGE RAIL HEAVY DUTY STEEL BEAM FASCIA MOUNTED (MOD 1)	525.41	-
		40	40	LF	15'' CSP .064 (2-2/3 X 1/2)	601.0010	EST.
		190	190	HR	POWER GRADER RENTAL	608.15	EST.
		190	190	HR	ALL PURP. EXCAVATOR RENTAL, TYPE I	608.25	EST.
		120	120	HR	POWER BROOM RENTAL	608.30	EST.
		190	190	HR	TRUCK RENTAL	608.37	EST.
		190	190	HR	LOADER RENTAL TYPE I	608.40	EST.
		12	12	EA	YIELDING MARKER POST	619.17	EST.
		5600	5600	LF	STEEL BEAM GUARD RAIL	621.20	75
		150	150	LF	STEEL BEAM GUARD RAIL W/ 8' STEEL POSTS (MOD)	621.20	-
	300		300	LF	HEAVY DUTY STEEL BEAM GUARD RAIL	621.21	15
	5	35	40	EA	BREAKAWAY CABLE TERMINAL	621.50	-
	3	11	14	EA	ANCHOR FOR STEEL BEAM GUARD RAIL	621.60	-
		5150	5150	LF	REMOVAL AND DISPOSAL OF GUARD RAIL	621.80	38
		20	20	EA	REMOVAL AND DISPOSAL OF GUIDE POSTS	621.81	2
		300	300	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
		1130	1130	HR	FLAGGERS	630.15	EST.
		1	1	LS	FIELD OFFICE - ENGINEERS	631.10	
		0.50	0.50	LS	TESTING EQUIPMENT - CONCRETE	631.16	-
		0.50	0.50	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	-
		1	1	LS	FIELD OFFICE TELEPHONE (NOT A BID ITEM)	631.25	
520			520	HR	EMPLOYEE TRAINEESHIP	634.10	EST.
		0.50	0.50	LS	MOBILIZATION	635.10	-
		450	450	HR	TRAFFIC OFFICER W/ FLASHING LIGHT	641.35	EST.
		78500	78500	LF	DURABLE 4'' WHITE LINE	646.40	88
		73100	73100	LF	DURABLE 4'' YELLOW LINE	646.41	18
		60	60	LF	DURABLE 24'' STOP BAR	646.46	6
		29	29	EA	DURABLE LETTER OR SYMBOL	646.50	-
		26	26	LF	DUR. CROSSWALK MKG. W/DIAG. LINES	646.51	-
		78500	78500	LF	TEMPORARY 4'' WHITE LINE	646.60	88
		73100	73100	LF	TEMPORARY 4'' YELLOW LINE	646.61	18
		60	60	LF	TEMPORARY 24'' STOP BAR	646.66	6
		1000	1000	EA	LINE STRIPING TARGETS	646.73	12
		40	40	LB	SEED	651.15	EST.
		250	250	LB	FERTILIZER	651.18	EST.
		1	1	TON	AGRICULTURAL LIMESTONE	651.20	EST.
		1	1	TON	HAY MULCH	651.25	EST.
		25	25	CY	TOPSOIL	651.35	EST.
		46	46	SF	TRAFFIC SIGNS, TYPE A	675.20	-
		228	228	LB	FLANGED CHANNEL SIGN POST	675.30	-
		5	5	EA	REMOVING SIGNS	675.50	-
		1	1	EA	ERECTING SALVAGED SIGNS	675.60	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING - BITUMINOUS PAVEMENT
217	SY	BEGINNING OF PROJECT
567	SY	SHEFFIELD MM 2.310 BRIDGE #16
587	SY	SHEFFIELD MM 2.950 BRIDGE #17
273	SY	TOWN HIGHWAYS
529	SY	END OF PROJECT
27	SY	ROUNDING
2200	SY	TOTAL
		MEDIUM DUTY BITUMINOUS CONCRETE PAVEMENT
9516	TON	MAINLINE - WEARING COURSE
12688	TON	MAINLINE - BINDER COURSE
154	TON	TOWN HIGHWAYS
37	TON	APPROACHES AND DRIVES
5	TON	ROUNDING
22400	TON	TOTAL
		REMOVING SIGNS
1	EA	SHEFFIELD MM 1.613 RT
1	EA	SHEFFIELD MM 1.670 RT
1	EA	SHEFFIELD MM 1.687 LT
1	EA	SHEFFIELD MM 1.738 LT
1	EA	SHEFFIELD MM 3.687 RT, TH 3
5	EA	TOTAL
		FLANGED CHANNEL SIGN POSTS
42	LB	SHEFFIELD MM 1.613 RT
51	LB	SHEFFIELD MM 1.670 RT
51	LB	SHEFFIELD MM 1.675 LT
42	LB	SHEFFIELD MM 1.738 LT
42	LB	SHEFFIELD MM 3.707 RT, TH 3
228	LB	TOTAL
		TRAFFIC SIGNS TYPE A
9	SF	SHEFFIELD MM 1.613 RT
9	SF	SHEFFIELD MM 1.670 RT
5	SF	SHEFFIELD MM 1.670 RT
5	SF	SHEFFIELD MM 1.675 LT
9	SF	SHEFFIELD MM 1.675 LT
9	SF	SHEFFIELD MM 1.738 RT
46	SF	TOTAL
		ERECTING SALVAGED SIGNS
1	EA	SHEFFIELD MM 3.707 RT, TH 3
1	EA	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

STATIONS FROM	STATIONS TO	PAVEMENT WIDTHS			EQUATIONS +	EQUATIONS -	FEET	MILES	REMARKS
TOTALS									

9-OCT-1995
/pave/92c176/pc176.dgn

PROJECT NAME SHEFFIELD-GLOVER
PROJECT NUMBER STP 9419(11)S

SHEET 3 OF SHEETS
SHEET 9 OF 44