# ITEM DETAIL SUMMARY SHEET

| MILE MARKER | MILE MARKER | POS. | DROP INLET | LAT. DITCH | CLEAN INLET DITCH | CLEAN OUTLET DITCH | EARTH BORROW | TIMBER CURB | STONE FILL | NEW PIPE D | NEW PIPE L | NEW PIPE TH/CL | CSPES D | CSPES TH | CSPES QTY | FLUSH PIPES 0-24" | FLUSH PIPES > 24" | 6" UND. | CONC. CL B | REINF. STEEL | GRATE TYPE EA | CHAN ELEV EA | REHAB DI EA | GUARDRAIL ITEMS MOD. 621.20 | 620.20 | 621.21 | 621.50 | 621.60 | 621.80 | 621.81 | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| SHEFFIELD | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 4.757 | 4.800 | LT. | | | | | | | | | | | | | | | | | | | | | | 200 | | | 1 | 1 | 221 | | REMOVE EXIST. 2 CABLE GUARDRAIL ON WOOD POSTS, INSTALL A 16'R END TERMINAL AT EXISTING DRIVE, 200 LF OF NEW STEEL BEAM GUARDRAIL WITH STEEL POSTS, AND A BCT AT MM 4.800 |
| 5.036 | 5.055 | LT. | | | | | | | | | | | | | | | | | | | | | | 50 | | | 2 | | 90 | | REMOVE EXISTING 2 CABLE GUARDRAIL ON WOOD POSTS, INSTALL A BCT AT MM 5.036, 50 LF OF NEW STEEL BEAM GUARDRAIL WITH STEEL POSTS, AND A BCT AT MM 5.055, LT. |
| 5.040 | 5.045 | RT. | | | | | | | | | | | | | | | | | | | | | | | | | | | | 4 | REMOVE EXISTING WOOD GUIDE POSTS. |
| 5.111 | 5.173 | LT. | | | | | | | | | | | | | | | | | | | | | | 275 | | | 2 | | 328 | | REMOVE EXISTING 2 CABLE GUARDRAIL ON WOOD POSTS, INSTALL A BCT AT MM 5.111, 275 LF OF NEW STEEL BEAM GUARDRAIL WITH STEEL POSTS AND A BCT AT MM 5.173, RT. |
| 5.220 | 5.244 | LT. | | | | | | | | | | | | | | | | | | | | | | 75 | | | 2 | | 120 | | REMOVE EXISTING 2 CABLE GUARDRAIL ON WOOD POSTS, INSTALL A BCT AT MM 5.220, LT., 75 LF OF NEW STEEL BEAM GUARDRAIL WITH STEEL POSTS AND A BCT AT MM 5.244, LT. |
| 5.228 | 5.242 | RT. | | | | | | | | | | | | | | | | | | | | | | 50 | | | 2 | | 23 | | REMOVE EXISTING 2 CABLE GUARDRAIL ON WOOD POSTS, INSTALL A BCT AT MM 5.228, 50 LF OF NEW STEEL BEAM GUARDRAIL WITH STEEL POSTS AND A BCT AT MM 5.242. |
| 5.308 | 5.332 | LT. | | | | | | | | | | | | | | | | | | | | | | 75 | | | 2 | | 112 | | REMOVE EXISTING 2 CABLE GUARDRAIL ON WOOD POSTS, INSTALL A BCT AT MM 5.308, 75 LF OF NEW STEEL BEAM GUARDRAIL WITH STEEL POSTS AND A BCT AT MM 5.332. |
| 5.820 | 5.924 | LT. | | | | | | | | | | | | | | | | | | | | | | 500 | | | 2 | | 498 | | REMOVE EXISTING 2 CABLE GUARDRAIL ON WOOD POSTS, INSTALL A BCT AT MM 5.820 LT., 500 LF OF NEW STEEL BEAM GUARDRAIL WITH STEEL POSTS, AND A BCT AT MM 5.924. |
| 6.013 | 6.088 | LT. | | | | | | | | | | | | | | | | | | | | | | 375 | | | 1 | 1 | 335 | | REMOVE EXISTING 2 CABLE GUARDRAIL ON WOOD POSTS, INSTALL A BCT AT MM 6.013, 375 LF OF NEW STEEL BEAM GUARDRAIL WITH STEEL POSTS. WITH A 15'R END TERMINAL AT MM 6.088. |
| 6.076 | 6.095 | RT. | | | | | | | | | | | | | | | | | | | | | | 50 | | | 2 | | 16 | | REMOVE EXISTING 2 CABLE GUARDRAIL ON WOOD POSTS, INSTALL A BCT AT MM 6.076 AND 6.095 AND INSTALL 50 LF OF NEW STEEL BEAM GUARDRAIL WITH STEEL POSTS. |
| 7.480 | 7.508 | LT. | | | | | | | | | | | | | | | | | | | | | | 100 | | | 2 | | 135 | | INSTALL A BCT AT MM 7.480 AND MM 7.508, LT. AND 100 LF OF NEW STEEL BEAM GUARDRAIL WITH STEEL POSTS. |
| 7.480 | 7.499 | RT. | | | | | | | | | | | | | | | | | | | | | | 50 | | | 2 | | 81 | | INSTALL A BCT AT MM 7.480 AND 7.499, RT. AND 50 LF OF NEW STEEL BEAM GUARDRAIL WITH STEEL POSTS. |
| GLOVER | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 0.562 | - | RT.&LT. | | | | | | | | | | | | | | | | | | | | | | | | | | | | 4 | REMOVE EXISTING WOOD GUIDE POSTS, LT. & RT. |
| 1.167 | 1.265 | LT. | | | | | | | | | | | | | | | | | | | | | | | | | | | | 10 | REMOVE EXISTING WOOD GUIDE POSTS |
| SHEET 05 TOTAL | | | | | | | | | | | - | | | | | | | | | | | | | 1800 | - | - | 20 | 2 | 1,959 | 18 | |
| SHEET 04 TOTAL | | | | | | | | | | 15 | 40 | .064 | | | | | | | | | | | | 3575 | 150 | 25 | 15 | 9 | 3,153 | - | |
| SHEET 12 TOTAL | | | | | | | | | | | - | | | | | | | | | | | | | 150 | - | 260 | 5 | 3 | - | - | |
| SUB TOTALS | | | | | | | | | | 15 | 40 | .064 | | | | | | | | | | | | 5525 | 150 | 285 | 40 | 14 | 5,112 | 18 | |
| ROUNDING | | | | | | | | | | | | | | | | | | | | | | | | 75 | - | 15 | - | - | 38 | 2 | |
| PROJECT TOTALS | | | | | | | | | | 15 | 40 | .064 | | | | | | | | | | | | 5600 | 150 | 300 | 40 | 14 | 5150 | 20 | |

ITEM DETAIL SHEET

SURVEYED BY N/A DATE N/A
DRAWN BY DJ DATE 03/93
SQUAD LEADER
DESIGN FILE NO.
IPARM FILE DATE PLOTTED
PROJ. NAME SHEFFIELD-GLOVER
PROJ. NO. STP 9419(1)S
HTA FILE: SHFSUM2
SHEET 05 OF SHEETS