QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

APPROXIMATE SUMMARY OF QUANTITIES

EMPLOYEE TRAINEESHIP	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
		1800	1800	SY	COLD PLANING-BIT. PAVEMENT	210.10	47
		104000	104000	SY	RECLAIMED STABILIZED BASE	310.20	415
		105	105	MGL	WATER FOR STABILIZATION	310.23	1
		4500	4500	TON	CRUSHED AGGREGATE FOR STABILIZATION	310.24	86
		1775	1775	TON	AGGREGATE SHOULDERS	402.12	2
		135	135	CWT	EMULSIFIED ASPHALT	404.65	4
		26200	26200	TON	MEDIUM DUTY BIT. CONCRETE PAVEMENT	406.27	32
		175	175	HR	POWER GRADER RENTAL	608.15	EST.
		175	175	HR	ALL PURP. EXCAVATOR RENTAL, TYPE I	608.25	EST.
		110	110	HR	POWER BROOM RENTAL	608.30	EST.
		175	175	HR	TRUCK RENTAL	608.37	EST.
		175	175	HR	LOADER RENTAL TYPE I	608.40	EST.
		50	50	TON	BIT. CONC. GUTTERS & TRAFFIC ISLANDS	616.47	-
		8	8	EA	YIELDING MARKER POST	619.17	3
		1000	1000	LF	STEEL BEAM GUARD RAIL	621.20	50
		100	100	LF	STEEL BEAM GUARD RAIL W/ 8' STEEL POSTS (MOD)	621.20	EST.
		8	8	EA	BREAKAWAY CABLE TERMINAL	621.50	-
		925	925	LF	REMOVAL AND DISPOSAL OF GUARD RAIL	621.80	20
		300	300	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
		1040	1040	HR	FLAGGERS	630.15	EST.
		0.40	0.40	LS	TESTING EQUIPMENT - CONCRETE	631.16	EST.
		0.40	0.40	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	EST.
520			520	HR	EMPLOYEE TRAINEESHIP	634.10	EST.
		0.40	0.40	LS	MOBILIZATION	635.10	EST.
		400	400	HR	TRAFFIC OFFICER W/ FLASHING LIGHT	641.35	EST.
		72100	72100	LF	DURABLE 4'' WHITE LINE	646.40	74
		63300	63300	LF	DURABLE 4'' YELLOW LINE	646.41	57
		125	125	LF	DURABLE 8'' WHITE LINE	646.42	15
		75	75	LF	DURABLE 24'' STOP BAR	646.46	7
		25	25	EA	DURABLE LETTER OR SYMBOL	646.50	-
		72100	72100	LF	TEMPORARY 4'' WHITE LINE	646.60	74
		63300	63300	LF	TEMPORARY 4'' YELLOW LINE	646.61	57
		125	125	LF	TEMPORARY 8'' WHITE LINE	646.62	15
		75	75	LF	TEMPORARY 24'' STOP BAR	646.66	7
		1000	1000	EA	LINE STRIPING TARGETS	646.73	88
		40	40	LB	SEED	651.15	EST.
		250	250	LB	FERTILIZER	651.18	EST.
		1	1	TON	AGRICULTURAL LIMESTONE	651.20	EST.
		1	1	TON	HAY MULCH	651.25	EST.
		25	25	CY	TOPSOIL	651.35	EST.

DETAILED SUMMARY OF QUANTITIES

COLD PLANING - BITUMINOUS PAVEMENT

QUANTITIES	UNIT	ITEMS
679	SY	BEGINNING OF PROJECT
1074	SY	END OF PROJECT
47	SY	ROUNDING
1800	SY	TOTAL

MEDIUM DUTY BITUMINOUS CONCRETE PAVEMENT

QUANTITIES	UNIT	ITEMS
8776	TON	MAINLINE - WEARING COURSE
17264	TON	MAINLINE - BINDER COURSE
66	TON	TOWN HIGHWAYS
18	TON	APPROACHES AND DRIVES
76	TON	ROUNDING
26200	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

STATIONS FROM	STATIONS TO	PAVEMENT WIDTHS		EQUATIONS +	EQUATIONS -	FEET	MILES	REMARKS
TOTALS								

9-OCT-1995
/pave/92c176/pc176.dgn

PROJECT NAME BROWNINGTON-CHARLESTON
PROJECT NUMBER STP 9426(11)S