# ITEM DETAIL SUMMARY SHEET

| MILE MARKER | MILE MARKER | POS. | DROP INLET | LAT. DITCH | CLEAN INLET DITCH | CLEAN OUTLET DITCH | EARTH BORROW | TIMBER CURB | STONE FILL | NEW PIPE D | NEW PIPE L | NEW PIPE TH/CL | CSPES D | CSPES TH | CSPES QTY | FLUSH PIPES 0-24" | FLUSH PIPES > 24" | 6" UND. | | | GRATE TYPE EA | CHAN ELEV EA | REHAB DI EA | MOD. GUARDRAIL ITEMS 621.20 | 621.20 | 621.21 | 621.50 | 621.505 | 621.60 | 621.80 | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| BROWNINGTON | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 1.391 | 1.448 | LT. | | | | | | | | | | | | | | | | | | | | | | 250 | | | 2 | | | 247 | REMOVE EXISTING 3 CABLE GUARD RAIL ON WOOD POSTS, INSTALL A BCT AT MM 1.391, 250 LF OF NEW STEEL BEAM GUARD RAIL WITH STEEL POSTS AND A BCT AT MM 1.448, LT. |
| CHARLESTON | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 1.929 | 2.038 | RT. | | | | | | | | | | | | | | | | | | | | | | 525 | | | 2 | | | 525 | REMOVE EXISTING 3 CABLE GUARD RAIL ON WOOD POSTS, INSTALL A BCT AT MM 1.929, 525 LF OF NEW STEEL BEAM GUARD RAIL WITH STEEL POSTS AND A BCT AT MM 2.038. |
| 3.195 | 3.228 | RT. | | | | | | | | | | | | | | | | | | | | | | 125 | | | 2 | | | 133 | REMOVE EXISTING 3 CABLE GUARD RAIL ON WOOD POSTS, INSTALL A BCT AT MM 3.195, RT, 125 LF OF NEW STEEL BEAM GUARD RAIL WITH STEEL POSTS, AND A BCT AT MM 3.228, RT. |
| 3.579 | 3.598 | LT. | | | | | | | | | | | | | | | | | | | | | | 50 | | | 2 | | | | INSTALL A BCT AT MM's 3.579 & 3.598, 50 LF OF NEW STEEL BEAM GUARD RAIL WITH STEEL POSTS. |
| TOTAL SHEET 04 | | | | | | | | | | | | | | | | | | | | | | | | 950 | | | 8 | | | 905 | |
| ROUNDING | | | | | | | | | | | | | | | | | | | | | | | | 50 | | | - | | | 20 | |
| PROJECT TOTALS | | | | | | | | | | | | | | | | | | | | | | | | 1000 | | | 8 | | | 925 | |

ITEM DETAIL SHEET

SURVEYED BY N/A DATE N/A
DRAWN BY WBL DATE 03/93
SQUAD LEADER
DESIGN FILE NO.
IPARM FILE DATE PLOTTED
PROJ. NAME BROWNINGTON–CHARLESTON
PROJ. NO. STP 9426(1)S
SHEET 26 OF 44
SHEET 04 OF SHEET