QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

APPROXIMATE SUMMARY OF QUANTITIES

EMPLOYEE TRAINEESHIP	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
		1000	1000	SY	COLD PLANING-BIT. PAVEMENT	210.10	64
		775	775	TON	SUBBASE OF CRUSHED GRAVEL (FINE GRADED)	301.28	10
		700	700	TON	AGGREGATE SHOULDERS	402.12	12
		65	65	CWT	EMULSIFIED ASPHALT	404.65	1
		3100	3100	TON	MEDIUM DUTY BIT. CONCRETE PAVEMENT	406.27	44
	205		205	LF	REMOVAL OF EXISTING RAILING	525.10	-
	100		100	LF	BRIDGE RAILING HEAVY DUTY STEEL BEAM FASCIA MOUNTED (MOD. 3)	525.41	-
		40	40	LF	15'' CSP 0.064 (2-2/3'' X 1/2'')	601.0010	-
		50	50	HR	POWER GRADER RENTAL	608.15	EST.
		50	50	HR	ALL PURP. EXCAVATOR RENTAL, TYPE I	608.25	EST.
		30	30	HR	POWER BROOM RENTAL	608.30	EST.
		50	50	HR	TRUCK RENTAL	608.37	EST.
		50	50	HR	LOADER RENTAL TYPE I	608.40	EST.
		15	15	EA	YIELDING MARKER POST	619.17	3
	50	800	850	LF	STEEL BEAM GUARD RAIL	621.20	25
		100	100	LF	STEEL BEAM GUARD RAIL W/ 8' STEEL POSTS (MOD)	621.20	EST.
	130		130	LF	HEAVY DUTY STEEL BEAM GUARD RAIL	621.21	-
	4	7	11	EA	BREAKAWAY CABLE TERMINAL	621.50	-
		3	3	EA	ANCHOR FOR STEEL BEAM GUARD RAIL	621.60	-
		160	160	LF	REMOVAL AND DISPOSAL OF GUARD RAIL	621.80	4
		20	20	EA	REMOVAL AND DISPOSAL OF GUIDE POSTS	621.81	1
		100	100	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
		300	300	HR	FLAGGERS	630.15	EST.
		0.10	0.10	LS	TESTING EQUIPMENT - CONCRETE	631.16	EST.
		0.10	0.10	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	EST.
520			520	HR	EMPLOYEE TRAINEESHIP	634.10	EST.
		0.10	0.10	LS	MOBILIZATION	635.10	EST.
		100	100	HR	TRAFFIC OFFICER W/ FLASHING LIGHT	641.35	EST.
		17800	17800	LF	DURABLE 4'' WHITE LINE	646.40	88
		16800	16800	LF	DURABLE 4'' YELLOW LINE	646.41	81
		15	15	LF	DURABLE 24'' STOP BAR	646.46	-
		4	4	EA	DURABLE LETTER OR SYMBOL	646.50	-
		17800	17800	LF	TEMPORARY 4'' WHITE LINE	646.60	88
		16800	16800	LF	TEMPORARY 4'' YELLOW LINE	646.61	81
		15	15	LF	TEMPORARY 24'' STOP BAR	646.66	-
		250	250	EA	LINE STRIPING TARGETS	646.73	25
		40	40	LB	SEED	651.15	EST.
		250	250	LB	FERTILIZER	651.18	EST.
		1	1	TON	AGRICULTURAL LIMESTONE	651.20	EST.
		1	1	TON	HAY MULCH	651.25	EST.
		25	25	CY	TOPSOIL	651.35	EST.

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING - BITUMINOUS PAVEMENT
333	SY	BRIDGE #15
603	SY	END OF PROJECT
64	SY	ROUNDING
1000	SY	TOTAL
		MEDIUM DUTY BITUMINOUS CONCRETE PAVEMENT
1940	TON	MAINLINE - WEARING COURSE
16	TON	TOWN HIGHWAYS
19	TON	APPROACHES AND DRIVES
1081	TON	LEVELING
44	TON	ROUNDING
3100	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

STATIONS FROM	STATIONS TO	PAVEMENT WIDTHS			EQUATIONS +	EQUATIONS -	FEET	MILES	REMARKS
TOTALS									

9-OCT-1995
/pave/92c176/pc176.dgn

PROJECT NAME GLOVER
PROJECT NUMBER STP 9436(11)S