

ITEM DETAIL SUMMARY SHEET

| MILE MARKER | MILE MARKER | POS. | DROP INLET | LAT. DITCH | CLEAN INLET DITCH | CLEAN OUTLET DITCH | EARTH BORROW | TIMBER CURB | STONE FILL | NEW PIPE | | | CSPES | | | FLUSH PIPES 0-24" > 24" | 6" UND. | GRATE TYPE EA | CHAN ELEV EA | REHAB DI EA | MOD GUARDRAIL ITEMS | | | | | | REMARKS | | | | | |
|----------------|-------------|-----------|------------|------------|-------------------|--------------------|--------------|-------------|------------|----------|-----|-------|-------|----|-----|----------------------------|---------|------------------|-----------------|----------------|---------------------|--------|--------|--------|--------|---|---------|--------|--|--|--|--|
| | | | | | | | | | | D | L | TH/CL | D | TH | QTY | | | | | | 621.20 | 621.20 | 621.21 | 621.50 | 621.60 | 621.80 | | 621.81 | | | | |
| 2.957 | 2.981 | RT. | | | | | | | | | | | | | | | | | | | | | | | | INSTALL A 16' R END TERMINAL AT MM 2.957, RT. NORTH OF DRIVE TO BALLFIELD, 125 LF OF NEW STEEL BEAM GUARDRAIL WITH STEEL POSTS AND A BCT AT MM 2.981, RT. | | | | | | |
| 2.957 | 2.976 | LT. | | | | | | | | | | | | | | | | | | | | | | | | INSTALL A 16' R END TERMINAL AT MM 2.957 (NORTH OF EXISTING DRIVE), 75 LF OF NEW STEEL BEAM GUARDRAIL WITH STEEL POSTS AND A BCT AT MM 2.976, LT. | | | | | | |
| 3.164 | 3.221 | LT. | | | | | | | | | | | | | | | | | | | | | | | | INSTALL A BCT AT MM 3.164, LT., 250 LF OF NEW STEEL BEAM GUARDRAIL WITH STEEL POSTS AND A BCT AT MM 3.221, LT.; REMOVE EXISTING WOOD GUIDE POSTS. | | | | | | |
| 3.282 | 3.306 | RT. | | | | | | | | | | | | | | | | | | | | | | | | INSTALL A BCT AT MV 3.282 AND 3.306, 75 LF OF NEW STEEL BEAM GUARDRAIL WITH STEEL POSTS; REMOVE EXISTING 2 CABLE GUARDRAIL WITH WOOD POSTS. | | | | | | |
| 3.246 | 3.298 | LT. | | | | | | | | 15" | 40' | 0.064 | | | | | | | | | | | | | | REMOVE EXISTING 2 CABLE GUARDRAIL ON WOOD POSTS. BURY NEW GUARDRAIL INTO BACKSLOPE AT MM 3.246, INSTALL 250 LF OF NEW STEEL BEAM GUARDRAIL WITH STEEL POSTS AND A BCT AT MM 3.298 | | | | | | |
| 3.895 | 3.913 | RT. & LT. | | | | | | | | | | | | | | | | | | | | | | | | (SEE BRIDGE DETAILS, SHEET NOS. 8 & 9). | | | | | | |
| SHEET 04 TOTAL | | | | | | | | | | 15 | 40' | .064 | | | | | | | | | | | | | | | | | | | | |
| SHEET 08 TOTAL | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| SUB TOTALS | | | | | | | | | | 15 | 40' | .064 | | | | | | | | | | | | | | | | | | | | |
| ROUNDING | | | | | | | | | | - | - | - | | | | | | | | | | | | | | | | | | | | |
| PROJECT TOTALS | | | | | | | | | | 15 | 40' | .064 | | | | | | | | | | | | | | | | | | | | |

ITEM DETAIL SHEET

SURVEYED BY N/A DATE N/A
 DRAWN BY WBL DATE 03/93
 SQUAD LEADER _____
 DESIGN FILE NO. _____
 IPARM FILE _____ DATE PLOTTED _____
 PROJ. NAME GLOVER
 PROJ. NO. STP 9435(1)S
 SHEET 04 OF _____ SHEETS

HTA FILE: GLVSUM1
SHEET 38 OF 44