STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (In) lb/ft 1.75	2.0	2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0	4.0	4.0 MOD	TUBULAR STEEL Ø (in) lb/ft FOUNDATION	3.0	3.5	4.0	5.0	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	REASSIGNED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
	OPTION ITEMS																																			
99+04.18 RT.		1	36	36	9.00						2					35.0 ~~30.0~~		X															SIDE ROAD WARNING SIGN MUTCD W2-2L TO BE MOUNTED ON 2 POSTS WITH LAKE ROAD SIGN MOUNTED BELOW ON SAME POSTS		SHSM
99+04.18 RT.		1	24	8	1.33																											LAKE ROAD SIGN MUTCD W16-8P MOUNTED ON SAME POSTS AS SIDE ROAD WARNING SIGN	65	N/A
101+45.00 RT.		1						1			2					30.0		X															SALVAGED TIS SIGN SHALL BE MOUNTED ON NEW POSTS NO FEDERAL PARTICIPATION		E-125
55 102+~~54.20~~ LT.		1	24	30	5.00						1					14.25 ~~15.0~~		X															SPEED LIMIT SIGN MUTCD R2-1 SHALL BE MOUNTED ON SAME POST AS MILEMARKER SIGN		SHSM
55 102+~~54.~~20 LT.		1	6	10	.42																											MILEMARKER SIGN SHALL BE MOUNTED ON SAME POST AS SPEED LIMIT SIGN		E-138
105+03.83 RT.		1	30	30	6.25						1					14.0 ~~15.0~~		X															MUTCD R3-8		SHSM
105+39.00 RT.		1	36	12	3.00																											KILBURN ROAD SIGN TO BE AND MOUNTED ON SAME POST AS STOP SIGN	65	N/A
105+39.00 RT.		1	30	30	6.25						1					14.0 ~~15.0~~		X															STOP SIGN MUTCD R1-1 SHALL BE MOUNTED ON SAME POST AS KILBURN ROAD SIGN		SHSM
106+50.96 RT.		1					1			1																										
107+12.10 LT.		1	30	12	2.50																											LAKE ROAD SIGN SHALL BE MOUNTED ON SAME POST AS STOP SIGN AND MILE MARKER SIGN	65	N/A
107+12.10 LT.		1	30	30	6.25						1					13.25 ~~15.0~~		X															STOP SIGN MUTCD R1-1 SHALL BE MOUNTED ON SAME POST AS LAKE ROAD SIGN AND MILE MARKER SIGN		SHSM
107+12.10 LT.		1	6	10	.42																											MILEMARKER SIGN SHALL BE MOUNTED ON SAME POST AS STOP SIGN AND LAKE ROAD SIGN		E-138
50.00 108+~~13.97~~ RT.		1	24	12	2.00																											NORTH MARKER MUTCD M3-1 SHALL BE MOUNTED ON SAME POST AS US 7 ROUTE MARKER		SHSM
50.00 108+~~13.97~~ RT.		1	24	24	4.00						1					14.0 ~~15.0~~		X															US 7 ROUTE MARKER MUTCD M1-4 SHALL BE MOUNTED ON SAME POST AS NORTH MARKER		SHSM

SHSM = 2010 FHWA'S STANDARD HIGHWAY SIGNS & MARKINGS

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

	SF	SF	EA.	EA.		FT	FT	FT	FT	FT	FT	EA	LB	LB	LB		LB	LB	LB	LB	EA.	EA.	LB
TOTALS	46.42		1	1						~~135~~ 104.50													
						FT			FT 135				LB			EA.	LB				EA.	EA.	LB

PROJECT NAME: MILTON
PROJECT NUMBER: STP 5800 (2)

FILE NAME: t920289tssum.dgn
PROJECT LEADER: J. SCHULTZ
DESIGNED BY: D. LYMAN
TRAFFIC SIGN SUMMARY SHEET !

PLOT DATE: 23-FEB-2011
DRAWN BY: J. DEVLIN
CHECKED BY: J. DEVLIN
SHEET 63 OF 104