QUANTITY SHEET

QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

				QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
				1	LS	CLEARING & GRUBBING (PLUS INDIVIDUAL TREE & STUMPS)	201.10	
				1	EA	DEMOLITION & DISPOSAL OF BUILDING (WOODEN STRUCTURE)	202.10	
				1200	CY	UNCLASSIFIED EXCAVATION	203.17	EST
				1500	SY	FINE GRADING - SUBGRADE	203.40	EST
				25	CY	TRENCH EXCAVATION OF EARTH	204.20	EST
				480	CY	SUBBASE OF DENSE GRADED CRUSHED STONE (MOD.)	301.35	EST
				10	CWT	ASPHALT EMULSION	404.65	EST
				180	TON	MEDIUM DUTY BITUMINOUS CONCRETE PAVING	406.27	12
				48	LF	18" CSP (2-2/3 X 1/2)(0.064)	601.0015	
				2	EA	18" CSPES (2-2/3 X 1/2)(0.064)	601.6015	
				103	LF	VERTICAL GRANITE CURB	616.21	
				10	SY	PORTLAND CEMENT CONCRETE SIDEWALK - 5"	618.10	EST
				160	SY	BRICK PAVING	618.20	EST
			*	1	CY	GRANULAR BACKFILL FOR STRUCTURES (NOT A BID ITEM)	204.30	
				52	LF	STEEL BEAM GUARD RAIL W/TERMINAL END SECTION	621.20	
				1	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	
				140	LF	SEAMLESS COPPER WATER TUBE (2")	629.23	6
				1	LS	FIELD OFFICE - ENGINEERS	631.10	
				1	LS	TESTING EQUIPMENT - CONCRETE	631.16	
				1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	
				1	LS	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25	
				1	LS	MOBILIZATION	635.10	
				1	LS	UTILITY SYSTEM (SEPTIC SYSTEM)	636.15	
				500	LF	4" WHITE LINE	646.20	EST
				1	EA	LETTER OR SYMBOL	646.30	
				175	SY	GEOTEXTILE FOR ROADBED SUBGRADE SEPARATOR	649.11	5
				166	SY	GEOTEXTILE FOR SILT FENCE	649.51	EST
				120	LB	SEED (URBAN MIX)	651.15	EST
				40	LB	WILDFLOWER SEED	651.16	EST
				1000	LB	FERTILIZER	651.18	EST
				4	TON	AGRICULTURAL LIMESTONE	651.20	EST
				4	TON	HAY MULCH	651.25	EST
				20	EA	HAY BALES FOR EROSION CONTROL	651.26	3
				50	CY	TOPSOIL	651.35	EST.
				16	EA	EVERGREEN SHRUBS(JUIPERUS SABINA TAMARISCIFOLIA) TAM JUNIPER(18"-24"MIN CONTAINER)	656.25	
				3	EA	DECIDUOUS TREES (ACER SACCHARUM) SUGAR MAPLE (3" - 3.5" CAL., B&B)	656.30	EST
				1	LS	ROADSIDE REST FACILITY (BUILDING)	658.15	
				5	SF	TRAFFIC SIGN TYPE A	675.20	1.5
				70	LB	FLANGED CHANNEL SIGN POST 2 LB/FT	675.30	EST
				150	LF	ELECTRICAL CONDUIT (1 1/2")	678.21	8
				150	LF	WIRED CONDUIT (1 1/2")	678.23	8
				150	LF	WIRED CONDUIT (2")	678.23	8
				3	EA	LIGHT POLE (MOD.)	679.45	
				40	SF	BUSINESS INFORMATION SIGN (MOD.)(SIGN # 7)	680.25	1.8
				3	EA	AIRCRAFT TIE DOWN ANCHOR, TYPE A (MOD.)	854.07	

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

* ITEM OUT OF ORDER

Revised 7/25/96 PLD

SURVEYED BY _____ DATE _____
DRAWN BY _____ DATE _____
SQUAD LEADER _____
DESIGN FILE NO. _____
IPARM FILE _____ DATE PLOTTED _____
PROJ. NAME ALBURG WELCOME CENTER
PROJ. NO. NH 028- 1(17)S
SHEET 2 OF 21 SHEETS