GENERAL PROJECT NOTES

1. THE CONTRACTOR SHALL BE RESPONSIBLE FOR FIELD VERIFYING ALL DIMENSIONS AND EXISTING SITE INFORMATION. NEW WORK SHALL BE LAID OUT AND DIMENSIONS CHECKED FOR CONFORMITY WITH DRAWINGS. ADVISE OWNER AND A/E OF ANY DISCREPANCIES IMMEDIATELY.
2. DRAINAGE OF PAVERS&WALKS: PITCH ALL SUBBASE AND BASE COURSE MATERIALS SIMILAR TO THE FINISHED SURFACES. PONDING WITHIN THE BASE AND SUBBASE COURSES WILL NOT BE ACCEPTABLE. ALL WALKS AND PAVERS SHALL PITCH TO AVOID STANDING WATER.
3. ALL EXTERIOR AND INTERIOR SURFACES SHALL RECEIVE AT LEAST ONE COAT OF STAIN, OR AS SCHEDULED ON THE ROOM FINISH SCHEDULE.
4. THE CONTRACTOR SHALL COORDINATE AND PROVIDE ALL CUTOUTS, BLOCKING, BACKPLATES, RECESSED SLABS, SLEEVES, BURIED OR EMBEDDED CONDUIT,ETC. REQUIRED TO INSTALL THE WORK AND EQUIPMENT SHOWN.
5. THE CONTRACTOR SHALL PROVIDE ALL TRENCHES AND SITEOWORK REQUIRED FOR MECHANICAL/ELECTRICAL/PLUMBING WORK, INCLUDING BACKFILL AND FINAL GRADING PER SPECIFATIONS.

EROSION CONTROL NOTES

1. FOLLOW VT-AOT GUIDELINES FOR EROSION AND SEDIMENT CONTROL FOR ALL PHASES OF DEMOLITION, SITE PREPARATION AND CONSTRUCTION.
2. THE TOPSOIL SHALL BE REMOVED FROM THE AREAS TO BE GRADED AND STOCKPILED. STAKED HAY BALES OR A SILT FENCE SHALL BE PLACED CONTINUOUSLY AROUND THE BOTTOM OF THE PILE. NOTE THAT AT ALL SILT FENCES, FABRIC SHALL BE KEYED INTO GROUND 6" MIN.
3. ALL DISTURBED AREAS SHALL HAVE A SILT FENCE TO CONTROL SEDIMENTATION INCLUDING STAKED HAY BALES WHERE REQUIRED.
4. PROVIDE STAKED HAY BALES AND FILTER FABRIC AT ALL AFFECTED STORM DRAIN INLETS.
5. ALL TEMPORARY EROSION CONTROL FACILITIES SHALL BE INSTALLED AND MAINTAINED BY THE CONTRACTOR.
6. ALL EROSION CONTROL FACILITIES SHALL BE PROMPTLY INSPECTED AND REPAIRED AFTER EACH HEAVY RAINFALL.
7. KEEP WORK AREA TO A MINIMUM BY STRIPPING ONLY THOSE AREAS THAT WILL BE WORKED ON IMMEDIATELY.
8. REMOVE NO MORE VEGETATIVE COVER THAN IS NECESSARY TO GRADE THE SITE AS SHOWN ON THE PLANS.

1/00 GENERAL NOTES

N.T.S.

GENERAL SITEWORK NOTES

1. THE CONTRACTOR SHALL REPAIR ALL EXISTING ROADWALK PAVEMENT AND FOUNDATIONS WHERE DAMAGED OR DISTURBED BY THE WORK OF THIS CONTRACT AT NO COST TO THE OWNER. REPAIRS SHALL BE MADE WITH MATERIALS OF EQUAL QUALITY AND TO THE EXISTING PAVEMENT/ FOUNDATION DEPTH. THE AREA OF REPAIR SHALL BE SQUARE CUT AND NOT LESS THAN 10'x10'(OR WIDTH OF WALK) UNLESS APPROVED BY THE OWNER.
2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DEMOLITION AND REMOVAL OF ALL EXISTING VEGETATION, PAVEMENT, CONCRETE ITEMS AND STRUCTURES NECESSARY TO PERFORM THE WORK.
3. THE CONTRACTOR SHALL REPAIR ALL EXISTING LAWN OR VEGETATED AREAS DAMAGED OR DISTURBED DURING WORK OF THIS CONTRACT. REPAIRS SHALL BE MADE WITH LIKE PLANT MATERIAL IN ACCORDANCE WITH METHODS AND MATERIALS APPROVED BY THE OWNER.
4. AT THE COMPLETION OF THE GRADING, ALL SLOPES, DITCHES, AND ALL DISTURBED AREAS SHALL BE HAND RAKED, SMOOTH AND FREE OF POCKETS, WITH SUFFICIENT SLOPE TO ENSURE DRAINAGE.
5. FINISH SLOPES, DITCHES AND DISTURBED AREAS SHALL RECEIVE A MINIMUM OF 4 INCHES OF TOPSOIL MIX, AND BE FERTILIZED, SEEDED, LIMED, AND MULCHED. TURF ESTABLISHMENT SHALL BE PERFORMED PER VAOT SECTION 651.
6. ALL FILL SHALL BE PLACED IN 6 INCH LIFTS AND THOROUGHLY COMPACTED TO 95% OF MAXIMUM DENSITY OF OPTIMUM MOISTURE CONTENT AS DETERMINED BY ASTM D698 STANDARD PROCTOR, UNLESS NOTED OTHERWISE.
7. HEALTHY EXISTING TREES ON SITE NOT SCHEDULED FOR REMOVAL OR RE-LOCATION SHALL BE MARKED AND PROTECTED FROM DAMAGE DURING THE WORK.
8. FINISH GRADE, TOPSOIL AND SEED ALL DISTURBED AREAS NOT DESIGNATED FOR ANOTHER MATERIAL.
9. ADJUST ALL EXISTING MANHOLES, CATCH BASINS, RIMS, COVERS, VALVES AND OTHER SITE STRUCTURES AND UTILITIES WHERE ENCOUNTERED TO MEET NEW LINE AND GRADE OF FINISHED LAWN AND PAVEMENT.
10. ALL HIGHWAY AND OTHER SIGNAGE NOT SHOWN IN THESE DRAWINGS WILL BE PROVIDED BY THE OWNER. THE CONTRACTOR SHALL NOTIFY AND COORDINATE THE SCHEDULING OF THESE ITEMS WITH THE OWNER.
11. THE CONTRACTOR SHALL REMOVE ALL TRASH AND DEBRIS GENERATED DURING THE WORK FROM THE SITE AT THE END OF THE PROJECT.

EARTH
STONE, GRAVEL
BITUMINOUS PAVING
CONCRETE
PRE-CAST CONCRETE
CONCRETE MASONRY UNITS
BRICK
STONE
SAND, MORTAR
ALUMINUM
STEEL
SHEET METAL
REINFORCING - W.W.F.
REINFORCING BAR (RODS)
PLASTER/LATH
GYPSUM WALLBOARD
GLASS
PLYWOOD
WOOD (FINISHED)
WOOD BLOCKING (CONT.) (NOM. 3 MEN.)
WOOD SHIMS (NON-CONT.)
BATT INSULATION
RIGID INSULATION
ACOUSTIC TILE
PARTICLE BOARD
PLASTIC LAMINATE (ON PLYWD)
CARPET
QUARRY TILE
VAPOR BARRIER

JOB SPECIFIC LEGEND

CONCRETE
PRECAST CONCRETE BRICK PAVERS
ASPHALT
FULLY PAINTED AREA
--- 501 ---- EXISTING 1' CONTOUR LINE
--- 500 ---- EXISTING 5' CONTOUR LINE
NEW 1' CONTOUR LINE
SIGNAGE
EXISTING TREE TO REMAIN
TREE TO BE RELOCATED
NEW OR RELOCATED TREE OR SHRUB
EXISTING SHRUB TO REMAIN
EXISTING STREET LIGHT TO REMAIN
NEW LUMINAIRE
FLAGPOLE

2/00 STANDARD MATERIALS LEGEND

NO SCALE

GENERAL NOTES

EXTERIOR

CONCRETE PAVERS

MFR: HANOVER
STYLE: APPIAN
COLOR: NATURAL / CHARCOAL BLEND

ROOF

MFR: BIRD
STYLE: ORGANIC
COLOR: CHESTNUT BROWN

INTERIOR

FLOORING

MFR: SILIKAL
STYLE: MMA / FULL FLAKE
F-1 #21 FOREST GREEN, #2 TURTLEDOVE GREY, #1 EGGSHELL WHITE, #9 FAWN BEIGE

FIBERGLASS PLASTIC PANELS

MFR: BP CHEMICALS
STYLE: TUFFLINER
FP-1 ALMOND

PAINT

MFR: PRATT & LAMBERT
PT-1 #2288 SILVER LINING
PT-2 *NOT USED*
PT-3 #1456 WOODLAND

STAIN

MFR: PRATT & LAMBERT
ST-1 CLEAR FINISH
ST-2 EARLY AMERICAN MAPLE
ST-3 RUSTIC # 3-107 OIL (EXTERIOR)

SPECIFIC NOTES

PAINT

1. ALL GWB SHALL BE PT-1.
2. ALL INTERIOR DOOR FRAMES. EXTERIOR DOORS. & DOOR FRAMES, MECH. DUCTS / PIPING, WINDOW FRAMES (inside as well) SHALL BE PT-3.

STAIN

4. ALL INTERIOR WOOD SURFACES, OTHER THAN WOOD TRUSSES AND INTERIOR DOORS, SHALL BE ST-1.
5. ALL WOOD TRUSSES AND ALL INTERIOR DOORS SHALL BE ST-2
6. ALL EXTERIOR SIDING (WOOD LOGS), SOFFITS, AND FASCIA SHALL BE ST-3.

@	AT	DIMEN.	DIMENSION	JAN.	JANITOR
∠	ANGLE	DN.	DEAD LOAD	JT.	JOINT
℄	CENTERLINE	DN.	DOWN	L.	LENGTH
[	CHANNEL	DTL.	DETAIL	LAM.	LAMINATE(D)
⊥	PERPENDICULAR	DWG.	DRAWING	LAV.	LAVATORY
▭	PLATE			LF	LINEAR FEET
ø	ROUND/DIAMETER	E.J.	EXPANSION JOINT	LG.	LONG
		E.P.	ELECTRIC PANEL	LL	LIVE LOAD
		EIFS	EXTERIOR INSUL. & FINISH SYSTEM	LLH.	LONG LEG HORIZONTAL
		E.W.C.	ELECTRIC WATER COOLER	LLV.	LONG LEG VERTICAL
		EA.	EACH	LOC.	LOCATE(D) (-ION)
A.F.F.	ABOVE FINISH FLOOR	EL.	ELEVATION	LT-GA.	LIGHT GAUGE
A.P.	ACCESS PANEL	ELEC.	ELECTRIC(AL)	LTG.	LIGHTING
A.T.	ASPHALT TILE	ELEV.	ELEVATOR	LTL.	LINTEL
A/C	AIR CONDITIONING	ENTR.	ENTRANCE	LVR.	LOUVER
AC.	ACRE	EQ.	EQUAL		
ACT.	ACOUSTICAL TILE	EQUIP.	EQUIPMENT	M.O.	MASONRY OPENING
ADDTN.	ADDITION	ESTM.	ESTIMATE	M.R.	MOISTURE RESISTANT
ADJ.	ADJACENT	EXIS.	EXISTING	MACH.	MACHINE
ADJUST.	ADJUSTABLE	EXH.	EXHAUST	MAT.	MATERIAL
ALT.	ALTERNATE	EXP.	EXPOSED	MAX.	MAXIMUM
ALUM.	ALUMINUM	EXPAN.	EXPANSION	MECH.	MECHANICAL
ANCH.	ANCHOR(AGE)	EXT.	EXTERIOR	MET.	METAL(LIC)
ANOD.	ANODIZED	F.O.O.	FURNISHED BY OTHER	MEZZ.	MEZZANINE
APPROX.	APPROXIMATE	F.C.U.	FAN COIL UNIT	MFR.	MANUFACTURER
ARCH.	ARCHITECT(URAL)	F.D.	FLOOR DRAIN	MIN.	MINIMUM
ASB.	ASBESTOS	F.E.	FIRE EXTINGUISHER	MISC.	MISCELLANEOUS
ASPH.	ASPHALT	F.E.C.	FIRE EXTINGUISHER CABINET	MLDG.	MOULDING
B.M.	BENCHMARK	F.H.	FIRE HYDRANT	MNB.	MEMBRANE
B.U.R.	BUILT-UP ROOF	F.H.D.	FOWING WATER DISPOSAL	MSRY.	MASONRY
B.W.	BOTH WAYS	F.O	FRAME OPENING	MTL.	METAL
B/G	BOTTOM OF	F.P.	FIREPROOFING	NULL.	NULLION
BD.	BOARD	F/O	FACE OF	N.A.	NOT APPLICABLE
BLDG.	BUILDING	F/R	FIRE-RESISTIVE	N.I.C.	NOT IN CONTRACT
BLKG.	BLOCKING	FAP	FIRE ANNUNCIATION (ALARM) PANEL	N.S.	NON-SLIP
BLKT.	BLANKET	FDN.	FOUNDATION	N.T.S.	NOT TO SCALE
BM.	BEAM	FIN.	FINISH(ED)	NAT.	NATURAL
BRG.	BEARING	FIXT.	FIXTURE	NO.	NUMBER
BRK.	BRICK	FL'G.	FLASHING	NOM.	NOMINAL
BSMT.	BASEMENT	FL.	FLOOR		
BVL.	BEVELED	FM	FACTORY MUTUAL	O.A.	OVERALL
		FWN.	FOWING WATER VENDOR	O.C.	ON CENTER
C.H.	CHEMICAL HARDENER	FR.	FRAME	O.D.	OUTS DE DIAMETER
C.I.	CAST IRON	FRMG	FRAMING	OPNG.	OPENING
C.I.P.	CAST-IN-PLACE	FT.	FOOT/FEET	OPP.	OPPOSITE
C.J.	CONTROL JOINT	FTG.	FOOTING	OPPH.	OPPOSITE HAND
C.L.L.	CONTRACT LIMIT LINE	FUR.	FURRING	OSU	OHIO STATE UNIV. (TEST)
C.M.P.	CORRUGATED METAL PIPE	FURN.	FURNISHED/FURNITURE	P.&M.	PATCH & MATCH
C.W.T.	CERAMIC MOSAIC TILE	FWC	FABRIC WALL COVERING	P.W.S.	PREFORMED METAL SIDING
C.M.U.	CONCRETE MASONRY UNIT	G.B.	GRAB BAR	P.V.C.	POLYVINYL CHLORIDE
CT.	CERAMIC TILE	G.C.	GENERAL CONTRACTOR	PBD.	PARTICLE BOARD
CABT.	CABINET	G.C.T.	GLAZED CERAMIC TILE	PERIM.	PERIMETER
CARP.	CARPENTER	GA.	GAUGE	PL.	PLASTIC/PLATE
CB.	CHALKBOARD	GALV.	GALVANIZED	PL.LAM.	PLASTIC LAMINATE
CEM.	CEMENT	GKT.	GASKET	PLAS.	PLASTER
CL.	CLOSET	GL.	GLASS, GLAZING	PLBG.	PLUMBING
CLG.	CEILING	GWB	GYPSUM WALLBOARD	PLYWD.	PLYWOOD
CLR.	CLEAR	GYP.	GYPSUM	PN.	PANEL
COL.	COLUMN			PREFAB.	PREFABRICATE(D)
COMB.	COMBINATION	H.	HEIGHT	P.T.	PRESSURE TREATED
COMP.	COMPOSITE	H.C.	HOLLOW CORE	PT./PTD.	PAINT/PAINTED
CONC.	CONCRETE	H.M.	HOLLOW METAL	PTN.	PARTITION
CONST.	CONSTRUCTION	H/C	HANDICAPPED	PVMT.	PAVEMENT
CONT.	CONTINUOUS	HDB.	HARDBOARD		
CONTR.	CONTRACTOR	HDWD.	HARDWOOD	Q.T.	QUARRY TILE
CORR.	CORRIDOR	HDWR.	HARDWARE	QTY.	QUANTITY
CORRUG.	CORRUGATED	HGLR	HEAT/GLARE/LIGHT REDUCING(GLASS)		
CPT.	CARPET	HORIZ.	HORIZONTAL	R.	RADIUS/RISER
CRS.	COURSE(S)	HR.	HOUR	R.B.	RUBBER BASE
C.U.H.	CABINET UNIT HEATER	HVAC.	HEATING/VENTILATING/AIR COND.	R.D.	ROOF DRAIN
				R.F.	RUBBER FLOORING
D.	DEPTH	I.C.S.	INSULATED COMPOSITE SIDING	R.O.	ROUGH OPENING
D.F.	DRINKING FOUNTAIN	I.D.	INSIDE DIAMETER	REF.	REFERENCE
D.H.	DOUBLE HUNG	IMPREG.	IMPREGNATED	REINF.	REINFORCED
D.O.	DOOR OPENING/DITTO	INCL.	INCLUDE(D) (-ING)	REQ'D	REQUIRED
DEFL.	DEFLECTION	INSUL.	INSULATE(D) (-ON) (-ING)	RET.	RETURN
DIA.	DIAMETER	INT.	INTERIOR	REV.	REVISED/REVISION
DIAG.	DIAGONAL	INV.	INVERT	RM.	ROOM
				RUB.	RUBBER

S.C.	SOLID CORE
S.S.	STAINLESS STEEL
S.T.C.	SOUND TRANSMISSION CLASS
SCH.	SCHEDULE
SECT.	SECTION
SH.	SHEET
SHTH.	SHEATHING
SIM.	SIMILAR
SLNT.	SEALANT
SLR.	SEALER
SPEC.	SPECIFICATION
SPR.	SPRINKLER
SQ.	SQUARE
ST./STL.	STEEL
STD.	STANDARD
STR./STRUCT.	STRUCTURE(-AL)
SUSP.	SUSPENDED
SYM.	SYMMETRICAL
T.	TRANSFORMER/TREAD
T.&G.	TONGUE & GROOVE
T/CONC.	TOP OF CONCRETE
T/J	TOP OF DECK
T/O	TOP OF
T/S	TOP OF STEEL
T/W	TOP OF WALL
TB	TACKBOARD
TEL.	TELEPHONE
TEM.	TEMPERED
TEMP.	TEMPERATURE
TERM.	TERMINAL
TERR.	TERRAZZO
TH.	THICK(NESS)
THRES.	THRESHOLD
TLT.	TOILET
TRANS.	TRANSPORT
TRANSF.	TRANSFORMER
TRANSP.	TRANSPARENT
TRS.	TILE REDUCER STRIP
TYP.	TYPICAL
U.C.	UNDERCUT
U.N.O.	UNLESS NOTED OTHERWISE
UL	UNDERWRITER'S LAB. (TEST)
URI.	URINAL
V.	VINYL
V.B.	VAPOR BARRIER
V.I.F.	VERIFY IN FIELD
V.P.	VISION PANEL
VAR.	VARNISH
VB	VINYL BASE
VCT.	VINYL COMPOSITION TILE
VERT.	VERTICAL
VEST.	VESTIBULE
VNR.	VENEER
VT	VINYL TILE
VWC.	VINYL WALLCOVERING
W.	WIDTH
W.C.	WATER CLOSET
W.G.L.	WIRE GLASS
W.P.	WATERPROOF/WORKPOINT
W.R.	WATER REPELLENT/RESISTANT
W.S.	WEATHER STRIP
W.W.	WINDOW WALL
W.W.F.	WELDED WIRE FABRIC
W/	WITH
W/O	WITHOUT
WDW.	WINDOW

JOB SPECIFIC ABBREVIATIONS

FP FIBERGLASS PANEL

3/00 STANDARD ABBREVIATIONS

NO SCALE

DATUM POINT: T/CONC. T/STL. T/SUBSTRATE
STRUCTURAL GRID LINE
DOT: DIMENSION TO ℄ OR TO STRUCTURAL GRID LINE
SLASH: DIMENSION TO ACTUAL FACE OF MATERIAL; ACTUAL WALL THICKNESS
GRIDLINES
FINISHED SURFACE LINES - CUT
ELEMENTS BELOW CUT LINE - HIDDEN
ELEMENTS ABOVE CUT LINE - DASHED SOFFIT ABOVE CO-ORDINATE W/ CEILING PLANS, SECTIONS, DETAILS.
ACCESSORY ITEM SEE ACCESSORY SCHEDULE FOR DESCRIPTION.
SPECIAL NOTATION (e.g. DEMO NOTE)
LOUVER TYPE DESIGNATION
DOOR DESIGNATION
PARTITION TYPE: SEE PARTITION LEGEND ON A-0.
ROOM NUMBER DESIGNATION: SEE FINISH SCHEDULE.

SECTION OR DETAIL REFERENCE:
DETAIL NUMBER
SHEET NUMBER WHERE DETAIL IS LOCATED.
VIEW DIRECTION
SPECIAL NOTES
WALL SECTIONS: THRU-BUILDING SECTIONS
ROOM / WALL ELEVATIONS
REVISION NOTE
DETAIL No.
DETAIL TITLE
SCALE
SHEET No.

JOB SPECIFIC

FINISHED SURFACE LINES - NEW
NEW DOOR WITH FRAME CONSTRUCTION: SEE DOOR SCHEDULE INFORMATION.

4/00 STANDARD SYMBOLS LEGEND

NO SCALE

SEEDING FORMULA

URBAN AREAS

% WT.	LBS./ACRE	NAME	PUR %	GERM %
42.5	34.0	CREEPING RED FESCUE	98	85
10.0	8.0	PERENNIAL RYE GRASS	95	90
42.5	34.0	KENTUCKY BLUE GRASS	85	85
5.0	4.0	ANNUAL RYE GRASS	95	85

RURAL AREAS

% WT.	LBS./ACRE	NAME	PUR %	GERM %
37.5	22.5	CREEPING RED FESCUE	98	85
37.5	22.5	TALL FESCUE	95	90
5.0	3.0	RED TOP	95	90
15.0	9.0	BIRDSFOOT TREFOIL	98	85
5.0	3.0	ANNUAL RYEGRASS	95	85

SEED MIXTURE:
SHALL NOT HAVE A WEED CONTENT EXCEEDING 0.04 % BY WEIGHT AND SHALL BE FREE OF ALL NOXIOUS WEED SEED.

SEED:
TO BE APPLIED PER SEEDING FORMULAS AS DIRECTED BY THE ENGINEER.

FERTILIZER FORMULA:
10-20-10 TO BE USED WITH SEED, APPLIED AT THE RATE OF 500 LBS/ACRE.

AGRICULTURAL LIMESTONE:
TO BE APPLIED AT THE RATE OF 2 TONS/ACRE OR AS DIRECTED BY THE ENGINEER.

HAY MULCH:
TO BE PLACED ON EARTH SLOPES AT THE RATE OF 2 TONS/ACRE OR AS DIRECTED BY THE ENGINEER.

TOPSOIL:
TO BE USED WITH SEED AS INDICATED ON THE PLANS OR AS DIRECTED BY THE ENGINEER.

ARCHITECT
DORE AND WHITTIER INC.
ARCHITECTS • PROJECT MANAGERS
1793 VILLIERS ROAD • SOUTH BURLINGTON, VERMONT 05407

MECHANICAL/ ELECTRICAL ENGINEER
N.F.Laurence + Associates, Inc.
113 West Main Street
Northborough, MA 01532

CIVIL ENGINEER + SURVEY
VERMONT SURVEY and ENGINEERING, INC.
SURVEYORS and CIVIL ENGINEERS
55 EAST STATE STREET • MONTPELIER, VERMONT • 05602

STATE OF VERMONT
DEPARTMENT OF STATE BUILDINGS
AGENCY OF ADMINISTRATION
MONTPELIER, VERMONT

ALBURG WELCOME CENTER
ALBURG
GENERAL NOTES/ LEGENDS

DATE:	SCALE:	REVISIONS:	DRAWING NO:
MARCH 18, 1998		8-18-98	A-0
DRAWN BY: BJLI APPROVED BY: JBA	PROJECT NO: NB 028-1(17)S		SHEET 3 OF 21