STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

Metric

SUMMARY OF ESTIMATED QUANTITIES

		FULL E&C	LANDSCAPING	UTILITIES NON-GOVT. PARTICIPATING	EROSION CONTROL	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
						500	500	m	150 mm UNDERDRAIN	605.10	4
						35	35	m	150 mm UNDERDRAIN CARRIER PIPE	605.20	2
						6	6	EA	UNDERDRAIN FLUSHING BASIN	605.95	-
						1	1	h	BULLDOZER RENTAL, TYPE I (NOT A BID ITEM)	608.10	EST.
						1	1	h	POWER GRADER RENTAL (NOT A BID ITEM)	608.15	EST.
						1	1	h	ALL PURP. EXCAVATOR RENTAL, TYPE I (NOT A BID ITEM)	608.25	EST.
						1	1	h	TRUCK RENTAL (NOT A BID ITEM)	608.37	EST.
						250	250	m³	DUST CONTROL W/WATER	609.10	EST.
						0.5	0.5	t	DUST AND ICE CONTROL W/CALC. CHLORIDE	609.15	EST.
					2		2	m³	STONE FILL, TYPE I	613.10	EST.
						100	100	m	GRANITE SLOPE EDGING	616.20	-
						1150	1150	m	VERTICAL GRANITE CURB	616.21	15.7
						90	90	m	REMOVING AND RESETTING CURB	616.40	1
						210	210	m	REMOVAL OF EXISTING CURB	616.41	-
						360	360	m²	PORTLAND CEMENT CONC. SIDEWALK 125 mm	618.10	4.8
						15	15	m²	PORTLAND CEMENT CONC. SIDEWALK 200 mm	618.11	.3
						220	220	m²	BRICK PAVING	618.20	-
						5	5	EA	BOUNDARY MARKERS	619.10	EST.
						5	5	EA	REMOVING AND RESETTING PROP. MARKER	619.20	EST.
						30	30	m	REMOVING AND RESETTING GUARDRAIL	621.75	EST.
				0.5			0.5	m³	INSULATION BOARD	622.10	-
				140			140	m	DUCTILE IRON PIPE, 250mm (CLASS 52)	628.28	-
				10			10	EA	ADJUST ELEVATION OF VALVE BOX	629.20	-
				2			2	EA	EXTENSION SERVICE BOX & CURB STOP (38mm & 50mm)	629.25	-
				1			1	EA	HYDRANT, RELOCATE (MODIFIED)	629.29	-
				1			1	EA	CORPORATION STOP - 19mm	629.39	-
				110			110	T	CRUSHED STONE BEDDING	629.54	-
						400	400	h	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
						850	850	h	FLAGGERS	630.15	EST.

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME : BRATTLEBORO

PROJECT NO.: NH 2000(18)

DESIGN FILE NAME: /sqdc/93d191/dd191frm.dgn
IPARM FILE NAME: dd191qs2.i
SURVEYED BY:
SQUAD LEADER: MENARD
REVISED 5-15-97

PLOT DATE: 8-APR-1999
SURVEY DATE:
DRAWN BY: SQUAD C
SHEET: 5 OF 67