STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

Metric

SUMMARY OF ESTIMATED QUANTITIES

		FULL E&C	LANDSCAPING	UTILITIES NON-GOVT. PARTICIPATING	EROSION CONTROL	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
		1					1	LS	FIELD OFFICE - ENGINEERS	631.10	-
		1					1	LS	TESTING EQUIPMENT - CONCRETE	631.16	-
		1					1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	-
		1					1	LS	FIELD OFFICE TELEPHONE (NOT A BID ITEM)	631.25	-
						1	1	LS	MOBILIZATION	635.10	EST.
						1	1	LS	TRAFFIC CONTROL	641.10	EST.
						1	1	LS	TRAFFIC CONTROL (MOD.)	641.10	EST.
						5	5	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
						590	590	m	DURABLE 100 mm WHITE LINE	646.40	5.9
						810	810	m	DURABLE 100 mm YELLOW LINE	646.41	3.8
						50	50	m	DURABLE 200 mm YELLOW LINE	646.43	4.3
						31	31	m	DURABLE 300 mm WHITE LINE	646.44	.4
						104	104	EA	DURABLE LETTER OR SYMBOL	646.50	-
						85	85	m	DURABLE CROSSWALK W/ DIAGONAL LINES	646.51	1.5
						1180	1180	m	TEMPORARY 100 mm WHITE LINE	646.60	11.8
						1620	1620	m	TEMPORARY 100 mm YELLOW LINE	646.61	7.6
						100	100	m	TEMPORARY 200 mm YELLOW LINE	646.63	8.6
						62	62	m	TEMPORARY 300 mm WHITE LINE	646.64	.8
						170	170	m	TEMPORARY CROSSWALK W/ DIAGONAL LINES	646.71	3.0
						50	50	EA	LINE STRIPING TARGETS	646.76	EST.
					200		200	m²	GEOTEXTILE FABRIC FOR SILT FENCE	649.51	EST.
					5		5	kg	SEED	651.15	-
					10		10	kg	SEED - WINTER RYE	651.17	-
					25		25	kg	FERTILIZER	651.18	-
					0.5		0.5	t	AGRICULTURAL LIMESTONE	651.20	-
					0.2		0.2	t	HAY MULCH	651.25	-
					20		20	EA	HAY BALES FOR EROSION CONTROL	651.26	-
						310	310	m³	TOPSOIL	651.35	6
					1000		1000	m²	EROSION MATTING	654.10	EST.
			3				3	EA	EVERGREEN TREES (NORWAY SPRUCE)	656.20	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME : BRATTLEBORO	PROJECT NO.: NH 2000(18)

DESIGN FILE NAME: /sqdc/93d191/dd191frm.dgn
IPARM FILE NAME: dd191qs3.i
SURVEYED BY:
SQUAD LEADER: MENARD
REVISED 5-15-97

PLOT DATE: 8-APR-1999
SURVEY DATE:
DRAWN BY: SQUAD C
SHEET: 6 OF 67