



- UNDERDRAIN**
- ① US 5 I+075.0 LT ~ I+090.0 LT
NEW 150 mm x 15 m UNDERDRAIN
 - ② B.S.H. 2+055.0 RT ~ US 5 I+090.5 LT
NEW 150 mm x 92 m UNDERDRAIN
W/ F.B. @ 2+055.0 RT
 - ③ B.S.H. 2+052.0 LT ~ US 5 I+167.5 LT
NEW 150 mm x 92 m UNDERDRAIN
W/ F.B. @ 2+052.0 LT
 - ④ US 5 I+167.5 LT ~ I+215.0 LT
NEW 150 mm x 47 m UNDERDRAIN
W/ F.B. @ I+215.0 LT
 - ⑤ VT 9 2+179.1 LT ~ US 5 I+215.0 RT
NEW 150 mm x 90 m UNDERDRAIN
 - ⑥ VT 9 2+183.0 LT ~ 2+225.0 LT
NEW 150 mm x 42 m UNDERDRAIN
W/ F.B. @ 2+183.0 LT
 - ⑧ VT 9 2+183.0 RT ~ 2+243.0 RT
NEW 150 mm x 60 m UNDERDRAIN
W/ F.B. @ 2+183.0 RT
 - ⑨ US 5 I+063.0 RT ~ I+073.3 RT
NEW 150 mm x 13 m CARRIER PIPE
 - ⑩ US 5 I+073.3 RT ~ VT 9 2+179.0 RT
NEW 150 mm x 58 m UNDERDRAIN
W/ F.B. @ 2+179.0 RT

- NEW DRAINAGE**
- ① US 5 I+062.7 RT ~ I+090.0 LT
NEW 600 mm X 38 m PCCPSP OR CAAP OR CPEP W/
NEW 1.2 X 1.2 RCDI @ INLET & 1.2 m WIDE X 2.4 m
LONG X 0.6 m DEEP STONE PAD TYPE II @ OUTLET
 - ② US 5 I+090.6 LT ~ I+103.4 LT
NEW 450 mm X 14 m RCP CL III OR CPEP (SL)
NEW 1.2 X 1.2 RCDI W/ C.I. COVER @ INLET
CONNECT EXISTING PIPE ② TO DI
 - ③ B.S.H. 2+112.0 RT ~ US 5 I+103.7 LT
NEW 450 mm X 19 m RCP CL III OR CPEP (SL)
NEW 1.2 X 1.2 RCDI @ INLET
 - ④ B.S.H. 2+101.5 LT ~ 2+111.9 RT
NEW 450 mm X 24 m RCP CL III OR CPEP (SL)
NEW 1.2 X 1.2 RCDI @ INLET
 - ⑤ US 5 I+167.5 LT ~ I+238.7 LT
NEW 450 mm X 71 m RCP CL III OR CPEP (SL)
NEW 1.2 X 1.2 RCDI @ INLET
 - ⑥ US 5 I+157.8 RT ~ I+167.5 LT
NEW 450 mm X 24 m RCP CL III OR CPEP (SL)
NEW 1.2 X 1.2 RCDI @ INLET
 - ⑦ VT 9 2+152.0 C.L. ~ US 5 I+167.5 RT
NEW 450 mm X 37 m RCP CL III OR CPEP (SL)
NEW 1.2 X 1.2 RCDI @ INLET
 - ⑧ VT 9 2+152.3 C.L. ~ US 5 I+090.0 LT
NEW 450 mm X 45 m RCP CL III OR CPEP (SL)
NEW 1.2 X 1.2 RCDI @ INLET
 - ⑨ VT 9 2+179.4 LT ~ RT
NEW 450 mm X 20 m RCP CL III OR CPEP (SL)
NEW 1.2 X 1.2 RCDI @ INLET
 - ⑩ VT 9 2+179.4 LT ~ 2+191.1 LT
EXTEND & CONNECT EXISTING 450 mm RCP
W/ NEW 450 mm X 12 m RCP CL III

* SEE SHEET 34 FOR NEW WATERLINE LOCATION

NEW DRAINAGE
Metric



PROJECT:	BRATTLEBORO	PROJECT NO.:	NH 2000(18)
DESIGN FILE NAME:	/sqdc/93d191/d191bdr.dgn	PLOT DATE:	8-APR-1999
IPARM FILE NAME:	dd191d12.i	SURVEY DATE:	10-95
SURVEYED BY:	R. GILMAN	DRAWN BY:	K. UPMAL
SQUAD LEADER:	S. MENARD	SHEET:	29 OF 67