STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAMED REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
	OPTION ITEMS																																			
	U. S. RTE. 5															—																				
~~885~~ 0+~~860.0~~ RT		1	900	900	0.81						2		10.97 X			X																	SEE DETAIL SH. #47		
		1	900	900	0.81																												W3-2A		E-150M
0+920.0 RT	JCT	1	525	375	0.20						1		4.27 X			X																M2-1		E-136BM
	ROUNDABOUT 0.18 VERMONT 9	1	600	600	0.36											—																		E-136BM
0+980.0 RT	BELLOWS FALLS 20	1	1350	190	0.26						2		7.31 X			X																		E-123M
	KEENE N.H. 25 →	1	1350	190	0.26											—																		E-123M
~~1+239~~ 0+~~983.5~~ CL		1	600	750	0.45						1		4.27 X			X			1													R4-7		E-144M
		1	450	450	0.20																											OM-1		E-150M
~~2+247~~ 1+~~027.5~~ CL		1	600	750	0.45						1		4.27 X			X			1													R4-7		E-144M
		1	450	450	0.20																											OM-1		E-150M
1+043.0 RT	TO NORTH EAST	1	600	300	0.18						2		X 9.75			X															1	M4-5		E-135M
		1	600	300	0.18																											M3-1		E-136AM
		1	600	300	0.18																											M3-2		E-136BM
	91 5 VERMONT 9	1	600	600	0.36																											M1-1		E-135M
		1	600	600	0.36																											M1-4		E-136AM
		1	600	600	0.36																													E-136BM
		1	525	375	0.20																											SEE DETAIL SH. #47		
		1	525	375	0.20																											M6-3		E-136AM
		1	525	375	0.20																											M6-1		E-136BM
~~055~~ 1+~~046.0~~ CL		1	600	750	0.45						1		4.27 X			X			1													R4-7		E-144M
		1	450	450	0.20																											OM-1		E-150M
1+047.0 LT	BRATTLEBORO 2	1	1350	190	0.26						2		4.27 X			X																		E-123M
	GUILFORD 5	1	1350	190	0.26																													E-123M
TOTALS			m² 7.39	m²	EA.	m²						m 54.9			m 54.9				EA 3	kg			kg	EA.	kg						EA.	EA.	kg			

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: BRATTLEBORO
PROJECT NO.: NH 2000(18)
DESIGN FILE NAME: /sqdc/93dl91/ddl91frm.dgn
PARM FILE NAME: ddl91fsl.t
SURVEYED BY:
SQUAD LEADER: MENARD
REVISED 1-5-99
PLOT DATE: 8-APR-1999
SURVEY DATE:
DRAWN BY: SQUAD C
SHEET: 40 OF 67