STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 / 3.4	50 / 3.9	63 / 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 / 1.9	100 / 2.5	100 MOD / 2.5	TUBULAR STEEL Ø (mm) FOUND-ATION	75	89	100	125	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																								
1+074.0 LT	SOUTH	1	600	300	0.18						1		4.87 X			~~X~~			1														M3-3		E-136AM
	5	1	600	600	0.36																												M1-4		E-136AM
	TO	1	600	300	0.18																												M4-5		E-136BM
	30	1	600	600	0.36																														E-136BM
1+090.0 RT		1	600	750	0.45						1		4.27 X			~~X~~			1														VR-004A		E-146M
1+095.0 LT		1	600	750	0.45						1		4.27 X			~~X~~			1														VR-004A		E-146M
1+102.0 CL	900X900X900	1			0.35						1		4.27 X			~~X~~			1														R1-2		E-146M
1+102.0 CL		1	450	450	0.20						1		3.66 X			~~X~~			1														OM-1		E-150M
1+103.0 RT	900X900X900	1			0.35						1		4.27 X			~~X~~			1														R1-2		E-146M
1+116.0 RT	ONE WAY	1	900	300	0.27						2		7.31 X			~~X~~																	R6-1R		E-142M
1+144.0 LT	ONE WAY	1	900	300	0.27						2		7.31 X			~~X~~																	R6-1R		E-142M
1+156.0 LT	900X900X900	1			0.35						1		4.27 X			~~X~~			1														R1-2		E-146M
1+159.0 CL		1	450	450	0.20						1		4.27 X			~~X~~			1														OM-1		E-150M
1+172.0 RT		1	600	750	0.45						1		4.27 X			~~X~~			1														VR-004A		E-146M
1+180.0 RT	NORTH	1	600	300	0.18						1		4.27 X			~~X~~			1														M3-1		E-136AM
	5	1	600	600	0.36																												M1-4		E-136AM
1+180.0 LT		1	600	750	0.45						1		4.27 X			~~X~~			1														VR-004A		E-146M
												m	m	m	m	m	m		EA 11	kg	kg	kg		kg	kg	kg	kg								
TOTALS					m² 5.41	m²	EA.	m²				m 62.5			m 62.5					kg			EA.	kg				EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: BRATTLEBORO	PROJECT NO.: NH 2000(18)
DESIGN FILE NAME: /sqdc/93d191/dd191frm.dgn	
IPARM FILE NAME: dd191ts2.i	PLOT DATE: 8-APR-1999
SURVEYED BY:	SURVEY DATE:
SQUAD LEADER: MENARD	DRAWN BY: SQUAD C
REVISED 1-7-99	SHEET: 41 OF 67