STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																								
BRATTLEBORO STATE HWY.																																		
2+025.0 RT		1	900	900	0.81						2		12.19 X			X																SEE DETAIL SH. #47		
		1	900	900	0.81 0.18																											W3-2A		E-150M
2+040.0 RT	ROUNDABOUT JCT JCT	1	525	375	0.20						2		X 9.75			X															1	M2-1		E-136AM
		1	525	375	0.20																											M2-1		E-136BM
	5 VERMONT 9	1	600	600	0.36																											M1-4		E-136AM
		1	600	600	0.36																													E-136BM
2+~~050.0~~ 035.0 LT	SOUTH NORTH	1	600	300	0.18						2		9.75 X			X															1	M3-3		E-135M
		1	600	300	0.18																											M3-1		E-135M
	91 91	1	600	600	0.36																											M1-1		E-135M
		1	600	600	0.36																											M1-1		E-135M
		1	525	375	0.20																											M6-3		E-135M
		1	525	375	0.20																											M6-1		E-135M
2+059.0 RT	KEENE N.H. 25	1	1350	190	0.26						2		X 8.53			X																		E-123M
	BELLOWS FALLS 20	1	1350	190	0.26																											SEE DETAIL SH. #47		
	BRATTLEBORO 2	1	1350	190	0.26																													E-123M
		1	600	600	0.36																											SEE DETAIL SH. #47		
		1	600	150	0.09																											SEE DETAIL SH. #47		
2+086.0 RT	NORTH EAST SOUTH	1	600	300	0.18						2		X 8.53			X			2												1	M3-1		E-136AM
		1	600	300	0.18																											M3-2		E-136BM
		1	600	300	0.18																											M3-3		E-136AM
	5 VERMONT 9 5	1	600	600	0.36																											M1-4		E-136AM
		1	600	600	0.36																													E-136BM
		1	600	600	0.36																											M1-4		E-136AM
		1	525	375	0.20																											SEE DETAIL SH. #47		
		1	525	375	0.20																											M6-3		E-136BM
		1	525	375	0.20																											M6-1		E-136AM
												m	m	m	m	m	m		EA 2	kg	kg	kg		kg	kg	kg	kg							
TOTALS			m^2 7.67	m^2	EA.	m^2						m 53.0			m 53.0					kg			EA.	kg				EA.	EA.	kg				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT:	PROJECT NO.:
BRATTLEBORO	NH 2000(18)

DESIGN FILE NAME: /sqdc/93dl91/dd191frm.dgn
IPARM FILE NAME: dd191ts6.1
SURVEYED BY:
SQUAD LEADER: MENARD
REVISED 3-10-97

PLOT DATE: 8-APR-1999
SURVEY DATE:
DRAWN BY: SQUAD C
SHEET: 45 OF 67