SUMMARY OF ESTIMATED QUANTITIES

ITEM NO.	ITEM DESCRIPTION	UNIT	SUPER-STRUCTURE	ABUTMENT 1	ABUTMENT 2	PIER 1	PIER 2	RETAINING WALLS	BRIDGE SUBTOTAL	ROADWAY	CHANNEL	EROSION CONTROL	FULL E & C	TOTAL	REMARKS
613.10	STONE FILL, TYPE I	CY										10		10	
613.10	STONE FILL, TYPE I (MOD. - CHECK DAM)	CY										5		5	ESTIMATED
613.10	STONE FILL, TYPE I (MOD. - CONSTRUCTION ENTRANCE)	CY										15		15	ESTIMATED
613.10	STONE FILL, TYPE I (MOD. - INLET PROTECTION)	CY										5		5	ESTIMATED
613.11	STONE FILL, TYPE II	CY										60		60	
613.12	STONE FILL, TYPE III	CY									131			131	
616.21	VERTICAL GRANITE CURB	LF								480				480	
616.41	REMOVAL OF EXISTING CURB	LF								263				263	
618.10	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH (MOD.)	SY								167				167	
618.30	DETECTABLE WARNING SURFACE	SY								3				3	
619.17	YIELDING MARKER POSTS	EA								6				6	
620.50	REMOVING AND RESETTING FENCE (MOD. - STONE WALL)	LF								15				15	
620.70	SNOW FENCE (MOD. - ARCH)	LF								335				335	
620.70	SNOW FENCE (MOD. - PDF)	LF								510				510	
621.21	HEAVY DUTY STEEL BEAM GUARD RAIL (GALVANIZED)	LF								155				155	
621.60	ANCHOR FOR STEEL BEAM RAIL	EA								3				3	
621.74	ALUMINUM APPROACH RAILING (MOD. - ANODIZED BLACK)	LF								257				257	
621.80	REMOVAL AND DISPOSAL OF GUARD RAIL	LF								335				335	
621.90	TEMPORARY TRAFFIC BARRIER (MOD.)	LF								1010				1010	
630.10	UNIFORMED TRAFFIC OFFICERS	HR								700				700	ESTIMATED
630.15	FLAGGERS	HR								600				600	ESTIMATED

N.A.B.I. = NOT A BID ITEM

VHB *Vanasse Hangen Brustlin, Inc.*

STATE OF VERMONT
AGENCY OF TRANSPORTATION

Town Of WOODSTOCK	Bridge No. 50
	Log Sta.
Highway No. U.S. ROUTE 4	Surv. Sta.
U.S. ROUTE 4 OVER OTTAUQUECHEE RIVER	
QUANTITY SHEET (3 OF 5)	
Designed By L.S. GARDNER	Drawn By B.J. MASSE
Checked By J.T. KLEIN Date 10/06	Bridge Design Supervisor M.A. COLGAN Date 10/06
PROJECT WOODSTOCK	PROJECT NO. BHF 020-2 (32)
I.G.C. Info.	
Bridge Sheet No. ZJ028QNT3	Sheet 5 of 71

VHB NO. 51298 plot date: 10/11/2006