SUMMARY OF ESTIMATED QUANTITIES

ITEM NO.	ITEM DESCRIPTION	UNIT	SUPER-STRUCTURE	ABUTMENT 1	ABUTMENT 2	PIER 1	PIER 2	RETAINING WALLS	BRIDGE SUBTOTAL	ROADWAY	CHANNEL	EROSION CONTROL	FULL E & C	TOTAL	REMARKS
652.10	EROSION PREVENTION & SEDIMENT CONTROL PLAN	LS										1		1	
652.20	MONITORING EROSION PREVENTION & SEDIMENT CONTROL PLAN	HR										100		100	
652.30	MAINTENANCE OF EROSION PREVENTION & SEDIMENT CONTROL PLAN (N.A.B.I.)	LU										1		1	
654.10	EROSION MATTING	SY										240		240	
675.20	TRAFFIC SIGNS, TYPE A	SF								6.3				6.3	
	BEGIN SIGN POST OPTIONS														
675.301	FLANGED CHANNEL SIGN POST	LF								45				45	
675.341	SQUARE TUBE SIGN POSTS AND ANCHOR	LF								45				45	
	END SIGN POST OPTIONS														
675.50	REMOVING SIGNS	EA								12				12	
675.60	ERECTING SALVAGED SIGNS	EA								9				9	
678.23	WIRED CONDUIT (2") (PVC)	LF	405						405	110				515	
678.25	PULL BOX - STANDARD	EA								1				1	
678.26	JUNCTION BOX	EA	8						8					8	
678.30	ELECTRICAL CONDUIT SLEEVE (6") (PVC)	LF								40				40	
679.45	LIGHT POLE (MOD.)	EA	8						8					8	
679.50	LUMINAIRE (MOD.)	EA	8						8					8	
995.10	INCENTIVE/DISINCENTIVE WORK ORDER (N.A.B.I.)	LU								1				1	

N.A.B.I. = NOT A BID ITEM

VHB ***Vanasse Hangen Brustlin, Inc.***

STATE OF VERMONT
AGENCY OF TRANSPORTATION

Town Of WOODSTOCK	Bridge No. 50
	Log Sta.
Highway No. U.S. ROUTE 4	Surv. Sta.
U.S. ROUTE 4 OVER OTTAUQUECHEE RIVER	
QUANTITY SHEET (5 OF 5)	
Designed By L.S. GARDNER	Drawn By B.J. MASSE
Checked By J.T. KLEIN Date 10/06	Bridge Design Supervisor M.A. COLGAN Date 10/06
PROJECT WOODSTOCK	PROJECT NO. BHF 020-2(32)
I.G.C. Info.	
Bridge Sheet No. ZJ028QNT5	Sheet 7 of 71

VHB NO. 51298 plot date: 10/6/2006