



1 **2**

3 5 7 9 11 13 15 **16 14 12 10 8 6 4**

DETENSING SCHEDULE
N.T.S.

MARK:	WD-I	QTY.:	1	WT.:	17.86 T	VOL.:	11.50 cy
MARK:	WD-II	QTY.:	1	WT.:	17.86 T	VOL.:	11.50 cy
MATERIAL LIST / BEAM							
ITEM	MARK	DESCRIPTION	QTY./BEAM				
1	401E	#4 BENT BAR (EPOXY COATED)	102	102			
2	402E	#4 BENT BAR (EPOXY COATED)	51	51			
3	403E	#4 BENT BAR (EPOXY COATED)	12	12			
4	404E	#4 BENT BAR (EPOXY COATED)	4	4			
5	405E	#4 BENT BAR (EPOXY COATED)	4	4			
6							
7	501E	#5 BENT BAR (EPOXY COATED)	50	50			
8	502E	#5 x 57'-4" (E.C. W/ (3) 2'-0" STAGGERED LAPS)	4	4			
9							
10		WVF 4x4-W4.0xN4.0 [1'-11 1/2" x 3'-10"]	6	6			
11							
12							
13	MK-P4	DAYTON 1/2" F-42 LOOP FERRULE INSERT (GALV.)	2	2			
14	MK-P3	DAYTON C-24 TYPE 4-APR PRESS-STEEL PRECAST HALF HANGER (GALV.)	15	15			
15		3'-1 1/2" x 1'-4" x 17'-0 3/4" BOX VOID	1	1			
16		3'-1 1/2" x 1'-4" x 17'-6 3/8" BOX VOID	2	2			
17		3/4" x 5 1/2" NON-FERROUS VOID DRAIN	6	6			
18		DOUBLE 1/2" STRAND LIFTING LOOPS	4	4			
19							

3-20-07 REVISE STRAND PATTERN
2-13-07 REVISE BOX VOIDS

APPROVAL STAMP:

J.P. CARRARA & SONS INC.
Precast & Prestress Manufacturer
2444 CASE STR. MOORESBURY, VERMONT 05753 Phone:(802)388-6361 Fax:(802)388-9010

T. BUCK CONSTRUCTION, INC.
CONTRACTOR
AUBURN, MAINE

STATE OF VERMONT A.O.T.
COUNTY OF WINDSOR

TOWN OF WOODSTOCK
US ROUTE 4 OVER OTTAUGUECHEE RIVER
BRIDGE NO. 50 PROJECT NO. BHF 020-2(32)

P/S BOX BEAM DETAILS

DATE: JAN. 9, 2007
SCALE: NOTED
CHKD: D.F. DFTM: B.L.
JOB NO: 23244-06
DWG. NO: **B1**