**STATE OF VERMONT**
**AGENCY OF TRANSPORTATION**

# DETOUR SIGN SUMMARY SHEET (1)

Metric

| KILOMETER MARKER, STATION, OR SIGN NUMBER | SIGN LEGEND | SIGN DIMENSIONS EA | WIDTH (mm) | HEIGHT (mm) | NEW & SALVAGED SIGNS "A" | "B" | SALV SIGN | SALV TIS | EXIST POST RETAIN | SALVAGE | NO. OF POSTS | FLANGED CHANNEL kg/m 1.7 | 3.0 | 4.5 | SQUARE STEEL (mm) kg/m 44 3.4 | 50 3.9 | 63 5.0 | ANCHOR | SLEEVE | TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9 | 100 2.5 | 100 MOD 2.5 | TUBULAR STEEL Ø (mm) FOUNDATION | kg/m 75 11.3 | 89 13.4 | 100 16.1 | 125 21.7 | W-SHAPE STEEL FTG. SIZE 600 mm | 750 mm | WEIGHT | POST SIZE | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL DETAIL ON SHEET NUMBER | STD. SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | | | OPTION ITEMS | | | | | | | | | | | | | | | | | | | | | | | | |
| 5DR | DETOUR | 2 | 600 | 300 | 0.36 | | | | | | 2 | | | 8.85 | | | | | | | | | | | | | | | | | | | SEE CONSTRUCTION SIGN DETAIL (1) | 24 | |
| | 5 | 2 | 600 | 600 | 0.72 | | | | | | | | | | | | | | | | | | | | | | | | | | | | M1-4 | | E-136AM |
| | → | 2 | 525 | 375 | 0.39 | | | | | | | | | | | | | | | | | | | | | | | | | | | | M6-1 | | E-136AM |
| ED | END | 2 | 600 | 300 | 0.36 | | | | | | 2 | | | 7.50 | | | | | | | | | | | | | | | | | | | M4-6 | | E-140M |
| | DETOUR | 2 | 600 | 300 | 0.36 | | | | | | | | | | | | | | | | | | | | | | | | | | | | SEE CONSTRUCTION SIGN DETAIL (1) | 24 | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| ⚠1 | US 5/MAIN ST. BRIDGE CLOSED USE EXIT 2 TO VT 9 EAST FOR DOWNTOWN | 1 | 5200 | 1800 | | 9.36 | | | | | 2 | | | | | | | | | | | | ~~2~~ | | | ~~183.5~~ | | | | | | | SEE CONSTRUCTION SIGN DETAIL (3) | 26 | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| ⚠2 | US 5/MAIN ST. BRIDGE CLOSED USE EXIT 1 TO US 5 NORTH FOR CANAL ST. | 2 | 5200 | 1800 | | 18.72 | | | | | 4 | | | | | | | | | | | | 2 ~~4~~ | | | 183.6* ~~367.1~~ * SEE CHANGE ORDER #2 DATED 7-9-03 FWR | | | | | | | SEE CONSTRUCTION SIGN DETAIL (3) | 26 | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| SA | | 2 | 900 | 900 | 1.62 | | | | | | 2 | | | 9.46 | | | | | | | | | | | | | | | | | | | W3-1A | | E-150M |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| NLT | | 1 | 600 | 600 | 0.36 | | | | | | 1 | | | 3.75 | | | | | | | | | | | | | | | | | | | R3-2 | | E-143M |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| DNE | DO NOT ENTER | 8 | 750 | 750 | 4.50 | | | | | | 5 | | | 19.50 | | | | | | | | | | | | | | | | | | | R5-1 | | E-143M |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| WW | WRONG WAY | 8 | 900 | 600 | 4.32 | | | | | | 8 | | | 30.00 | | | | | | | | | | | | | | | | | | | R5-1A | | E-143M |
| | | | | | | | | | | | | m | m | m 79.06 | m | m | m | | EA | kg | kg | kg | | kg | kg | kg 550.6 | kg | | | | | | | | |
| **TOTALS** | | | | | | m² 12.99 | m² 28.08 | EA. | m² | | | m 79.06 | | | m | | | | | kg | | | EA. 6 | | | kg 550.6 | | EA. | EA. | kg | | | | | |

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: BRATTLEBORO
PROJECT NUMBER: BHF 2000 (17)

FILE NAME: 94J078\Structures\sj078tss2.I PLOT DATE: 24-MAY-2004
PROJECT MANAGER: R. R. WHITCOMB DRAWN BY: G. ROY
DESIGNED BY: G. ROY CHECKED BY: T. SUMNER
REVISED BY VAOT 04/22/2003 SHEET 17 OF 71