STATE OF VERMONT
AGENCY OF TRANSPORTATION

DETOUR SIGN SUMMARY SHEET (2)

Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (mm)	SIGN DIMENSIONS HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) 44 kg/m 3.4	SQUARE STEEL (mm) 50 kg/m 3.9	SQUARE STEEL (mm) 63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	TUBULAR ALUMINUM Ø (mm) 100 kg/m 2.5	TUBULAR ALUMINUM Ø (mm) 100 MOD kg/m 2.5	TUBULAR STEEL Ø (mm) FOUND-ATION	TUBULAR STEEL Ø (mm) 75 kg/m 11.3	TUBULAR STEEL Ø (mm) 89 kg/m 13.4	TUBULAR STEEL Ø (mm) 100 kg/m 16.1	TUBULAR STEEL Ø (mm) 125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAMED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																							
OWL		2	900	300	0.54						2		6.90																				R6-1L		E-142M
OWR		10	900	300	2.70						10		34.50																				R6-1R		E-142M
S3W		1	750	750	0.56						1			4.05																			R1-1		E-143M
		1	300	150	0.05																												SEE CONSTRUCTION SIGN DETAIL (2)	25	
S3WDR		1	600	300	0.18						1			5.18									~~1~~	~~72.1~~									SEE CONSTRUCTION SIGN DETAIL (1)	24	
		1	600	300	0.18																												M3-1		E-136AM
		1	600	600	0.36																												M1-4		E-136AM
		1	525	375	0.20																												M6-1		E-136AM
		1	750	750	0.56																												R1-1		E-143M
		1	300	150	0.05																												SEE CONSTRUCTION SIGN DETAIL (2)	25	
S3WDL		1	600	300	0.18						1			5.18									~~1~~	~~72.1~~									SEE CONSTRUCTION SIGN DETAIL (1)	24	
		1	600	300	0.18																												M3-1		E-136AM
			600	600	0.36																												M1-4		E-136AM
		1	525	375	0.20																												M6-1		E-136AM
		1	750	750	0.56																												R1-1		E-143M
		1	300	150	0.05																												SEE CONSTRUCTION SIGN DETAIL (2)	25	
												m	m 41.40	m 4.05	m	m	m		EA	kg	kg	kg		kg 144.2	kg	kg	kg							
TOTALS					m^2 6.91	m^2	EA.	m^2				m 45.45			m					kg			EA. 2	kg 144.2				EA.	EA.	kg				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: BRATTLEBORO
PROJECT NUMBER: BHF 2000 (17)

FILE NAME: 94J078\Structures\sJ078tss3.i PLOT DATE: 24-MAY-2004
PROJECT MANAGER: R. R. WHITCOMB DRAWN BY: G. ROY
DESIGNED BY: G. ROY CHECKED BY: T. SUMNER
REVISED BY VAOT 04/22/2003 SHEET 18 OF 71