STATE OF VERMONT
AGENCY OF TRANSPORTATION

DETOUR SIGN SUMMARY SHEET (7)

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAMED REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																								
5D	DETOUR	1	600	300	0.18						1			4.43																			SEE CONSTRUCTION SIGN DETAIL (1)	24	
	5	1	600	600	0.36																												M1-4		E-136AM
	↑	1	525	375	0.20																												M6-3		E-136AM
DA5N	DETOUR AHEAD	4 ~~6~~	600	600	1.44 ~~2.16~~						6			27.9																			SEE CONSTRUCTION SIGN DETAIL (1)	24	
	NORTH	4 ~~6~~	600	300	0.72 ~~1.08~~																												M3-1		E-136AM
	5	4 ~~6~~	600	600	1.44 ~~2.16~~																												M1-4		E-136AM
DA5S	DETOUR AHEAD	1	600	600	0.36						1			4.65																			SEE CONSTRUCTION SIGN DETAIL (1)	24	
	SOUTH	1	600	300	0.18																												M3-3		E-136AM
	5	1	600	600	0.36																												M1-4		E-136AM
CANAL ST. LT.	SIDEWALK CLOSED ← USE DETOUR	1	600	300	0.18						2		4.20																				SEE CONSTRUCTION SIGN DETAIL (2) MOUNT ON TYPE III BARRICADE (MOD.)	25	
CANAL ST. LT.	❯	2	450	600	0.54						4		9.60																				W1-8 ORANGE BACKGROUND MOUNT ON TYPE III BARRICADE (MOD.)		E-101M
CANAL ST. LT.	BRIDGE CLOSED	1	1200	750	0.90						2		5.10																				SEE CONSTRUCTION SIGN DETAIL (1) MOUNT ON TYPE III BARRICADE (MOD.)	24	
												m	m	m	m	m	m		EA	kg	kg	kg		kg	kg	kg	kg								
													18.90	36.98																						
TOTALS					m^2 6.86 ~~8.56~~	m^2	EA.	m^2				m 55.88			m					kg			EA.	kg				EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: BRATTLEBORO
PROJECT NUMBER: BHF 2000 (17)

FILE NAME: 94J078\Structures\sJ078tss8.I PLOT DATE: 24-MAY-2004
PROJECT MANAGER: R. R. WHITCOMB DRAWN BY: G. ROY
DESIGNED BY: G. ROY CHECKED BY: T. SUMNER
REVISED BY VAOT 04/22/2003 SHEET 22B OF 71