STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 1.75	SQUARE STEEL (in) lb/ft 2.0	SQUARE STEEL (in) lb/ft 2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0	TUBULAR ALUMINUM Ø (in) lb/ft 4.0	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD	TUBULAR STEEL Ø (in) FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0	TUBULAR STEEL Ø (in) lb/ft 3.5	TUBULAR STEEL Ø (in) lb/ft 4.0	TUBULAR STEEL Ø (in) lb/ft 5.0	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																								
RAMP "B"																																				
STATION 54+24, RT RAMP	W3-3, SIGNAL AHEAD						1				2 +						X	2 +																RELOCATE EXISTING SIGN ON NEW POSTS		
STATION 57+14, RT RAMP "B"	ST. MICHAEL'S COLLEGE DI-1, GUIDE SIGN, ST. MICHAEL'S COLLEGE						1				2						X	2																RELOCATE EXISTING SIGN ON NEW POSTS		
	CHAMPLAIN VALLEY EXPOSITION 2 DI-1, GUIDE SIGN, CHAMPLAIN VALLEY EXPOSITION						1																											RELOCATE EXISTING SIGN ON NEW POSTS (SUB-MOUNT WITH PREVIOUS SIGN)		
	SERVICES SERVICE SIGN, SERVICES		54	7.5	2.82																													INSTALL NEW SIGN ON NEW POSTS (SUB-MOUNT WITH PREVIOUS SIGNS)		STD. E-133
	WRONG WAY R5-1A, WRONG WAY						1																											RELOCATE EXISTING SIGN ON NEW POSTS (MOUNT BACK TO BACK WITH PREVIOUS SIGNS)		
STATION 57+18, LT RAMP "B" 57+25	WRONG WAY R5-1A, WRONG WAY						1				2					X		2																RELOCATE EXISTING SIGN ON NEW POSTS		
STATION 57+53 RAMP "B" OVERHEAD	15 WEST Winooski GUIDE SIGN ROUTE 15 WEST WINOOSKI	1	138	132		126.5																												INSTALL NEW SIGN ON NEW OVERHEAD SIGN SUPPORT, CENTER ARROW OVER LEFT-MOST LANE	SHEET 53	
STATION 57+53 RAMP "B" OVERHEAD	15 EAST Essex Junction GUIDE SIGN ROUTE 15 EAST ESSEX JUNCTION	1	186	132		170.5																												INSTALL NEW SIGN ON NEW OVERHEAD SIGN SUPPORT, CENTER ARROWS OVER MIDDLE AND RIGHT-MOST LANES	SHEET 53	
STATION 58+02, LT RAMP "B"	ONLY ONLY ONLY VR-936, LEFT, RIGHT, RIGHT	1	54	30	11.25						2					X		2																INSTALL NEW SIGN ON NEW POSTS		STD. E-145B
STATION 58+02, RT RAMP "B"	ONLY ONLY ONLY VR-936, LEFT, RIGHT, RIGHT	1	54	30	11.25						2					X		2																INSTALL NEW SIGN ON NEW POSTS		STD. E-145B
SLIP RAMP																																				
STATION 80+79, RT SLIP RAMP	OMI-1, OBJECT MARKER						1				1					X		1																RELOCATE EXISTING SIGN ON NEW POST		
STATION 81+46, LT SLIP RAMP	DO NOT ENTER R5-1, DO NOT ENTER						1																											RELOCATE EXISTING SIGN ON NEW PEDESTAL POST 4		
	NO TURN ON RED R10-11B, NO TURN ON RED	1	30	30	6.25																													INSTALL NEW SIGN ON NEW PEDESTAL POST 4 (MOUNT BACK TO BACK WITH PREVIOUS SIGN)		SHS PAGE 1-141
STATION 81+46, RT SLIP RAMP	DO NOT ENTER R5-1, DO NOT ENTER						1				1					X		1																RELOCATE EXISTING SIGN ON NEW POST		
												FT	FT	FT	FT	FT 104.25	FT 44.5		EA	LB	LB	LB		LB	LB	LB	LB								
	TOTALS				SF 31.57	SF 297	EA. 8	SF				FT			FT 148.75					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE VTRANS STANDARD SHEETS AND THE "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: WINOOSKI
PROJECT NUMBER: NH 089-3(65)

FILE NAME: z94a198tss.dgn
PROJECT LEADER: KEN UPMAL
DESIGNED BY: J.SOBEL
TRAFFIC SIGN SUMMARY SHEET 1

PLOT DATE: 2/22/2010
DRAWN BY: J.WILTSHIRE
CHECKED BY: D.FLYNN
SHEET 44 OF 67