

# QUANTITY SHEET



SUMMARY OF ESTIMATED QUANTITIES										TOTALS			DESCRIPTIONS		DETAILED SUMMARY OF QUANTITIES		
WPD #1 NON-PART COST	EROSION CONTROL	STP ADAS(2)	NHG SGNL (26)S	BRIDGE QUANTITY	ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS				
			85		4	85		CM	COMMON EXCAVATION	203.15							
			28		1	28		CM	SOLID ROCK EXCAVATION (SIDEWALK REMOVAL)	203.16							
240		180	32		8	452		CM	TRENCH EXCAVATION OF EARTH	204.20							
23		26	3		8	52		CM	TRENCH EXCAVATION OF ROCK	204.21							
		1130			8	1130		SM	COLD PLANING-BIT PAVEMENT	210.10							
		154	16		2	170		T	SUBBASE OF CRUSHED GRAVEL (FINE GRADED)	301.28							
			800		15	800		KG	EMULSIFIED ASPHALT	404.85							
			190		1	190		T	BITUMINOUS CONCRETE PAVEMENT	406.25							
													BITUMINOUS CONCRETE PAVEMENT				
											139	T	MAINLINE WEARING COURSE (TYPE III)				
											49	T	LEVELING (TYPE IV)				
											2	T	ROUNDING				
											190	T	TOTAL				
4		20				24		CM	CONCRETE, CLASS B	501.25							
260		1300			34	1560		KG	REINFORCING STEEL	507.15							
		46			1	46		L	WATER REPELLENT	514.10							
		10				10		M	METAL HAND RAILING (2-RAIL)	525.15							
		2				2		M	450 mm RCP CLASS III	601.0815							
									BEGIN OPTION ITEM								
		20			1	20		M	450 mm RCP CLASS III	601.0815							
		20			1	20		M	450 mm CPEP (SL)	601.2615							
									END OPTION ITEM								
					1	1		EACH	REHABING DI CB OR MH CLASS I	604.412							
					6	6		EACH	CAST IRON GRATE WITH FRAME, TYPE D	604.47							
					4	4		HR	POWER GRADER RENTAL	608.15							
					4	4		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25							
					2	3		HR	POWER BROOM RENTAL, TYPE II	608.31							
					4	4		HR	TRUCK RENTAL	608.37							
					4	4		HR	LOADER RENTAL, TYPE I	608.40							
		95				95		M	VERTICAL GRANITE CURB	616.21							
		60				60		M	REMOVAL OF EXISTING CURB	616.41							
		235				235		SM	PORTLAND CEMENT CONCRETE SIDEWALK, 125 MM	618.10							
		26				26		SM	BRICK PAVING	618.20							
4		2				6		CM	INSULATION BOARD	622.10							
		40				40		M	PVC SEWER PIPE (450 mm, CL 100, AWWA C905)	628.35							
120						120		M	DUCTILE, IRON PIPE, CEM LINED (300mm CL 52)	629.24							
1						1		EACH	GATE VALVE WITH VALVE BOX (150mm)	629.27							
1						1		EACH	GATE VALVE WITH VALVE BOX (200mm)	629.27							
1						1		EACH	GATE VALVE WITH VALVE BOX (300mm)	629.27							

FINAL QUANTITIES ARE ARCHIVED  
WITH THE FIELD BOOKS

Scanned