



- NOTES**
1. ALL CONSTRUCTION MUST COMPLY WITH THE NATIONAL ELECTRICAL CODE AND UTILITY COMPANY REQUIREMENTS.
 2. STANCHIONS MUST BE PLACED OUTSIDE THE CLEAR ZONE OR THEY MUST BE PROTECTED BY GUARDRAIL. THE LOCATION OF STANCHIONS MUST BE APPROVED BY THE UTILITY COMPANY PRIOR TO CONSTRUCTION.
 3. THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING ALL MATERIALS, EXCEPT FOR STANDOFF BRACKETS WHICH ARE USUALLY FURNISHED AND INSTALLED BY THE UTILITY COMPANY. THE CONTRACTOR IS RESPONSIBLE FOR INSTALLING ALL MATERIALS, EXCEPT THOSE ATTACHED TO THE UTILITY POLE. ALL MATERIAL AND INSTALLATION COSTS FOR THE POWER SERVICE, STREET LIGHTING OR SIGN ITEM, WHICHEVER IS APPLICABLE.
 4. ALL EXPOSED METAL EQUIPMENT MUST BE GROUNDED.
 5. ATTACH CONDUIT ON THE SIDE OF THE POLE OR STANCHION AWAY FROM TRAFFIC. CONTACT THE LOCAL UTILITY COMPANY FOR FINAL PLACEMENT.
 6. MATERIALS AND DIMENSIONS APPLY TO ALL STANCHIONS.
 7. IN RURAL AREAS, WITH THE PERMISSION OF THE UTILITY COMPANY, THE METER AND THE DISCONNECT MAY BE INSTALLED ON AN EXISTING UTILITY POLE. SEE OPTION #4.
 8. OPTION #1, #2, #3 OR #5 MAY BE USED IN URBAN AREAS, EITHER RESIDENTIAL OR COMMERCIAL, OR AS DETERMINED BY THE UTILITY AND APPROVED BY THE ENGINEER.
 9. THE METER AND DISCONNECT SHALL BE ATTACHED THE STANCHION/POLE WITH TWO LENGTHS OF GALVANIZED BACKING MATERIAL.
 10. SERVICE CONDUIT SHALL BE MINIMUM 2 INCH. SMALLER CONDUIT MAY BE ALLOWED WITH PRIOR APPROVAL FROM THE UTILITY AND THE ENGINEER AND AFTER CONSULTATION WITH THE TRAFFIC & SAFETY DIVISION.
 11. WHEN MORE THAN ONE GROUND ELECTRODE IS REQUIRED, THEY SHALL BE A MINIMUM OF 6' APART.
 12. METERS MAY NOT BE REQUIRED BY ALL UTILITY COMPANIES.
 13. ALL EXPOSED CONDUIT SHALL BE SCHEDULE 80.

LEGEND

ITEM	MATERIAL
CL	BONDING LUG (IF STEEL CONDUIT)
C-40	CONDUIT - PVC SCHEDULE 40
C-80	CONDUIT - PVC SCHEDULE 80
CN	CONDUIT NIPPLE
FA	FEMALE ADAPTER OR COUPLINGS AS REQUIRED
GR	GROUND ELECTRODE, 3/4" X 8' (MIN) COPPER CLAD (2 REQ.)
GW	GROUND CONDUCTOR, #6 AWG CU (MIN)
SB	STANDOFF BRACKET (SEE DETAIL)
SJ	SLIP JOINT, INSTALL 2/3 OPEN
SSS	STAINLESS STEEL STRAP (1/2" MIN)
SW	90° SWEEPS, (PVC) 36" R. - SERVICE, 24" R. - LOAD
TB	THREADED BUSHING
WH	WEATHERHEAD OR CONDULATOR

FRONT VIEW METER (SHOWN FOR AERIAL SERVICE)

THE POWER SERVICE METER AND DISCONNECT SHALL HAVE A CONTINUOUS GROUND CONDUCTOR FROM THE METER TO THE GROUND ELECTRODE. OTHER GROUND CONDUCTORS MAY BE CONNECTED TO THIS CONTINUOUS GROUND CONDUCTOR WITH SPLIT NUTS. SEE THE STRAIN POLE/ FOOTING DETAIL SHEET.

REVISIONS AND CORRECTIONS
NOV. 17, 1993 - DATE OF ORIGINAL ISSUE

APPROVED
Stanley B. MacArthur
DIRECTOR OF ENGINEERING
David A. Ross
TRAFFIC AND SAFETY ENGINEER

POWER DROP STANCHIONS

OTHER STDS. E-171A REQUIRED (WHEN OPTION #5 IS USED) SEE PLANS FOR OPTION #

STANDARD E-175

//trnf/std/ardel75.dgn - stdel75.1