

AS-BUILT/RECORDED DRAWINGS

STANDARD SHEETS

E-111 03-11-97
 E-115 06-06-99
 E-113 06-06-99
 F6 06-01-84

FINAL CONTRACT
 PLANS 10/31/01

QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	QUANTITY	FINAL
201.11	CLEARING & GRUBBING (INCLUDING INDIVIDUAL TREES AND STUMPS)	ASFE	1	
203.15	COMMON EXCAVATION	CY	260	
307.25	SUBBASE OF CRUSHED GRAVEL (FINE GRADED)	CY	330	
406.25	BITUMINOUS CONCRETE PAVEMENT (PS4-28)	TON	60	
541.21	CONCRETE VAULT (MOD-TELEPHONE)	EA	3	
541.21	CONCRETE VAULT (MOD-CATV)	EA	4	
601.0415	18" WOOD POST (2" x 2" x 1/2")	LF	48	
616.40	REMOVING AND RESETTING CURB	LF	10	
618.10	PORTLAND CEMENT CONCRETE SIDEWALK 3" THICK	SY	8	
620.16	GATE FOR CHAIN LINK FENCE, 8 FEET (MOD)	LF	40	
621.57	ENERGY ABSORPTION ATTENUATOR	EA	2	
621.60	TEMPORARY TRAFFIC BARRIER	LF	843	
624.20	BUCKS, CONCRETE ENCASED (MOD-DUCT BANK-18 TO 22)	LF	1,860	
624.20	BUCKS, CONCRETE ENCASED (MOD-DUCT BANK, ROADWAY-18 TO 22)	LF	330	
624.20	BUCKS, CONCRETE ENCASED (MOD-DUCT BANK, THROUGH SLEEVES-18 TO 22)	LF	375	
630.10	UNIFORMED TRAFFIC OFFICER	HR	150	
635.10	MOBILIZATION - MOD 1	LS	1	
641.10	TRAFFIC CONTROL-MOD 2	LS	1	
643.00	JACKING OR BORING WELDED STEEL PIPE (36")	LF	370	
651.15	SEED	LB	10	
651.18	FERTILIZER	LB	70	
651.20	AGRICULTURAL LIMESTONE	TON	0.3	
651.30	SODDING	SY	90	
651.35	TOPSOIL	CY	78	
676.27	PULL BOX-DOUBLE	EA	4	

STATE OF VERMONT
 AGENCY OF TRANSPORTATION

Town Of SOUTH BURLINGTON Bridge No. 68
 Highway No. U.S. 2 Span: 51a
 U.S. 2 OVER I-89

TELECOMMUNICATIONS DETAILS

Designed By: M. HAYES Drawn By: M. HAYES
 Checked By: Date Bridge Design Supervisor: S. JOHNSON Date

PROJECT: SOUTH BURLINGTON PROJECT NO: M (EX)(3)
 VHB Contract No. VTrans-Telecom Date 10/31/01
 Bridge Sheet No. TD 1 OF 8 Sheet 59 of 75

VANASSE HANGEN BRUSTLIN, INC.