

ITEM DETAIL SUMMARY SHEET



LOCATION			GUARD RAIL										DROP INLETS			DRAINAGE				MISCELLANEOUS				REMARKS
STATION	STATION	POS.	621.20		621.20	621.54	621.60	621.75	621.76	621.77	621.80	621.81	CHANGE ELEV. D.I.	REHAB. D.I.	GRATE/ TYPE	NEW PIPE				203.15	203.16	301.28	618.10	
			WOOD POST G.R.	STEEL POST G.R.	2.4 m STEEL POST G.R.	WOOD POST M.E.L.T.	ANCHOR FOR G.R.	REMOVE & RESET G.R.	REPLACE G.R. POST ASSEMBLY	REPLACE BEAM UNIT	REMOVE & DISP. G.R.	REMOVE & DISP. G.P.				DIA.	LENGTH	THICK. OF PIPE	STONE FILL/ TYPE	COMMON EXCAVATION	SOLID ROCK EXCAVATION	SUBBASE OF CRUSHED GRAVEL	P.C.C. SIDEWALK 125 mm	
			m.	m.	m.	EA	EA	m.	EA	EA	m	EA	EA	EA		mm.	m.			m ³	m ³	t.	m ²	
7+086.0	7+189.0	RT				1			12	6	12.0													REMOVE EXISTING 4.8 m RADIUS AND ANCHOR AND INSTALL NEW MELT AT STA. 7+086.0
7+124.4	7+192.8	LT				2		68.4			12.6													INSTALL NEW MELT AT STA. 7+124.4 & STA. 7+192.8
7+748.0		RT										1												
7+391.0	7+840.0	LT							18	6														
7+926.0	7+975.0	RT							4	2														
8+046.3	8+104.5	LT			58.2		2				57.5													SEE VAOT STANDARD SHEET G-1D. PROVIDE ANCHOR AT STA. 8+048.8 & STA. 8+102.0
8+125.1	8+129.5	LT		4.4			1				4.4													SEE VAOT STANDARD SHEET G-1D. PROVIDE ANCHOR AT STA. 8+127.6
8+131.6	8+136.0	RT		4.4			1				4.4													SEE VAOT STANDARD SHEET G-1D. PROVIDE ANCHOR AT STA. 8+134.1
8+157.0	8+170.0	RT						2	1															
8+248.0		LT										1												
SHEET SUBTOTAL				8.8	58.2	3	4	68.4	36	15	90.9	2												
SHEET 30 SUBTOTAL				238.0	95.0	9	4	7.6	-	-	404.3	12												
ROUNDING				13.2	6.8	-	-	4.0	-	-	24.8	-												
TOTAL				260.0	160.0	12	8	80.0	36	15	520.0	14												

DATUM
VERTICAL N/A
HORIZONTAL N/A

ITEM
DETAIL
SHEET 2

SURVEYED BY N/A DATE N/A
DRAWN BY E.C.D. DATE 11/97
SQUAD LEADER T.P.K.
DESIGN FILE NO. /pave/95b022/pb022.dgn
IPARM FILE pb0221021 DATE PLOTTED 20-JAN-1998
PROJ. NAME DORSET
PROJ. NO. STP 9604(IIS)
SHEET 31 OF 43 SHEETS