QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

		FULL CE	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
				1	1	LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10	EST.
				1	1	AC	THINNING AND TRIMMING	201.30	EST.
				1	1	EA	THINNING AND TRIMMING FOR SIGNS	201.31	EST.
				700	700	CY	EARTH BORROW	203.30	EST.
				5300	5300	CY	TRENCH EXCAVATION OF EARTH	204.20	8.9
				15	15	CY	TRENCH EXCAVATION OF ROCK	204.21	EST.
				1	1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-
				8	8	CY	GRANULAR BACKFILL FOR STRUCTURES	204.30	-
				103000	103000	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	842.9
				45000	45000	TON	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.28	431.2
				122000	122000	SY	RECLAIMED STABILIZED BASE	310.20	166
				1750	1750	TON	AGGREGATE SHOULDERS	402.12	18
				1	1	LU	PRICE ADJUSTMENT ASPHALT CEMENT (N.A.B.I.)	406.50	-
				14400	14400	CWT	EMULSIFIED ASPHALT, COLD MIX	415.25	EST.
				23500	23500	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	179
				1	1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
				1	1	LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32	-
				1	1	LU	SURFACE TOLERANCE PAY ADJUSTMENT (N.A.B.I.)	490.33	-
				1	1	LU	LONGITUDINAL JOINT COMPACTION PAY ADJUSTMENT (N.A.B.I.)	490.34	-
			50		50	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	4
			10		10	CF	RAPID SETTING CONC. REPAIR MAT. W/ COARSE AGG.	580.20	-
				4	4	LF	15" CSP .064 (2-2/3X1/2)	601.0010	1
				8	8	LF	18" CSP .064 (2-2/3X1/2)	601.0015	-
				6	6	LF	18" RCP CLASS III	601.0815	-
				10	10	LF	18" CPEP(SL)	601.2615	1
				1	1	EA	REHAB DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	-
				17900	17900	LF	6 INCH UNDERDRAIN PIPE	605.10	69
				400	400	LF	6 INCH UNDERDRAIN CARRIER PIPE	605.20	35
				73	73	EA	UNDERDRAIN FLUSHING BASIN	605.95	-
				520	520	HR	POWER GRADER RENTAL	608.15	EST.
				920	920	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.
				190	190	HR	POWER BROOM RENTAL,TYPE I	608.30	EST.
				90	90	HR	POWER BROOM RENTAL,TYPE II	608.31	EST.
				1840	1840	HR	TRUCK RENTAL	608.37	EST.
				520	520	HR	LOADER RENTAL, TYPE I	608.40	EST.
				3200	3200	CY	STONE FILL, TYPE I	613.10	57.1
				130	130	CY	STONE FILL, TYPE II	613.11	EST.

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		TRENCH EXCAVATION OF EARTH
8	CY	ITEM DETAIL SUMMARY SHEET 4
5283.1	CY	UNDERDRAIN DETAIL SHEET
8.9	CY	ROUNDING
5300	CY	TOTAL
		COLD PLANING - BITUMINOUS PAVEMENT
100495.8	SY	MAINLINE
1661.4	SY	SIDEROAD APRONS
842.9	SY	ROUNDING
103000	SY	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
		WEARING COURSE
10608.0	TON	TYPE IVS
		INTERMEDIATE COURSE
12376.0	TON	TYPE IIIS
		SIDE ROADS
155.6	TON	TYPE IVS
181.4	TON	TYPE IIIS
179.0	TON	ROUNDING
23500	TON	TOTAL
		STONE FILL, TYPE I
1797.9	CY	ITEM DETAIL SUMMARY SHEET 4
1345	CY	DITCH CLEANING DETAIL SHEET
57.1	CY	ROUNDING
3200	CY	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: ADDISON - NEW HAVEN
PROJECT NUMBER: STP 9632(I)

FILE NAME: p95B076.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
PLOT FILE: p95B076_12.i

PLOT DATE: 3/13/2012
DRAWN BY: SJL
CHECKED BY: EPD
SHEET 12 OF 186