# QUANTITY SHEET 2

**STATE OF VERMONT**
**AGENCY OF TRANSPORTATION**

## SUMMARY OF ESTIMATED QUANTITIES

| | | FULL CE | BRIDGE | ROADWAY | QUANTITIES GRAND TOTAL | UNIT | ITEMS | ITEM NO. | ROUNDING |
|---|---|---|---|---|---|---|---|---|---|
| | | | | 13 | 13 | EA | RELOCATE MAILBOX, SINGLE SUPPORT | 617.10 | EST. |
| | | | | 200 | 200 | EA | YIELDING MARKER POSTS | 619.17 | 1 |
| | | | | 2650 | 2650 | LF | REMOVING AND RESETTING FENCE | 620.50 | 35 |
| | | | | 5675 | 5675 | LF | STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS | 621.205 | 12.75 |
| | | | | 375 | 375 | LF | STEEL BEAM GUARDRAIL, GALVANIZED/NESTED W/8 FEET POSTS | 621.207 | - |
| | | | | 190 | 190 | LF | HD STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS | 621.215 | - |
| | | | | 38 | 38 | EA | ANCHOR FOR STEEL BEAM RAIL | 621.60 | - |
| | | | | 1600 | 1600 | LF | REMOVAL AND DISPOSAL OF GUARDRAIL | 621.80 | - |
| | | | | 300 | 300 | HR | UNIFORMED TRAFFIC OFFICERS | 630.10 | EST. |
| | | | | 4000 | 4000 | HR | FLAGGERS | 630.15 | EST. |
| | | 1 | | | 1 | LS | FIELD OFFICE, ENGINEERS | 631.10 | - |
| | | 1 | | | 1 | LS | TESTING EQUIPMENT, BITUMINOUS | 631.17 | - |
| | | 3000 | | | 3000 | DL | FIELD OFFICE TELEPHONE (N.A.B.I.) | 631.26 | - |
| | | | | 1 | 1 | LS | MOBILIZATION/DEMOBILIZATION | 635.11 | - |
| | | | | 1 | 1 | LS | TRAFFIC CONTROL | 641.10 | - |
| | | | | 5 | 5 | EA | PORTABLE CHANGEABLE MESSAGE SIGN | 641.15 | EST. |
| | | | | | | | BEGIN OPTION AA | | |
| | | | | 78000 | 78000 | LF | DURABLE 4 INCH WHITE LINE, THERMOPLASTIC | 646.402 | 697 |
| | | | | 78000 | 78000 | LF | DURABLE 4 INCH WHITE LINE, EPOXY PAINT | 646.403 | 697 |
| | | | | 78000 | 78000 | LF | DURABLE 4 INCH WHITE LINE, POLYUREA | 646.404 | 697 |
| | | | | | | | END OPTION AA | | |
| | | | | | | | BEGIN OPTION BB | | |
| | | | | 70000 | 70000 | LF | DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC | 646.412 | 592 |
| | | | | 70000 | 70000 | LF | DURABLE 4 INCH YELLOW LINE, EPOXY PAINT | 646.413 | 592 |
| | | | | 70000 | 70000 | LF | DURABLE 4 INCH YELLOW LINE, POLYUREA | 646.414 | 592 |
| | | | | | | | END OPTION BB | | |
| | | | | | | | BEGIN OPTION CC | | |
| | | | | 270 | 270 | LF | DURABLE 24 INCH STOP BAR, THERMOPLASTIC | 646.482 | 6 |
| | | | | 270 | 270 | LF | DURABLE 24 INCH STOP BAR, EPOXY PAINT | 646.483 | 6 |
| | | | | 270 | 270 | LF | DURABLE 24 INCH STOP BAR, POLYUREA | 646.484 | 6 |
| | | | | | | | END OPTION CC | | |
| | | | | | | | BEGIN OPTION DD | | |
| | | | | 66 | 66 | EA | DURABLE LETTER OR SYMBOL, THERMOPLASTIC | 646.492 | - |
| | | | | 66 | 66 | EA | DURABLE LETTER OR SYMBOL, EPOXY PAINT | 646.493 | - |
| | | | | 66 | 66 | EA | DURABLE LETTER OR SYMBOL, POLYUREA | 646.494 | - |
| | | | | | | | END OPTION DD | | |

## DETAILED SUMMARY OF QUANTITIES

| QUANTITIES | UNIT | ITEMS |
|---|---|---|
| | | YIELDING MARKER POSTS |
| | | |
| 80 | EA | ITEM DETAIL SUMMARY SHEET 4 |
| 119 | EA | UNDERDRAIN DETAIL SHEET |
| 1 | EA | ROUNDING |
| 200 | EA | TOTAL |

## DETAILED SUMMARY OF QUANTITIES

| QUANTITIES | UNIT | ITEMS |
|---|---|---|

PROJECT NAME: ADDISON - NEW HAVEN
PROJECT NUMBER: STP 9632(1)

FILE NAME: p95B076.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
PLOT FILE: p95B076_13.i

PLOT DATE: 3/13/2012
DRAWN BY: SJL
CHECKED BY: EPD
SHEET 13 OF 186