

SITE	LOCATION			FEET OF DITCHING			MISC. ITEMS			REMARKS
	STA.	STA.	POS.	PERCENT GRADE	TEMP. EROS. MATT.	STONE FILL TYP.	653.20	613.10	649.31	
	VT 17			0-2.5	2.5-10					
ADDISON							SY	CY	SY	
1	445+50	448+00	RT	250			111			
2	455+15	464+65	LT	265	685		118	101	457	
3	455+15	464+65	RT	265	685		118	101	457	
4	465+15	481+00	RT	1100	485		489	72	323	
5	506+90	517+45	RT		1055			156	703	
6	528+50	538+50	RT	750	250		333	37	167	
7	549+65	559+70	RT	255	750		113	111	500	
WEYBRIDGE										
8	a 0+00	a 5+25	LT	175	350		78	52	233	
NEW HAVEN										
9	b 9+20	b 10+35	LT	115			51			
10	b 21+10	b 26+40	LT	530			236	5	20	USE STONE FILL AROUND INLET AT STA. b 26+26 LT
11	b 41+20	b 44+90	LT	270	100		120	15	67	
12	b 58+10	b 68+60	LT	1050			467			
13	b 73+90	b 79+20	LT	320	210		142	31	140	
14	b 89+75	b 95+05	LT	230	300		102	44	200	
15	b 95+05	b 97+70	RT	165	100		39	67		STONE LINE ENTIRE LENGTH OF DITCH
WALTHAM										
16	c 2+65	c 15+85	RT	150	1170		67	173	780	
17	c 12+95		RT					5	20	USE STONE FILL AROUND INLET
18	c 26+40	c 37+50	RT	310	800		138	119	533	
NEW HAVEN										
19	d 122+25	d 125+25	RT	300			133			
20	d 126+25	d 130+50	RT	425			189			
21	d 138+35	d 143+65	RT	200	230		89	34	153	
22	d 154+20	d 160+00	RT	480	100		213	15	67	
23	d 159+00	d 161+00	RT	200			89			
24	d 160+50	d 174+25	RT		1375			204	917	
25	d 161+75	d 162+25	RT	50			22			
26	d 163+50	d 165+35	LT	185			82			
27	d 176+90	d 182+13	RT	313	210		139	31	140	
ADDISON SUBTOTAL				2885	3910		1282	578	2607	
WEYBRIDGE SUBTOTAL				175	350		78	52	233	
NEW HAVEN SUBTOTAL				4833	2625		2074	418	1771	
WALTHAM SUBTOTAL				460	1970		205	297	1331	
ROUNDING				47	5					
TOTAL				8400	8860		3639	1345	5944	

SITE	LOCATION			FEET OF DITCHING			MISC. ITEMS			REMARKS
	STA.	STA.	POS.	PERCENT GRADE	TEMP. EROS. MATT.	STONE FILL TYP.	653.20	613.10	649.31	

NOT TO SCALE

**DITCH CLEANING
DETAIL
SHEET**

PROJECT NAME: ADDISON - NEW HAVEN
PROJECT NUMBER: STP 9632(1)

FILE NAME: p95B076.dgn PLOT DATE: 3/13/2012
PROJECT LEADER: CDL DRAWN BY: SJL
DESIGNED BY: SJL CHECKED BY: EPD
PLOT FILE: p95B076_19.1 SHEET 19 OF 186

**DITCH DETAIL < 2.5 PERCENT
NOT TO SCALE**

**DITCH DETAIL > 2.5 PERCENT
NOT TO SCALE**

NOTES:

- PIPE INLET AND OUTLET AREAS AND DITCH CLEANING THROUGHOUT THE PROJECT SHALL BE PERFORMED AT LOCATIONS IDENTIFIED ON THIS SHEET AND AS DIRECTED BY THE RESIDENT ENGINEER. PAYMENT WILL BE UNDER THE APPLICABLE EQUIPMENT RENTAL ITEM(S).
- GRADES LESS THAN 1 PERCENT SHALL USE ITEM 651.15, SEED AND ITEM 651.25, HAY MULCH. GRADES BETWEEN 1 AND 2.5 PERCENT SHALL USE ITEM 651.25, HAY MULCH OR ITEM 653.20, TEMPORARY EROSION MATTING AS DIRECTED BY THE RESIDENT ENGINEER. GRADES OVER 2.5 PERCENT SHALL USE ITEM 649.31, GEOTEXTILE UNDER STONE FILL AND ITEM 613.10, STONE FILL TYPE 1 AS DIRECTED BY THE RESIDENT ENGINEER.

NOT TO SCALE

DITCH CLEANING DETAIL SHEET	PROJECT NAME: ADDISON - NEW HAVEN
	PROJECT NUMBER: STP 9632(1)
FILE NAME: p95B076.dgn	PLOT DATE: 3/13/2012
PROJECT LEADER: CDL	DRAWN BY: SJL
DESIGNED BY: SJL	CHECKED BY: EPD
PLOT FILE: p95B076_19.1	SHEET 19 OF 186