

Element	Point Type	Station	Northing	Easting	Radius	Length	Delta / Theta	Rotation Direction	Maximum Banking	Design Speed
Tangent	POB	442+97.00	580190.5369	1429623.172						
	PC	444+46.47	580168.2173	1429770.963						
Arc	PC	444+46.47	580168.2173	1429770.963						
	PI	446+58.29	580136.5863	1429980.411						
	CC		578907.5129	1429580.57	1275	419.81	18°51'55.50"	Right	0.042	35
	PT	448+66.28	580038.9303	1430168.38						
Tangent	PT	448+66.28	580038.9303	1430168.38						
	PC	451+54.00	579906.2828	1430423.7						
	PC	451+54.00	579906.2828	1430423.7						
Arc	PI	454+78.41	579756.7233	1430711.573	7200	648.37	5°09'34.48"	Left	NC	35
	CC		586295.463	1433743.094						
	PT	458+02.37	579633.6582	1431011.729						
Tangent	PT	458+02.37	579633.6582	1431011.729						
	PC	474+41.69	579011.7711	1432528.513						
	PC	474+41.69	579011.7711	1432528.513						
Arc	PI	476+62.27	578928.0954	1432732.598	7300	441.01	3°27'40.97"	Right	NC	45
	CC		572257.4411	1429759.212						
	PT	478+82.70	578832.2507	1432931.258						
Tangent	PT	478+82.70	578832.2507	1432931.258						
	PC	483+92.56	578610.7045	1433390.465						
	PC	483+92.56	578610.7045	1433390.465						
Arc	PI	484+76.50	578574.2286	1433466.069	530	166.5	18°00'00.00"	Left	0.070	45
	CC		579088.0536	1433620.764						
	PCC	485+59.07	578562.9012	1433549.245						
	PCC	485+59.07	578562.9012	1433549.245						
	PI	486+38.00	578552.2491	1433627.462						
	CC		579172.2762	1433632.234						
	PT	487+16.08	578561.6961	1433705.834						
Tangent	PT	487+16.08	578561.6961	1433705.834						
	PC	488+94.78	578583.0811	1433883.242						
	PC	488+94.78	578583.0811	1433883.242						
Arc	PI	491+60.32	578614.86	1434146.877	33500	531.08	0°54'29.92"	Left	NC	45
	CC		611842.3205	1429874.128						
	PT	494+25.85	578650.8142	1434409.975						
Tangent	PT	494+25.85	578650.8142	1434409.975						
	PC	499+90.76	578727.3016	1434969.679						
	PC	499+90.76	578727.3016	1434969.679						
Arc	PI	501+32.24	578746.4585	1435109.862	38500	282.97	0°25'16.02"	Right	NC	45
	CC		540581.8391	1440182.518						
	PT	502+73.73	578764.5846	1435250.182						
Tangent	PT	502+73.73	578764.5846	1435250.182						
	PC	512+47.57	578889.3456	1436215.995						
	PC	512+47.57	578889.3456	1436215.995						
Arc	PI	513+34.46	578900.4774	1436302.17	660	172.79	15°00'00.00"	Right	0.080	45
	CC		578234.7843	1436300.55						
	PCC	514+20.35	578888.9263	1436388.289						
	PCC	514+20.35	578888.9263	1436388.289						
	PI	515+84.32	578867.1283	1436550.804						
	CC		578423.0979	1436325.808						
	PT	517+35.88	578748.971	1436664.492						
Tangent	PT	517+35.88	578748.971	1436664.492						
	PC	521+79.74	578429.1237	1436972.241						
	PC	521+79.74	578429.1237	1436972.241						
Arc	PI	522+81.98	578355.4556	1437043.122	40000	204.46	0°17'34.33"	Right	NC	45
	CC		550695.2393	1408148.09						
	PT	523+84.21	578281.4262	1437113.627						
Tangent	PT	523+84.21	578281.4262	1437113.627						
	PC	524+41.02	578240.2822	1437152.811						
	PC	524+41.02	578240.2822	1437152.811						
Arc	PI	526+11.49	578116.839	1437270.376	610	332.46	31°13'36.56"	Left	0.080	45
	CC		578660.9715	1437594.536						
	PT	527+73.48	578072.2289	1437434.904						
Tangent	PT	527+73.48	578072.2289	1437434.904						
	PC	530+72.24	577994.0452	1437723.257						
	PC	530+72.24	577994.0452	1437723.257						
Arc	PI	532+11.79	577957.5264	1437857.944	1000	277.31	15°53'18.92"	Right	0.068	45
	CC		577028.8934	1437461.566						
	PT	533+49.55	577885.53	1437977.487						
Tangent	PT	533+49.55	577885.53	1437977.487						
	PC	535+65.38	577774.1781	1438162.376						
	PC	535+65.38	577774.1781	1438162.376						
Arc	PI	537+34.23	577687.0691	1438307.012	690	331.18	27°30'00.00"	Left	0.078	45
	CC		578365.2574	1438518.361						
	PCC	538+96.56	577676.5881	1438475.528						
	PCC	538+96.56	577676.5881	1438475.528						
	PI	539+92.86	577670.61	1438571.645						
	CC		580970.2238	1438680.38						
	PT	540+89.11	577670.2472	1438667.947						
Tangent	PT	540+89.11	577670.2472	1438667.947						
	PC	542+79.76	577669.5289	1438858.598						

Element	Point Type	Station	Northing	Easting	Radius	Length	Delta / Theta	Rotation Direction	Maximum Banking	Design Speed
Arc	PC	542+79.76	577669.5289	1438858.598						
	PI	544+12.90	577669.0273	1438991.737	12000	266.27	1°16'16.84"	Left	NC	45
	CC		589669.4437	1438903.809						
	PT	545+46.03	577671.4798	1439124.855						
Tangent	PT	545+46.03	577671.4798	1439124.855						
	PC	547+47.85	577675.1974	1439326.64						
	PC	547+47.85	577675.1974	1439326.64						
Arc	PI	549+09.63	577678.1774	1439488.39	1200	321.62	15°21'21.67"	Left	0.062	45
	CC		578874.9938	1439304.535						
	PT	550+69.47	577723.885	1439643.576						
Tangent	PT	550+69.47	577723.885	1439643.576						
	PC	552+77.04	577782.5302	1439842.687						
	PC	552+77.04	577782.5302	1439842.687						
Arc	PI	553+71.44	577809.2027	1439933.246	12000	188.81	0°54'05.32"	Right	NC	45
	CC		566271.4426	1443233.095						
	PT	554+65.84	577834.4471	1440024.212						
Tangent	PT	554+65.84	577834.4471	1440024.212						
	PC	558+24.10	577930.2478	1440369.424						
	PC	558+24.10	577930.2478	1440369.424						
Arc	PI	559+15.20	577954.6084	1440457.206	12000	182.2	0°52'11.71"	Left	0.020	45
	CC		589493.2524	1437160.542						
	PT	560+06.29	577980.2989	1440544.608						
Tangent	PT	560+06.29	577980.2989	1440544.608						
	PC	562+90.55	578060.4598	1440817.324						
	PC	562+90.55	578060.4598	1440817.324						
Arc	PI	564+24.38	578098.2022	1440945.727	1200	266.57	12°43'39.92"	Right	0.062	45
	CC		576909.1645	1441155.731						
	PT	565+57.12	578106.7274	1441079.291						
Tangent	PT	565+57.12	578106.7274	1441079.291						
	PC	572+88.82	578153.3367	1441809.512						
	PC	572+88.82	578153.3367	1441809.512						
Arc	PI	574+14.90	578161.3674	1441935.327	900	250.51	15°56'53.44"	Left	0.071	45
	CC		579051.5089	1441752.182						
	PT	575+39.34	578203.6591	1442054.094						
Tangent	PT	575+39.34	578203.6591	1442054.094						
	PC	576+60.70	578244.3703	1442168.422						
	PC	576+60.70	578244.3703	1442168.422						
Arc	PI	578+29.87	578301.1208	1442327.793	1400	336.71	13°46'48.80"	Right	0.056	45
	CC		576925.4928	1442638.062						
	PT	579+97.41	578318.276	1442496.094						
Tangent	PT	579+97.41	578318.276	1442496.094						
	PC	584+04.37	578359.5438	1442900.953						
	PC	584+04.37	578359.5438	1442900.953						
Arc	PI	584+93.35	578368.5668	1442989.474	12000	177.95	0°50'58.82"	Left	NC	45
	CC		590297.6854	1441684.083						
	PT	585+82.32	578378.9015	1443077.851						
Tangent	PT	585+82.32	578378.9015	1443077.851						
	PC	587+14.66	578394.2722	1443209.293						
	PC	587+14.66	578394.2722	1443209.293						
	PI	a 0+57.73	578409.9823	1443343.638						
	CC		579069.6699	1443130.312						
		587+92.19	578407.6424	1443285.617	680	267.04	22°30'00.00"	Left	0.078	45
		a 0+00.00								
Arc	PCC	a 1+89.51	578475.9082	1443461.744						
	PCC	a 1+89.51	578475.9082	1443461.744						
	PI	a 2+71.93	578516.0829	1443533.717						
	CC		580658.8558	1442243.245						
	PT	a 3+54.30								