STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 4

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS			NEW & SALVAGED SIGNS				EXIST POST		NEW SIGN POSTS																		REMARKS	SIGN DETAIL		
		EA	WIDTH (in)	HEIGHT (in)	"A"	"B"	SALV SIGN	SALV TIS	RETAIN	SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft			SQUARE STEEL (in) lb/ft			ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft			TUBULAR STEEL Ø (in) FOUND-ATION	lb/ft				W-SHAPE STEEL FTG. SIZE		WEIGHT	POST SIZE	SIGN REMOVED	SHS = FHWA STANDARD HIGHWAY SIGNS BOOK	DETAIL IN SHS	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
												1.12	2.0	3.0	1.75	2.0	2.5			3.0	4.0	4.0 MOD		7.6	9.0	10.8	14.6	24"	30"							
															1.88	2.42	3.35			1.3	1.7	1.7													
STA. 552+81 LT ADDISON							1				1					X		X														SALVAGED SIGN			
	OTTER CREEK RD						1																													
STA. 559+45 RT ADDISON	SCHOOL BUS STOP AHEAD						1				1					X		X														SALVAGED SIGN			
STA. 561+67 RT ADDISON							1				1					X		X														SALVAGED SIGN			
STA. 565+38 LT ADDISON							1				1					X		X														SALVAGED SIGN			
STA. 583+25 RT ADDISON							1				1					X		X														SALVAGED SIGN			
STA. 583+51 LT ADDISON	SPEED LIMIT 45						1				1					X		X														SALVAGED SIGN			
STA. 580+60 LT	23 JCT		24	24	4.00		1				1																					NEW SIGN INSTALLED ON NEW POST WITH SALVAGED SIGN			
STA. 582+25 LT							1				1																					SALVAGED SIGN ON NEW POST			
STA. 515+89 LT							1				2																					SALVAGED SIGN ON NEW POSTS			
												LF	LF	LF	LF	LF 90	LF		EA.	LB	LB	LB	EA.	LB	LB	LB	LB							
TOTALS		SF -	SF		EA. 7	SF						LF			LF 90					LB			EA.	LB				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET 4

PROJECT NAME: ADDISON - NEW HAVEN
PROJECT NUMBER: STP 9632(1)

FILE NAME: p95B076.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
PLOT FILE: p95B076_163.i

PLOT DATE: 3/13/2012
DRAWN BY: SJL
CHECKED BY: EPD
SHEET 163 OF 186