STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 8

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REMOVED REQUIRED	REMARKS SHS = FHWA STANDARD HIGHWAY SIGNS BOOK	SIGN DETAIL DETAIL IN SHS	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
STA. a 6+59 RT WEYBRIDGE	SPEED LIMIT 45	1	24	30	5.00						1					X		X														R2-1	SHS		
STA. a 7+25 LT WEYBRIDGE	JCT	1	21	15	2.19						1					X		X														M2-1 BLACK ON WHITE	SHS		
	23	1	24	24	4.00																														E-136C
STA. a 10+60 ~~RT~~ LT NEW HAVEN	Weybridge | New Haven	1	72	10	5.00		3				2					X		X														SALVAGED SIGNS ON NEW POSTS VD-024		182	
	0170 0122 0022	1	6	10	0.42																											VD-700			E-138
	0170 0113 0000	1	6	10	0.42																											VD-700			E-138
STA. a 10+67 RT WEYBRIDGE		1	12	36	3.00						1					X		X														OM-3R	SHS		
STA. a 10+67 LT WEYBRIDGE		1	12	36	3.00						1					X		X														OM-3L	SHS		
STA. b 1+57 LT NEW HAVEN		1	12	36	3.00						1					X		X														OM-3R	SHS		
STA. b 1+59 RT NEW HAVEN		1	12	36	3.00						1					X		X														OM-3L	SHS		
												LF	LF	LF	LF	LF 120	LF	EA.	LB	LB	LB		LB	LB	LB	LB								
TOTALS					SF 29.03	SF	EA.	SF				LF			LF 120				LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET 8

PROJECT NAME: ADDISON - NEW HAVEN
PROJECT NUMBER: STP 9632(1)

FILE NAME: p95B076.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
PLOT FILE: p95B076_167.i

PLOT DATE: 3/13/2012
DRAWN BY: SJL
CHECKED BY: EPD
SHEET 167 OF 186