STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 19

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REMOVED & REINSTALLED	REMARKS SHS = FHWA STANDARD HIGHWAY SIGNS BOOK	SIGN DETAIL DETAIL IN SHS	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
STA. d 137+28 RT NEW HAVEN	0170 0113 0260	1	6	10	0.42						1				X			X															VD-700			E-138
STA. d 144+29 LT NEW HAVEN	SPEED LIMIT 45	1	24	30	5.00						1					X		X															R2-1	SHS		
STA. d 147+84 LT NEW HAVEN	0170 0113 0280	1	6	10	0.42						1				X			X															VD-700			E-138
STA. d 149+86 RT NEW HAVEN	SPEED LIMIT 45	1	24	30	5.00						1					X		X															R2-1	SHS		
STA. d 161+07 RT NEW HAVEN	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X		X															VR-017			E-141
STA. D 145+86 RT																																	NEW POST FOR TEMPORARY BUMP SIGN - POST SALVAGED AT END OF PROJECT			
STA. D 144+86 LT																																	NEW POST FOR TEMPORARY BUMP SIGN - POST SALVAGED AT END OF PROJECT			
											LF	LF	LF		LF 16	LF 45	LF 61	EA.		LB	LB	LB		LB	LB	LB	LB	EA.	EA.	LB						
	TOTALS				SF 15.84	SF	EA.	SF			LF				LF					LB			EA.	LB				EA.	EA.	LB						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET 19

PROJECT NAME: ADDISON - NEW HAVEN
PROJECT NUMBER: STP 9632(1)

FILE NAME: p95B076.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
PLOT FILE: p95B076_178.i

PLOT DATE: 3/13/2012
DRAWN BY: SJL
CHECKED BY: EPD
SHEET 178 OF 186