STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 22

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS SHS = FHWA STANDARD HIGHWAY SIGNS BOOK	SIGN DETAIL DETAIL IN SHS	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
STA. d 180+53 RT NEW HAVEN	NORTH EAST SOUTH	1	24	12	2.00						2												2	274							*3	M3-1 SIGN FRAME REQUIRED BLACK ON WHITE	SHS		
		1	24	12	2.00																											M3-2 GREEN ON WHITE	SHS		
		1	24	12	2.00																											M3-3 BLACK ON WHITE	SHS		
	7 VERMONT 17 7	1	24	24	4.00																											MI-4	SHS		
		1	24	24	4.00																											MI-5			E-136B
		1	24	24	4.00																											MI-4	SHS		
	← → →	1	21	15	2.19																											M6-1L BLACK ON WHITE	SHS		
		1	21	15	2.19																											M6-1R GREEN ON WHITE	SHS		
		1	21	15	2.19																											M6-1R BLACK ON WHITE	SHS		
STA. d 180+63 LT NEW HAVEN	WEST	1	24	12	2.00						1					X		X														M3-4 GREEN ON WHITE	SHS		
	VERMONT 17	1	24	24	4.00																											MI-5			E-136B
	TSSS 1 TOTAL						9									135																				
	TSSS 2 TOTAL						8									105																				
	TSSS 3 TOTAL						9									150																				
	TSSS 4 TOTAL						7									90																				
	TSSS 5 TOTAL						13									120																				
	TSSS 6 TOTAL				39.34		1									135																				
	TSSS 7 TOTAL				40.63											45	45																		
	TSSS 8 TOTAL				29.03											120																				
	TSSS 9 TOTAL				39.50											135																				
	TSSS 10 TOTAL				29.17		4									90																				
	TSSS 11 TOTAL				41.92											90																				
	TSSS 12 TOTAL				32.76										8	90																				
	TSSS 13 TOTAL				12.09		2								8	30																				
	TSSS 14 TOTAL				15.18										32	30																				
	TSSS 15 TOTAL				20.60										16	60																				
	TSSS 16 TOTAL				26.84		1								8	60																				
	TSSS 17 TOTAL				22.09		2								8	60																				
	TSSS 18 TOTAL				17.93		1								16	60																				
	TSSS 19 TOTAL				15.84										16	45																				
	TSSS 20 TOTAL				39.28		1								8	120																				
	TSSS 21 TOTAL				41.67										8	30								2	274											
	TSSS 22 TOTAL				30.57											15								2	274											
												LF	LF	LF	LF	LF	LF		EA.	LB	LB	LB		LB	LB	LB	LB									
															128	1815	45							548												
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."	SUBTOTAL		494.44																																	
	ROUNDING		0.56																																	
	TOTALS		SF 495		SF	EA. 58	SF					LF			LF 2003					LB			EA. 4		LB 548				EA.	EA.	LB					

TRAFFIC SIGN SUMMARY SHEET 22

PROJECT NAME: ADDISON - NEW HAVEN
PROJECT NUMBER: STP 9632(1)

FILE NAME: p95B076.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
PLOT FILE: p95B076_181.i

PLOT DATE: 3/13/2012
DRAWN BY: SJL
CHECKED BY: EPD
SHEET 181 OF 186