

BOTTOM OF PILE CAP = 575.00

ESTIMATED PILE TIP

		STATE OF VERMONT AGENCY OF TRANSPORTATION MATERIALS & RESEARCH SECTION SUBSURFACE INFORMATION		BORING NUMBER: B-106 SHEET 1 of 1 DATE STARTED: 2/09/09 DATE COMPLETED: 2/11/09					
PROJECT NAME: CHESTER SITE NAME: VT-103 STATION: 13+81 OFFSET: 29.00 VTSPG: N 276215.83 ft E 1617021.04 ft				PROJECT NUMBER: BRF 025-1(37)SC SITE NUMBER: BR-9 GROUND ELEVATION: 584.78 ft GROUNDWATER DEPTH: 10.8 ft 2/10/09 PROJECT PIN NUMBER: 95B168					
BORING CREW CREW CHIEF: GARROW DRILLER: GARROW LOGGER: MAHMUTOVIC				BORING RIG: LARGE SKID RIG w/AUTO HAMMER BORING TYPE: WASH BORE SAMPLE TYPE: SPLIT BARREL CHECKED BY: NSM					
DEPTH (ft)	SYMBOL	CLASSIFICATION OF MATERIALS (Description)	BLOWS PER FOOT	M.C. (%)	GRAVEL (%)	SAND (%)	FINES (%)	LL (%)	PI (%)
			RUN	REC (%)	ROD (%)	Dip (deg)	Drill Rate (min/ft)		
10		A-2-4, SiSa, brn, Moist, Rec. = 1.1 ft, Very strong petroleum odor.	49	9.0	17.6	58.9	23.5		
		A-1-a, SaGr, brn, Moist, Rec. = 1.1 ft, Very strong petroleum odor.	14	6.3	52.1	41.4	6.5		
		A-2-4, GrSa, brn, Moist, Rec. = 0.9 ft	13	7.5	30.3	56.0	13.7		
		A-1-b, GrSa, brn, Moist, Rec. = 1.0 ft	18	9.8	37.7	45.5	16.8		
		A-1-b, GrSa, brn, MTW, Rec. = 0.8 ft	27	7.8	44.7	44.9	10.4		
		A-1-b, GrSa, brn, MTW, Rec. = 0.5 ft	R	10.9	35.5	47.0	17.5		
		BXDC, Boulder, 10.6 ft - 12.0 ft	23	17.9	21.8	63.5	14.7		
		A-2-4, GrSa, gry, Wet, Rec. = 0.8 ft	9	18.3	32.2	59.4	8.4		
		A-3, GrSa, gry, Wet, Rec. = 0.3 ft, There was one stone in sample.	25						
		Field Note: No Recovery, Stone in sampler.	17	16.1	20.3	48.8	30.9		
20		A-2-4, GrSiSa, gry, Wet, Rec. = 0.9 ft	36	18.8	10.0	52.8	37.2		
		A-4, SiSa, gry, Wet, Rec. = 1.5 ft							
		A-4, SaSi, gry, Wet, Rec. = 1.6 ft	78	20.2	10.5	29.5	60.0		
30		A-6, SiCl, gry, Wet, Rec. = 0.7 ft	6	35.1	0.0	2.3	97.7	39	15
		BXDC, Boulder, 32.3 ft - 34.5 ft							
		A-2-4, SiSa, gry, Wet, Rec. = 0.4 ft	R	12.1	19.6	50.1	30.3		
40		BXMDC, Boulder, 38.8 ft - 41.8 ft							
		A-2-4, GrSiSa, gry, Wet, Rec. = 0.5 ft	R	11.0	26.6	43.8	29.6		
50		A-2-4, SiSa, gry, Wet, Rec. = 0.7 ft	R	20.1	0.0	69.3	30.7		
		A-2-4, SiSa, gry, Wet, Rec. = 0.7 ft	R	21.2	0.8	74.2	25.0		
60		Top of Bedrock @ 58.0 ft							
		Black and gray, Biotite Gneiss, Competent, Very hard, Unweathered, BXMDC, 58.0 ft - 63.0 ft, Rec. = 4.9 ft	1	98	52	20	6		
70		Black and gray, Biotite Gneiss, Competent, Very hard, Unweathered, BXMDC, 63.0 ft - 68.0 ft, Rec. = 4.2 ft	2	84	48	20	10		
							10		
70		Hole stopped @ 68.0 ft					9		
							8		

LOC OF BORING CHESTER BRF 025-1(37)SC.dgn VT AGT.BDT 5/13/09

PROJECT NAME: CHESTER
 PROJECT NUMBER: BRF 025-1(37)

FILE NAME: s95b168bor.dgn
 PROJECT LEADER: C.P.WILLIAMS
 DESIGNED BY: H.J.SALLS
 BRIDGE 9 BORING LOG - SHEET 3

PLOT DATE: 20-SEP-2010
 DRAWN BY: D.D.BEARD
 CHECKED BY: R.S.YOUNG
 SHEET 77 OF 124