

QUANTITY SHEET 4



SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
					ROADWAY	TRAINING	EROSION CONTROL	BRIDGE	FULL E&C ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							90	280		370		CM	UNCLASSIFIED CHANNEL EXCAVATION	203.27				
							185	65		250		CM	STRUCTURE EXCAVATION	204.25				
							100	100		200		CM	GRANULAR BACKFILL FOR STRUCTURES	204.30				
				103			37	37		177		CM	CONCRETE, HIGH PERFORMANCE CLASS A	501.33				
					27	27	31	31		116		CM	CONCRETE, HIGH PERFORMANCE CLASS B	501.34				
							1			1		LS	FURNISHING EQUIPMENT FOR DRIVING PILING	504.10				
							100	70		170		M	STEEL PILING FOR INTEGRAL ABUTMENTS, HP 360 X 132	505.28				
							1	1		2		EACH	DYNAMIC PILE LOADING TEST	505.45				
				64890						64890		KG	STRUCTURAL STEEL, PLATE GIRDER	506.55	REV. 2			
				17609	2782	2782	9664	9706		42543		KG	EPOXY COATED REINFORCING STEEL	507.17	REV. 1			
				1						1		LS	SHEAR CONNECTORS (1700 - 22 X 180)	508.15				
				83						83		L	WATER REPELLENT, SILANE	514.10				
							12	11		23		M	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10				
				414						414		SM	SHEET MEMBRANE WATERPROOFING, TORCH APPLIED	519.20				
					12	12				24		M	JOINT SEALER, HOT POURED	524.11				
				70						70		M	BRIDGE RAILING, GALVANIZED NETC 2 RAIL	525.33				
				400						400		SM	REMOVAL OF BRIDGE PAVEMENT	529.10				
				1						1		EACH	PARTIAL REMOVAL OF STRUCTURE	529.20				
							5	5		10		EACH	BEARING DEVICE ASSEMBLY, INTEGRAL ABUTMENT	531.14				
									50	50		CM	STONE FILL, TYPE I	613.10				
									280	280		CM	STONE FILL, TYPE III	613.12				
									580	580		SM	GEOTEXTILE UNDER STONE FILL	649.31				

REVISIONS	
DATE	REVISION
4/3/2008	1. REMOVE 506.60 "STRUCTURAL STEEL"
4/3/2008	2. INCREASE 506.55 "STRUCTURAL STEEL , PLATE GIRDER".

PROJECT NAME: **RUTLAND TOWN**
PROJECT NUMBER: **BRF 019-3(48)**
FILE NAME: s95b172qty.dgn VAOT_quant.xls PLOT DATE: 04/03/2008
PROJECT MANAGER: R. WHITCOMB DRAWN BY: T. LACKEY
DESIGNED BY: T. LACKEY CHECKED BY: R. WHITCOMB
QUANTITY SHEET #4 SHEET 10 OF 75