STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	FOUND-ATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																								
2+279.0 RT.	NORTH	1	600	300	0.18						1		X			X		X																M3-1		E-136A
2+279.0 RT.	7	1	600	600	0.36																													M1-4		E-136A
2+386.0 RT.	FARM SIGN	1					1		2																									REMOVE & ERECT OUTSIDE OF R.O.W.		
TOTALS					m2 0.54	m2	EA. 1	m2				m 6			m 6				EA	kg				kg				EA.				EA.	EA.	kg		

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY, TRAFFIC & SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: RUTLAND TOWN
PROJECT NUMBER: BRF 019-3(48)

FILE NAME: sb172tc6.i
PROJECT LEADER: R. WHITCOMB
DESIGNED BY: L. BULLOCK
/95b172/str/sb172tc.dgn

PLOT DATE: 11-MAR-2008
DRAWN BY: L. BULLOCK
CHECKED BY: T. LACKEY
SHEET 41 OF 75