

# QUANTITY SHEET



SUMMARY OF ESTIMATED QUANTITIES														TOTALS			DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES	
PART. UTILITY	NONPART. UTILITY	TRACK SUBGRADE	RT 9 RR BRG	RT 9 SO ABUT	RT 9 NO ABUT	SGT BK BRIDGE	SGT BK SO ABUT	SGT BK NO ABUT	SGT BK CHANNEL	ROADWAY	EROSION	TEMP EROSION	E & C ITEMS	ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS		QUANTITIES	ITEMS
										206					206		M	750mm CAAP 1.52 mm (75mm x 25mm)	60L0305		
										206					206		M	750mm PCCSP 2.01mm (68mm x 12mm)	60L0436		
										34					34		M	900mm CAAP 1.52 mm (75mm x 25mm)	60L0310		
										34					34		M	900mm PCCSP 2.01mm (68mm x 12mm)	60L0446		
										61					61		M	450mm RCP Class III	60L0815		
										61					61		M	450mm CPEP (SL)	60L2615		
										6					6		M	600mm RCP Class III	60L0825		
										6					6		M	600mm CPEP (SL)	60L2620		
										128					128		M	750mm RCP Class III	60L0835		
										128					128		M	750mm CPEP (SL)	60L2625		
										86					86		M	900mm RCP Class III	60L0845		
										86					86		M	900mm CPEP (SL)	60L2630		
										1					1		Each	750mm RCPEP Class III	60L6835		
										1					1		Each	750mm CPEPES	60L7025		
										1					1		Each	900mm RCPEP Class III	60L6845		
										1					1		Each	900mm CPEPES	60L7030		
																		END PIPE OPTIONS			
										14					14		Each	Precast Reinf. Conc. Catch Basin w/ CIG	604.20		
										2					2		Each	Precast Reinf. Conc. Catch Basin w/ CIG (1.5m)	604.20		
										4					4		Each	Precast Reinf. Conc. Catch Basin w/ CIG (1.8m)	604.20		
										1					1		Each	Precast Reinf. Conc. Catch Basin w/ CIG (2.1m)	604.20		
										1					1		Each	Precast Reinf. Conc. C.B. w/CIG 2.7m x 2.4m	604.20		
										1					1		Each	Precast Reinf. Conc. C.B. w/ CIG (1.5m x 1.5m)	604.20		
										5					5		Each	Precast Reinf. Conc. Manhole w/ CIG (1.5m)	604.21		
										1					1		Each	Precast Reinf. Conc. Manhole w/ CIG (1.8m)	604.21		
										3					3		Each	*Changing Elev. of D.I., C. B. or M.H.*	604.40		
										311					311		M	150mm Underdrain	605.10		
										7					7		M	150mm Underdrain Carrier Pipe	605.20		
										9					9		Each	Underdrain Flushing Basins	605.95		
										1					1		Hour	*Bulldozer Rental, Type I*	608.10		
										1					1		Hour	Power Grader Rental	608.15		
										1					1		Hour	*All Purpose Excavator Rental, Type I*	608.25		
										1					1		Hour	Power Broom Rental	608.30		

PROJECT NAME :	PROJECT NO. :
BRATTLEBORO	NH 010-2(2)
DESIGN FILE NAME: sf270qty.dgn	PLOT DATE: 10-01-2002
IPARM FILE NAME:	SURVEY DATE:
SURVEYED BY:	DRAWN BY: LB/LD/TT
SQUAD LEADER: JHR	SHEET: 15 OF 145