

RECORD OF BOREHOLE B-1											
DEPTH SCALE METERS		DEPTH SCALE FEET		BORING METHOD		SOIL PROFILE		SAMPLES		SAMPLE DESCRIPTIONS AND BORING NOTES	
0		0		WASH AND DRILL		0.0-4.0 Loose, light brown, m-f SAND.		S1 D.O. 1-1-6-8 7 8/24		Loose, light brown, m-f SAND, little silt.	
1		1				4.0-19.0 Loose to compact, grayish brown, m-f SAND, trace silt.		S2 D.O. 7-6-4-5 10 14/24		Grayish brown, loose, m-f SAND some silt.	
2		2				19.0-23.0 Compact, light brown, m-f SAND, trace gravel.		S5 D.O. 13-11-10-9 21 6/24		Compact, light brown, m-f SAND, trace gravel.	
3		3				23.0-38.0 Compact, light brown, SAND, some silt, trace gravel.		S6 D.O. 11-8-9-9 17 8/24		Compact light brown m-f SAND trace gravel.	
4		4				38.0 BEDROCK				Rollercored from 38'-39' bgs	

RECORD OF ROCK COREHOLE B-1											
DEPTH SCALE METERS		DEPTH SCALE FEET		BORING METHOD		CORE DESCRIPTION		RUN INFORMATION		DISCONTINUITIES	
12		12		NX Coring		38'-54' Fresh to slightly weathered, very closely jointed, gray, very fine grained PHYLLITE with several near vertical joints.		Run No. 1		0% 2	
13		13						Run No. 2		0% 2	
14		14						Run No. 3		0% 1	
15		15						Run No. 4		0% 1	
16		16						Run No. 5		0% 1	
17		17						Run No. 6		0% 1	
18		18						Run No. 7		0% 1	
19		19						Run No. 8		0% 1	
20		20						Run No. 9		0% 1	
21		21						Run No. 10		0% 1	
22		22						Run No. 11		0% 1	
23		23						Run No. 12		0% 1	
24		24						Run No. 13		0% 1	
25		25						Run No. 14		0% 1	
26		26						Run No. 15		0% 1	
27		27						Run No. 16		0% 1	
28		28						Run No. 17		0% 1	
29		29						Run No. 18		0% 1	
30		30						Run No. 19		0% 1	
31		31						Run No. 20		0% 1	
32		32						Run No. 21		0% 1	
33		33						Run No. 22		0% 1	
34		34						Run No. 23		0% 1	
35		35						Run No. 24		0% 1	
36		36						Run No. 25		0% 1	
37		37						Run No. 26		0% 1	
38		38						Run No. 27		0% 1	
39		39						Run No. 28		0% 1	
40		40						Run No. 29		0% 1	
41		41						Run No. 30		0% 1	
42		42						Run No. 31		0% 1	
43		43						Run No. 32		0% 1	
44		44						Run No. 33		0% 1	
45		45						Run No. 34		0% 1	
46		46						Run No. 35		0% 1	
47		47						Run No. 36		0% 1	
48		48						Run No. 37		0% 1	
49		49						Run No. 38		0% 1	
50		50						Run No. 39		0% 1	
51		51						Run No. 40		0% 1	
52		52						Run No. 41		0% 1	
53		53						Run No. 42		0% 1	
54		54						Run No. 43		0% 1	
55		55						Run No. 44		0% 1	
56		56						Run No. 45		0% 1	
57		57						Run No. 46		0% 1	
58		58						Run No. 47		0% 1	
59		59						Run No. 48		0% 1	

RECORD OF BOREHOLE B-2											
DEPTH SCALE METERS		DEPTH SCALE FEET		BORING METHOD		SOIL PROFILE		SAMPLES		SAMPLE DESCRIPTIONS AND BORING NOTES	
0		0		WASH AND DRIVE		0.0-11.0 Very loose to compact, light brown, m-f SAND, trace silt.		S1 D.O. 4-5-5-8 10 8/24		Dark brown compact SAND, little silt and organics.	
1		1				11.0-25.0 Compact, grayish brown, m-f SAND, trace silt.		S3 D.O. 2-2-3-3 5 8/24		Light brown, very loose M-F SAND trace silt.	
2		2				25.0-25.75 BEDROCK		S6 D.O. 26-25/3-50/0 150 8/24		4" dense grayish brown C-M-F SAND trace rock chips.	
3		3				TOP OF FOOTING				Rollercored 6" to 25" 3"	
4		4								Coring from 25'3"-50' bgs	

RECORD OF ROCK COREHOLE B-2											
DEPTH SCALE METERS		DEPTH SCALE FEET		BORING METHOD		CORE DESCRIPTION		RUN INFORMATION		DISCONTINUITIES	
25		25		NX Coring		25.25'-50' Fresh to slightly weathered, very closely jointed, gray, very fine grained PHYLLITE.		Run No. 1		1 25.4 7 J/S	
26		26						Run No. 2		2 26.3 35 M/FST	
27		27						Run No. 3		3 26.5 35 J/ST	
28		28						Run No. 4		4 26.9 78 M/FST	
29		29						Run No. 5		5 27.6 88 M/FST	
30		30						Run No. 6		6 28.6 75 J/R	
31		31						Run No. 7		7 28.4 35 J/R	
32		32						Run No. 8		8 29.9 90 J/R	
33		33						Run No. 9		9 31.3 68 M/FST	
34		34						Run No. 10		10 31.6 75 J/ST	
35		35						Run No. 11		11 32.2 36 J/R	
36		36						Run No. 12		12 32.7 85 J/R	
37		37						Run No. 13		13 33.5 80 M/FST	
38		38						Run No. 14		14 33.7 18 J/R	
39		39						Run No. 15		15 34.2 0 M/R	
40		40						Run No. 16		16 35.0 90 M/R	
41		41						Run No. 17		17 36.6 75 J/R	
42		42						Run No. 18		18 37.2 74 J/R	
43		43						Run No. 19		19 38.8 0 M/R	
44		44						Run No. 20		20 40.0 36 M/R	
45		45						Run No. 21		21 41.9 58 M/FST	
46		46						Run No. 22		22 43.0 22 J/S	
47		47						Run No. 23		23 43.7 85 M/FST	
48		48						Run No. 24		24 44.8 65 M/R	
49		49						Run No. 25		25 47.6 45 J/ST	
50		50						Run No. 26		26 48.1 30 J/S	
51		51						Run No. 27		27 48.3 30 M/R	
52		52						Run No. 28		28 48.4 83 M/R	
53		53						Run No. 29		29 49.6 85 J/R	
54		54						Run No. 30		30 49.6 85 J/R	

RECORD OF BOREHOLE B-3											
DEPTH SCALE METERS		DEPTH SCALE FEET		BORING METHOD		SOIL PROFILE		SAMPLES		SAMPLE DESCRIPTIONS AND BORING NOTES	
0		0		WASH AND DRIVE		0.0-5.0 Compact, light brown, F-SAND, some silt.		S1 D.O. 6-4-5-4 9 20/24		Compact, yellowish brown, FINE SAND, some silt.	
1		1				5.0-18.0 Compact, grayish brown, m-f SAND.		S2 D.O. 7-5-7-6 12 18/24		4" casing advanced to 4' bgs and washed.	
2		2				18.0 BEDROCK		S3 D.O. 7-8-7-8 15 12/24		6" Light brown compact FINE SAND, some silt.	
3		3						S4 D.O. 11-13-14-14 27 12/24		3" Black compact FINE SAND	
4		4								4" casing advanced to 9' bgs and washed.	
5		5								Grayish brown compact M-F SAND	
6		6								4" casing advanced to 14' bgs and washed.	
7		7								Grayish brown compact M-F SAND	
8		8								4" casing advanced to 18' bgs and washed.	
9		9								Refusal of 18' bgs	
10		10								4" casing advanced to 18' bgs and washed.	
11		11								Rollercored 6" to 18'6" bgs	
12		12								Coring from 18'6"-51' bgs	

RECORD OF ROCK COREHOLE B-3											
DEPTH SCALE METERS		DEPTH SCALE FEET		BORING METHOD		CORE DESCRIPTION		RUN INFORMATION		DISCONTINUITIES	
18.5		18.5		NX Coring		18.5'-51' Fresh to slightly weathered, very closely jointed, gray, very fine grained PHYLLITE with few vertical joints.		Run No. 1		2 18.8 52 M/R	
19		19						Run No. 2		3 19.3 51 M/R	
20		20						Run No. 3		4 19.8 28 M/R	
21		21						Run No. 4		5 20.1 40 M/R	
22		22						Run No. 5		6 20.4 26 M/R	
23		23						Run No. 6		7 20.8 88 J/R	
24		24						Run No. 7		8 21.3 55 M/R	
25		25						Run No. 8		9 21.5 60 M/R	
26		26						Run No. 9		10 22.3 20 M/R	
27		27						Run No. 10		11 23.5 80 M/R	
28		28						Run No. 11		12 24.0 29 M/SM	
29		29						Run No. 12		13 24.4 24 J/R	
30		30						Run No. 13		14 24.6 24 J/R	
31		31						Run No. 14		15 25.3 90 M/R	
32		32						Run No. 15		16 25.4 34 M/SM	
33		33						Run No. 16		17 27.2 20 J/ST	
34		34						Run No. 17		18 28.1 21 M/SM	
35		35						Run No. 18		19 28.5 0 J/R	
36		36						Run No. 19		20 28.8 10 J/R	
37		37						Run No. 20		21 29.4 15 M/SM	
38		38						Run No. 21		22 29.7 0 M/R	
39		39						Run No. 22		23 32.2 37 J/R	
40		40						Run No. 23		24 32.4 36 M/R	
41		41						Run No. 24		25 32.8 36 M/SM	
42		42						Run No. 25		26 33.0 90 J/UE	
43		43						Run No. 26		27 33.1 42 J/UE	
44		44						Run No. 27		28 33.2 43 M/FST	
45		45						Run No. 28		29 35.0 70 M/R	
46		46						Run No. 29		30 35.7 65 M/R	
47		47						Run No. 30		31 35.8 12 M/FST	
48		48						Run No. 31		32 36.4 27 M/R	
49		49						Run No. 32		33 37.4 30 M/R	
50		50						Run No.			