

RECORD OF BOREHOLE B-4										
DEPTH SCALE METERS		DEPTH SCALE FEET		BORING METHOD		SOIL PROFILE		SAMPLES		SAMPLE DESCRIPTIONS AND BORING NOTES
DEPTH SCALE METERS	DEPTH SCALE FEET	USCS	GRAPHIC LOG	ELEVATION	NUMBER	TYPE	BLOWS / 6 INCHES	N	REC. ATT.	
0	0			84.8	S1	D.O.	1-2-3-1	5	5/24	Loose, light brown, M-F SAND some roots
1	1			84.2						4" casing advanced to 5' bgs and washed
2	2			83.3	S2	D.O.	7-7-7-7	14	18/24	Compact, grayish brown FINE SAND, trace gravel and silt
3	3			82.6						4" casing advanced to 9' bgs and washed Gravel observed in wash water
4	4			82.0	S3	D.O.	5-6-5-7	11	12/24	Compact, grayish brown M-F SAND, trace silt
5	5			81.4						4" casing advanced to 14' bgs and washed Bottom appears to be hard.
6	6			80.5						14.0 BEDROCK Possible bedrock at 14' bgs Attempted sampling but had refusal at 14' bgs Coring from 14'-24' bgs

RECORD OF ROCK COREHOLE B-4										
DEPTH SCALE METERS		DEPTH SCALE FEET		BORING METHOD		CORE DESCRIPTION		RUN INFORMATION		DISCONTINUITIES
DEPTH SCALE METERS	DEPTH SCALE FEET	USCS	GRAPHIC LOG	ELEVATION	RUN	PERFORATION MIN. / FT.	RUN TIME START / STOP	WATER USAGE	% FLUSH RET. FRACTURE INDEX	
14	14			80.5	Run No. 1					14'-24" Fresh to slightly weathered, close to moderately closely jointed, gray, very fine grained PHYLITE.
19	19			79.0	Run No. 2					
24	24			77.5	Run No. 3					

DRILL RIG: MOBILE B-47
 DRILLING CONTRACTOR: Con-Tec Inc.
 DRILLER: B. BOURASSA

TOTAL LENGTH CORED: 10'
 BITS USED: 1

LOGGED: MRT
 CHECKED: TKA
 DATE:

RECORD OF BOREHOLE B-4A										
DEPTH SCALE METERS		DEPTH SCALE FEET		BORING METHOD		SOIL PROFILE		SAMPLES		SAMPLE DESCRIPTIONS AND BORING NOTES
DEPTH SCALE METERS	DEPTH SCALE FEET	USCS	GRAPHIC LOG	ELEVATION	NUMBER	TYPE	BLOWS / 6 INCHES	N	REC. ATT.	
0	0									Borehole advanced to 14' bgs without split spoon sampling. See borehole log B-4 for coring from 14'-34' bgs
10	10									TOP OF FOOTING

RECORD OF ROCK COREHOLE B-4A										
DEPTH SCALE METERS		DEPTH SCALE FEET		BORING METHOD		CORE DESCRIPTION		RUN INFORMATION		DISCONTINUITIES
DEPTH SCALE METERS	DEPTH SCALE FEET	USCS	GRAPHIC LOG	ELEVATION	RUN	PERFORATION MIN. / FT.	RUN TIME START / STOP	WATER USAGE	% FLUSH RET. FRACTURE INDEX	
14	14			80.5	Run No. 1					14'-34" Fresh to slightly weathered, close to very closely foliated, close to moderately closely jointed, block to gray (with vitreous luster), very fine grained PHYLITE, with several near vertical joints and slight oxidation on some joint surfaces.
19	19			79.0	Run No. 2					
24	24			77.5	Run No. 3					
29	29			75.9	Run No. 4					
34	34			74.4	Run No. 5					

DRILL RIG: MOBILE B-47
 DRILLING CONTRACTOR: Con-Tec Inc.
 DRILLER: B. BOURASSA

TOTAL LENGTH CORED: 20'
 BITS USED: 1

LOGGED: MZ
 CHECKED: TKA
 DATE:

RECORD OF BOREHOLE B-5										
DEPTH SCALE METERS		DEPTH SCALE FEET		BORING METHOD		SOIL PROFILE		SAMPLES		SAMPLE DESCRIPTIONS AND BORING NOTES
DEPTH SCALE METERS	DEPTH SCALE FEET	USCS	GRAPHIC LOG	ELEVATION	NUMBER	TYPE	BLOWS / 6 INCHES	N	REC. ATT.	
0	0			86.7	S1	D.O.	1-1-2-3	3	8/24	4" Black topsoil, followed by very loose, light brown SAND trace silt
1	1			86.1						4" casing advanced to 4' bgs and washed
2	2			85.5	S2	D.O.	5-3-2-2	5	6/24	Loose, light brown SAND, some silt trace organics
3	3			84.9						4" casing advanced to 9' bgs and washed
4	4			84.0						Loose, light brown SAND, some silt trace organics
5	5			83.7						Refusal at 9'-4" Refused to 10' bgs Coring from 10'-30' bgs (Core barrel bent at 10' bgs and coring continued with new barrel.)

RECORD OF ROCK COREHOLE B-5										
DEPTH SCALE METERS		DEPTH SCALE FEET		BORING METHOD		CORE DESCRIPTION		RUN INFORMATION		DISCONTINUITIES
DEPTH SCALE METERS	DEPTH SCALE FEET	USCS	GRAPHIC LOG	ELEVATION	RUN	PERFORATION MIN. / FT.	RUN TIME START / STOP	WATER USAGE	% FLUSH RET. FRACTURE INDEX	
10	10			83.7	Run No. 1					10'-30" Fresh to slightly weathered, close to moderately closely jointed gray, very fine grained PHYLITE.
15	15			82.1	Run No. 2					
20	20			80.6	Run No. 3					
25	25			79.1	Run No. 4					
30	30			77.6	Run No. 5					

DRILL RIG: MOBILE B-47
 DRILLING CONTRACTOR: Con-Tec Inc.
 DRILLER: B. BOURASSA

TOTAL LENGTH CORED: 20'
 BITS USED: 1

LOGGED: MRT
 CHECKED: TKA
 DATE: