

RECORD OF PROBEHOLE P-1											
			PROJECT NAME: RT 9 ROAD IMPROVEMENT SITE NAME: BRATTLEBORO VT STATION: 50+252.70 GROUND EL.: 83.254			PROJECT NUMBER: 993-6874 SITE NO.: OFFSET: LT 14.25 G.W. DEPTH:			BORING NO.: P-1 SHEET 1 OF 1 DATE STARTED: 10/01/11-8-99 DATE COMPLETED: 10/01/11-8-99		
			BORING CREW: CREW CHIEF: DRILLER: B. BOURASSA LOGGER: MRT CHECKED: TKA ADDITIONAL CREW:			BORING RIG: MOBILE B-47 BORING TYPE: SAMPLE TYPE: WEIGHT OF HAMMER: N/A DROP: N/A			SAMPLE DESCRIPTIONS AND BORING NOTES		
DEPTH SCALE METERS	DEPTH SCALE FEET	BORING METHOD	SOIL PROFILE			SAMPLES					
			USCS	GRAPHIC LOG ELEVATION	NUMBER	TYPE	BLOWS / 6 INCHES	N			
0	0	4" AUGER	0.0-6.0	Light brown, m-SAND.	83.3						
1	5		6.0-10.0	Grayish brown, m-SAND, wet.	81.4						
2	10				80.2						
			DRILL RIG: MOBILE B-47 DRILLING CONTRACTOR: Con-Tec INC. DRILLER: B. BOURASSA			LOGGED: MRT CHECKED: TKA DATE:			SHEET 1 OF 1		

RECORD OF PROBEHOLE P-3											
			PROJECT NAME: RT 9 ROAD IMPROVEMENT SITE NAME: BRATTLEBORO VT STATION: 50+263.99 GROUND EL.: 81.41			PROJECT NUMBER: 993-6874 SITE NO.: OFFSET: RT 14.49 G.W. DEPTH: 1'			BORING NO.: P-3 SHEET 1 OF 1 DATE STARTED: 10/01/11-8-99 DATE COMPLETED: 10/06/11-8-99		
			BORING CREW: CREW CHIEF: DRILLER: B. BOURASSA LOGGER: MRT CHECKED: TKA ADDITIONAL CREW:			BORING RIG: MOBILE B-47 BORING TYPE: SAMPLE TYPE: WEIGHT OF HAMMER: N/A DROP: N/A			SAMPLE DESCRIPTIONS AND BORING NOTES		
DEPTH SCALE METERS	DEPTH SCALE FEET	BORING METHOD	SOIL PROFILE			SAMPLES					
			USCS	GRAPHIC LOG ELEVATION	NUMBER	TYPE	BLOWS / 6 INCHES	N			
0	0	4" AUGER	0.0-4.5	Dark brown, c-m SAND.	81.1						
1	5		4.5	BEDROCK	79.8						Refusal at 4'6"
			DRILL RIG: MOBILE B-47 DRILLING CONTRACTOR: Con-Tec INC. DRILLER: B. BOURASSA			LOGGED: MRT CHECKED: TKA DATE:			SHEET 1 OF 1		

RECORD OF PROBEHOLE P-2											
			PROJECT NAME: RT 9 ROAD IMPROVEMENT SITE NAME: BRATTLEBORO VT STATION: 50+261.17 GROUND EL.: 82.726			PROJECT NUMBER: 993-6874 SITE NO.: OFFSET: LT 5.89 G.W. DEPTH:			BORING NO.: P-2 SHEET 1 OF 1 DATE STARTED: 10/01/11-8-99 DATE COMPLETED: 10/25/11-8-99		
			BORING CREW: CREW CHIEF: DRILLER: B. BOURASSA LOGGER: MRT CHECKED: TKA ADDITIONAL CREW:			BORING RIG: MOBILE B-47 BORING TYPE: SAMPLE TYPE: WEIGHT OF HAMMER: N/A DROP: N/A			SAMPLE DESCRIPTIONS AND BORING NOTES		
DEPTH SCALE METERS	DEPTH SCALE FEET	BORING METHOD	SOIL PROFILE			SAMPLES					
			USCS	GRAPHIC LOG ELEVATION	NUMBER	TYPE	BLOWS / 6 INCHES	N			
0	0	4" AUGER	0.0-10.0	Grayish brown, m-SAND, wet, trace silt.	82.7						
1	5										No soil cuttings observed down to 5' bgs.
2	10				79.7						Water appears to be approximately 5'-6" bgs. Hole cased in therefore exact water level was not measured.
			DRILL RIG: MOBILE B-47 DRILLING CONTRACTOR: Con-Tec INC. DRILLER: B. BOURASSA			LOGGED: MRT CHECKED: TKA DATE:			SHEET 1 OF 1		

RECORD OF PROBEHOLE P-4											
			PROJECT NAME: RT 9 ROAD IMPROVEMENT SITE NAME: BRATTLEBORO VT STATION: 50+265.75 GROUND EL.: 80.675			PROJECT NUMBER: 993-6874 SITE NO.: OFFSET: RT 21.97 G.W. DEPTH: 2'5"			BORING NO.: P-4 SHEET 1 OF 1 DATE STARTED: 10/13/11-10-99 DATE COMPLETED: 10/25/11-10-99		
			BORING CREW: CREW CHIEF: DRILLER: B. BOURASSA LOGGER: MRT CHECKED: TKA ADDITIONAL CREW:			BORING RIG: MOBILE B-47 BORING TYPE: SAMPLE TYPE: WEIGHT OF HAMMER: N/A DROP: N/A			SAMPLE DESCRIPTIONS AND BORING NOTES		
DEPTH SCALE METERS	DEPTH SCALE FEET	BORING METHOD	SOIL PROFILE			SAMPLES					
			USCS	GRAPHIC LOG ELEVATION	NUMBER	TYPE	BLOWS / 6 INCHES	N			
0	0	4" AUGER	0.0-5.8	Dark brown, c-m SAND, some gravel.	80.7						Water at 2'5"
1	5		5.8	BEDROCK	78.9						Refusal at 5'10"
			DRILL RIG: MOBILE B-47 DRILLING CONTRACTOR: Con-Tec INC. DRILLER: B. BOURASSA			LOGGED: MRT CHECKED: TKA DATE:			SHEET 1 OF 1		