GENERAL NOTES:

1. ALL MATERIALS AND CONSTRUCTION SHALL CONFORM TO STATE OF VERMONT AGENCY OF TRANSPORTATION STANDARD SPECIFICATIONS FOR CONSTRUCTION DATED 2001, AND ITS LATEST REVISIONS; AREMA'S "MANUAL FOR RAILWAY ENGINEERING", LATEST EDITION , AND ITS LATEST REVISIONS.

2. THESE SHOP DRAWINGS WERE PREPARED IN ACCORDANCE WITH THE CONTRACT PLANS AND SPECIFICATIONS. THE D.S. BROWN COMPANY DOES NOT ACCEPT LIABILITY FOR THE DESIGN OF THE PRODUCTS DETAILED IN THESE SHOP DRAWINGS.

3. THE D.S. BROWN COMPANY IS TO ONLY SUPPLY THE PARTS SHOWN ON THESE DRAWINGS.

4. MATCH MARKS SHALL BE PLACED AT CENTER LINE ON PLATE EDGES TO INSURE CORRECT ASSEMBLY AT THE JOB SITE. THE MARKS SHALL BE MADE IN INDELIBLE INK AND SHALL BE BE VISIBLE AFTER BEARING INSTALLATION.

⚠ 5. BEARING SHALL BE GALVANIZED IN ACCORDANCE WITH VADOT 2001 STANDARD SPECIFICATIONS.

PROJECT NH010-2(2)
9/30/03
☒
BY J H Reed 6/18/03

REV.	DESCRIPTION	DATE	DET.	CKD.
⚠	ADDED GENERAL NOTE 5	4/23/03	BC	EK

D.S. BROWN

300 E. CHERRY STREET
NORTH BALTIMORE, OHIO 45872
419.257.3561
FAX: 419.257.0332

4201 NOREX DRIVE
CHASKA, MINNESOTA 55318
952.368.3000
FAX: 952.448.7000

DSBROWN.COM

LOCATION — VT ROUTE 9
BRIDGE — 62.56
PROJECT — NH 010-2(2)
—
—
DESIGNER — CONSULTING ENGINEERS
CUSTOMER — JA MCDONALD

ITEM	QUANTITY
—	—
—	—
—	—
—	—
—	—
—	—
—	—
—	—
—	—

DESCRIPTION	SCALE	DRAWN BY	CHECKED BY	DATE	
GENERAL NOTES WINDHAM COUNTY, VERMONT	N.T.S.	B.COPPUS	E.KELLEY	3/20/03	—
	PROJECT NUMBER: 7657	PRODUCT CODE: 1121		RELEASE: 1	SHEET: GN

183 BB