

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
					Roadway	TRAINING	Erosion Control	Bridge	Full C&E	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
					4					4		EACH	GUARDRAIL APPROACH SECTION, GALVANIZED NETC 2 RAIL	621.72				
					161					161		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
					2250					2250		HR	FLAGGERS	630.15				
									1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
									1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
									1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
									3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
						520				520		HR	EMPLOYEE TRAINEESHIP	634.10				
					1					1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
					1					1		LS	TRAFFIC CONTROL	641.10				
					1000					1000		LF	4 INCH WHITE LINE	646.20				
					1000					1000		LF	4 INCH YELLOW LINE	646.21				
								740		740		SY	GEOTEXTILE UNDER STONE FILL	649.31				
							320			320		SY	GEOTEXTILE FOR SILT FENCE	649.51				
							220			220		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515				
							140			140		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
							50			50		LB	SEED	651.15				
							10			10		LB	SEED, WINTER RYE	651.17				
							375			375		LB	FERTILIZER	651.18				
							2			2		TON	AGRICULTURAL LIMESTONE	651.20				
							2			2		TON	HAY MULCH	651.25				
							190			190		CY	TOPSOIL	651.35				
								360		360		SY	GRUBBING MATERIAL	651.40				
							1			1		LS	EPSC PLAN	652.10				
							250			250		HR	MONITORING EPSC PLAN	652.20				
							1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
							840			840		SY	TEMPORARY EROSION MATTING	653.20				
							20			20		CY	VEHICLE TRACKING PAD	653.35				
							530			530		LF	BARRIER FENCE	653.50				
							1190			1190		LF	PROJECT DEMARCATION FENCE	653.55				
					2					2		EACH	TRANSPLANTING SHRUBS	656.50				
					13.1					13.1		SF	TRAFFIC SIGNS, TYPE A	675.20				
					60					60		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
					60					60		EACH	REMOVING SIGNS	675.50				
					4					4		EACH	DELINEATOR WITH STEEL POST	676.10				
					4					4		EACH	REMOVAL OF EXISTING DELINEATOR	676.12				
					1					1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50				
					1					1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY)(N.A.B.I.)	900.650				
					1					1		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT)(N.A.B.I.)	900.650				
								390				SY	SPECIAL PROVISION (LONGITUDINAL DECK GROOVING)	900.675				

PROJECT NAME: BETHEL  
 PROJECT NUMBER: BHF 0214 (30)  
 FILE NAME: s95c002qty.252/236 gn PLOT DATE: 31-AUG-2011  
 PROJECT LEADER: M. EVANS-MONGEON DRAWN BY: M. LONGSTREET  
 DESIGNED BY: U. STANLEY CHECKED BY: U. STANLEY  
 QUANTITY SHEET 2 SHEET 7 OF 64