QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

APPROXIMATE SUMMARY OF QUANTITIES

R.O.W.			NON-GOV'T PARTICIPATING	GOV'T PARTICIPATING BRIDGE	GOV'T PARTICIPATING ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
					6	6	CY	COMMON EXCAVATION	203.15	--
					6	6	CY	SOLID ROCK EXCAVATION	203.16	--
					7	7	CY	TRENCH EXCAVATION OF EARTH	204.20	--
					8900	9000	SY	COLD PLANING - BITUMINOUS PAVEMENT	210.10	35
					1	1	TON	SUBBASE OF CRUSHED GRAVEL (FINE GRADED)	301.28	--
					10	10	TON	AGGREGATE SHOULDERS	402.12	EST
					22	22	CWT	EMULSIFIED ASPHALT	404.65	--
					1100	1100	TON	MEDIUM DUTY BIT. CONC. PAVEMENT	406.27	16
					1	1	EA	CHANGING ELEVATION OF DI's, CB's OR MH's	604.40	EST
					5	5	EA	REHABILITATION OF DI, CB OR MH CLASS I	604.412	EST.
					8	8	EA	REHABILITATION OF DI, CB OR MH CLASS II	604.415	EST.
					1	1	EA	REHABILITATION OF DI, CB OR MH CLASS III	604.418	EST.
					5	5	HR	POWER GRADER RENTAL	608.15	EST
					13	13	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST
					8	8	HR	POWER BROOM RENTAL	608.30	EST
					13	13	HR	TRUCK RENTAL	608.37	EST
					13	13	HR	LOADER RENTAL, TYPE I	608.40	EST
					13	13	TON	BIT. CONC. GUTTERS & TRAFFIC ISLANDS	616.47	--
					30	30	SY	PORTLAND CEMENT-CONCRETE SIDEWALK, 5 INCH	618.10	--
					2	2	EA	REPLACE GUARD RAIL BEAM UNIT	621.77	--
					150	150	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST
					300	300	HR	FLAGGERS	630.15	EST
					1	1	LS	TESTING EQUIPMENT - CONCRETE	631.16	--
					1	1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	--
					1	1	LS	MOBILIZATION	635.10	EST
					1225	1225	LF	DURABLE 4" WHITE LINES	646.40	--
					5250	5250	LF	DURABLE 4" YELLOW LINES	646.41	--
					130	130	LF	DURABLE 24" STOP BAR	646.46	--
					32	32	EA	DURABLE LETTER OR SYMBOL	646.50	--
					75	75	LF	DURABLE CROSSWALK W/DIAGONAL LINES	646.51	EST
					1225	1225	LF	TEMPORARY 4" WHITE LINE	646.60	EST
					5250	5250	LF	TEMPORARY 4" YELLOW LINE	646.61	EST
					130	130	LF	TEMPORARY 24" STOP BAR	646.66	EST
					32	32	EA	TEMPORARY LETTER OR SYMBOL	646.70	--
					75	75	LF	TEMPORARY CROSSWALK W/DIAGONAL LINES	646.71	--

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING - BITUMINOUS PAVEMENT
7943	SY	ALT ROUTE 5 STA 0+25 - 27+46
902	SY	SIDE STREETS
120	SY	DRIVES
35	SY	ROUNDING
9000	SY	TOTAL
		MEDIUM DUTY BIT. CONC. PAVEMENT
301	TON	ALT ROUTE 5 - LEVELING COURSE
662	TON	ALT ROUTE 5 - WEARING COURSE (TYPE III)
75	TON	SIDE STREETS
46	TON	DRIVES
16	TON	ROUNDING
1100	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

STATIONS FROM	STATIONS TO	PAVEMENT WIDTHS			EQUATIONS +	EQUATIONS -	FEET	MILES	REMARKS
TOTALS									

26-JUN-1996
QUANTITY SHEET
/pave/95c054/pc054.dgn pc054qsl.i

PROJECT NAME DERBY LINE
PROJECT NUMBER STP 9620(1)S

revised lsw 06/29/96
SHEET 3 OF 12 SHEETS

; Sheet Number: 3